

North – South Commuter Railway (NSCR) Project (Malolos – Tutuban) Package CP02: Elevated Structures and 3 Stations		
ITEM NO.	REFERENCE CLAUSE/ SECTION	REVISIONS/AMENDMENTS
<i>Volume II, Part 2 – Works Requirements</i>		
<i>GS 100</i>		
1	GS 100, Clause 113.1 General, Page GS-41	<p>The following texts are added after the last paragraph of Clause 113.1: “Regarding the foundation works or soil improvement works along the NSCR alignment, the Contractor should carry out necessary investigations to determine the presence of extraneous material such as old rails, machinery parts or other metallic scrap materials.</p> <p>The investigations shall be undertaken prior to the start of foundation construction in areas designated by the Engineer within the NSCR ROW. The investigations may be undertaken either by scarifying to a depth agreed with the Engineer within the foundation limits or by scanning with the use of a magnetometer device or by any other suitable methods the Contractor proposes and the Engineer approves.</p> <p>In the event such metallic materials are found, the situation shall be notified to PNR through the Engineer. Upon direction of the Engineer, the items shall be excavated, removed and then stockpiled for eventual transfer to PNR. Such cases shall therefore not be considered as unforeseen conditions.”</p>