



Republic of the Philippines
 Department of Budget and Management
PROCUREMENT SERVICE
BIDS AND AWARDS COMMITTEE



Supplemental/ Bid Bulletin No. 1
28 February 2019

PUBLIC BIDDING No. 19 – 063 – 4

Construction of (A) Naval Combat Engineering Brigade (NCEBde) Advance Command Post (320.4 Sqm) and (b) Amphibious Armour Battalion (AABn) Headquarters (426.5 Sqm) at Naval Station Leovigildo Gantioqui, San Antonio Zambales for the Philippine Navy (PN)

Issued pursuant to Sec. 22.5 of the IRR of R.A. 9184 to clarify and/or amend certain provisions in the Bidding Documents issued for this project, considering the issues raised and clarifications made by prospective bidders during the Pre-Bid Conference held on **February 27, 2019**.

I. AMENDMENTS

REFERENCE	BASES FOR AMENDMENT / INCLUSION										
SECTION I. INVITATION TO BID											
Page 4 X X X 6. The summary of the bidding activities is as follows: <table border="1" style="width: 100%;"> <thead> <tr> <th style="text-align: center;">X X X</th> <th style="text-align: center;">X X X</th> </tr> </thead> <tbody> <tr> <td>Last day of Submission of Written Clarifications</td> <td>March 4, 2019 March 8, 2018</td> </tr> <tr> <td>Last day of Issuance of Supplemental Bid Bulletin</td> <td>March 6, 2019 March 13, 2019</td> </tr> <tr> <td>Deadline of Submission and Receipt of Bids</td> <td>March 13, 2019; March 20, 2019 ; 10:00AM</td> </tr> <tr> <th style="text-align: center;">X X X</th> <th style="text-align: center;">X X X</th> </tr> </tbody> </table> X X X	X X X	X X X	Last day of Submission of Written Clarifications	March 4, 2019 March 8, 2018	Last day of Issuance of Supplemental Bid Bulletin	March 6, 2019 March 13, 2019	Deadline of Submission and Receipt of Bids	March 13, 2019 ; March 20, 2019 ; 10:00AM	X X X	X X X	<p><i>To amend the schedule of activities to give the prospective bidders ample time to prepare bids and to adjust minor changes in the BOQ.</i></p>
X X X	X X X										
Last day of Submission of Written Clarifications	March 4, 2019 March 8, 2018										
Last day of Issuance of Supplemental Bid Bulletin	March 6, 2019 March 13, 2019										
Deadline of Submission and Receipt of Bids	March 13, 2019 ; March 20, 2019 ; 10:00AM										
X X X	X X X										



REFERENCE	BASES FOR AMENDMENT / INCLUSION
SECTION III. BID DATA SHEET	
<p>ITB Clause 12.1(a)(i) Page 39</p> <p>xxx</p> <p>Notwithstanding the above requirements, the bidder may opt to submit the following eligibility documents in lieu of the submission of the PhilGEPS Certificate of Registration (Platinum Membership):</p> <ul style="list-style-type: none"> a. xxx b. <u>Mayor's Permit for 2019 or Mayor's Permit for 2018 accompanied by Official Receipt as proof that the bidder has applied and paid for the renewal of the permit within the prescribed period ;</u> c. xxx d. xxx e. xxx 	<p>To allow submission of proof of application and payment for the renewal of permit if Mayor's Permit for 2019 is not yet available.</p>
<p>ITB Clause 12.1(b)(ii.2) Page 40</p> <p>xxx</p> <p>Notes:</p> <ol style="list-style-type: none"> 1. Personnel <u>Health and Safety Officer</u> assigned should be different for each item/project except for Project Manager/Engineer. 2. xxx 	<p>To revise the requirement for better understanding.</p>
<p>ITB Clause 21 Page 42</p> <p>xxx</p> <p>The deadline for submission of bids is on March 13, 2019 <u>March 20, 2019</u> at 10:00AM.</p>	<p>Please refer to the discussions under Section I of A. Amendments.</p> <p style="text-align: right;"><i>FB</i></p>

For the purpose of this Bulletin and for better understanding of its contents, the following rules shall apply: (a) ~~Double Strike out~~ – denotes deletion; (b) Underline – denotes inclusion or new item/requirement; and "xxx" – denotes separation of phrase/s being amended from the rest of the main text.

REFERENCE	BASES FOR AMENDMENT / INCLUSION
SECTION V. SPECIAL CONDITIONS OF CONTRACT	
GCC Clause 6.5 Page 79 xxx The named Key Personnel shall not be assigned to other projects including projects by PN within Naval Station Leovigildo Gantioqui, San Antonio, Zambales. xxx	<p><i>To omit the provision for better understanding.</i></p>
SECTION VIII. BILL OF QUANTITIES	
Bill of Quantities Page 87	<p><i>The revised Bill of Quantities is hereby attached labeled as Attachment A.</i></p>

By Rules, all other related provisions in the Bidding Documents correspondingly affected by these amendments are likewise deemed amended to conform to this Bid Bulletin.

Amendments made herein shall be considered an integral part of the Bidding Documents.


ENGR. ESTRELLITA G. FULE
 Chairperson, BAC4 HW

For the purpose of this Bulletin and for better understanding of its contents, the following rules shall apply: (a) ~~Double Strike out~~ – denotes deletion; (b) Underline – denotes inclusion or new item/requirement; and "xxx" – denotes separation of phrase/s being amended from the rest of the main text.

BILL OF QUANTITIES

Construction of NCEBde (a) Advance Command Post (320.4 Sqm) and
(b) AABN Headquarters (426.65 Sqm) at NSLG, San Antonio Zambales
for the Philippine Navy (PN)

Public Bidding No. 19-063-4

CONSTRUCTION OF NCEBde ADVANCE COMMAND POST

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
I. EARTHWORKS	78.08	cu.m		
II. CONCRETE WORKS (73.46 cum)	73.46	cu.m		
III. REINFORCING STEEL BARS	6417.10	kgs		
IV. MASONRY WORKS	367.33	sqm		
V. FORMS AND SCAFFOLDINGS	100.80	sqm		
VI. DOORS AND WINDOWS	39.00	set		
VII. STRUCTURAL STEEL WORKS	7168.00	kgs		
VIII. TINSMITRY WORKS	423.52	sqm		
IX. CARPENTRY WORKS	423.08	sqm		
X. PLUMBING WORKS	31.00	set		
XI. PAINTING WORKS	1352.52	sqm		
XII. TILE WORKS	449.69	sqm		
XIII. ELECTRICAL WORKS				
Wire Electrical 100 sq mm THHN	150	mtrs		
Wire Electrical 38 sq mm THHN	25	mtrs		
Wire Electrical 22 sq mm THHN	25	mtrs		
Wire Electrical 14 sq mm THHN	150	mtrs		
Wire Electrical 8.0 sq mm THHN	300	mtrs		
Wire Electrical 5.5 sq mm THHN	600	mtrs		
Wire Electrical 3.5 sq mm THHN	1950	mtrs		
LED Tubular Bulb, 2X20W, Recessed-Type Mirrorized	27	sets		
LED Recessed Circular downlight w/ glass cover 4" dia., 12W pin lamp	56	sets		
Covenience Outlet, Duplex, Universal with ground Weatherproof	45	sets		
Covenience Outlet, Duplex, Universal with ground Weatherproof	4	sets		
Range Outlet	1	set		
1-Way, 1-Gang, Switch with plate cover	14	sets		
1-Way, 2-Gang, Switch with plate cover	8	sets		
1-Way, 3-Gang, Switch with plate cover	2	sets		
3-Way, 1-Gang, Switch	4	sets		
PVC Junction Box w/ Cover	73	pcs		
PVC Utility Box	80	pcs		
Utility Box, 4 x 4, metal	1	pc		
Pull Box 4" x 10" x 10"	2	sets		
Grounding Rod w/ Connector 3/4" x 10'	3	pcs		
PVC Pipe Clamp 20mm w/ nails	300	pcs		

H

20mm x 3m PVC Conduit Pipe	300	pcs		
20mm PVC Male Adaptor w/ Nut	500	sets		
Flexible Conduit Pipe, 20mm x 100m	2	rolls		
65mm x 3 m PVC Conduit Pipe	5	pcs		
65mm Male Adaptor w/ Nut	6	sets		
65mm PVC Elbow	6	pcs		
65mm PVC Coupling	2	pcs		
65mm dia. C-clamp, metal	20	pcs		
40mm x 3 m PVC Conduit Pipe	1	pc		
40mm Male Adaptor w/ Nut	3	sets		
40mm PVC Elbow	1	pc		
40mm PVC Coupling	1	pc		
32mm x 3 m PVC Conduit Pipe	1	pc		
32mm Male Adaptor w/ Nut	3	sets		
32mm PVC Elbow	1	pc		
32mm PVC Coupling	1	pc		
Entrance cap, 65mm.dia	1	pc		
100 sq mm Solderless Connector	6	pcs		
38 sq mm Solderless Connector	3	pcs		
22 sq mm Solderless Connector	3	pcs		
Duct Fan, 11" x 11", 250mm propeller 33W, 220V, 60Hz	8	sets		
LED Emergency Lamp, 2 x 3W	3	sets		
Electric Kilowatt Hour Meter, 3Φ class 200, 3W,240V, 30A	1	set		
Secondary rack, 4-wire	1	set		
Safety Breaker 200AT, 3P, 3Φ w/ Nema 3R Enclosure	1	set		
Feeder Panel Board Main Distribution:				
Panel, 2-Branches	1	set		
Main: 200AT, 3P, 3Φ, Bolt On, MCCB, 230V	1	set		
Branches: 70AT, 3P, 3Φ, Bolt On, MCCB, 230V	1	set		
125AT, 3P, 3Φ, Bolt On, MCCB, 230V	1	set		
PLP-1, Feeder Panel Board, 18-Branches, Bolt On	1	set		
Main: 70AT, 3P, 3Φ, Bolt On, MCCB, 230V	1	set		
Branches: 15AT, 2P, 1Φ, Bolt On, MCCB, 230V	8	sets		
20AT, 2P, 1Φ, Bolt On, MCCB, 230V	7	sets		
30AT, 2P, 1Φ, Bolt On, MCCB, 230V	1	set		
PLP-2, Feeder Panel Board, 10-Branches, Bolt On	1	set		
Main: 125AT, 3P, 3Φ, Bolt On, MCCB, 230V	1	set		
Branches: 20AT, 2P, 1Φ, Bolt On, MCCB, 230V	4	sets		
40AT, 2P, 1Φ, Bolt On, MCCB, 230V	4	sets		
TOTAL:				

AK

Name of Company

Signature Over Printed Name of
Authorized Representative

Date

11

BILL OF QUANTITIES

Construction of (a) NCEBde Advance Command Post (320.4 Sqm) and
(b) AABN Headquarters (426.65 Sqm) at NSLG, San Antonio Zambales
for the Philippine Navy (PN)

Public Bidding No. 19-063-4

CONSTRUCTION OF AABN HEADQUARTERS

DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL
I. EARTHWORKS	117.96	cu.m		
II. CONCRETE WORKS	107.94	cu.m		
III. REINFORCING STEEL BARS	10700.92	kgs		
IV. MASONRY WORKS	571.09	sqm		
V. FORMS AND SCAFFOLDINGS	135.68	sqm		
VI. DOORS AND WINDOWS	40.00	set		
VII. STRUCTURAL STEEL WORKS	9171.90	kgs		
VIII. TINSMITRY WORKS	685.55	sqm		
IX. CARPENTRY WORKS	546.05	sqm		
X. PLUMBING WORKS	25.00	set		
XI. PAINTING WORKS	2225.69	sqm		
XII. TILE WORKS	475.63	sqm		
XIII. ELECTRICAL WORKS				
Wire Electrical 80 sq mm THHN	200	mtrs		
Wire Electrical 22 sq mm THHN	150	mtrs		
Wire Electrical 8.0 sq mm THHN	300	mtrs		
Wire Electrical 5.5 sq mm THHN	600	mtrs		
Wire Electrical 3.5 sq mm THHN	1800	mtrs		
LED Recessed Tubular Bulb, 2X16W, w/ Aluminum Reflector	31	sets		
LED, Recessed Square Downlight, 4" dia, 7W Pin Lamp	19	sets		
LED Recessed Circular Downlight, 4" dia, 12W Pin Lamp	17	set		
LED Emergency Light 2 x 3W	3	set		
Universal Duplex Grounding Outlet w/ Plate Cover	34	sets		
Covenience Outlet, Duplex, Universal with Ground Weatherproof	4	sets		
ACU Outlet	10	sets		
1-Way, 1-Gang, Switch w/ Plate	15	sets		
1-Way, 2-Gang, Switch w/ Plate	9	sets		
1-Way, 3-Gang, Switch w/ Plate	2	sets		
PVC Junction Box w/ Cover	73	pcs		

PVC Utility Box	80	pcs		
Pull Box 4" x 8" x 8"	2	sets		
Grounding Rod w/ Connector 5/8"	1	pc		
PVC Pipe Clamp 20mm w/ nails	600	pcs		
20mm x 3m PVC Conduit Pipe	250	pcs		
20 mm PVC Elbow	20	pcs		
20 mm PVC Coupling	20	pcs		
20 mm PVC Male Adaptor w/ Nut	500	sets		
Flexible Conduit Pipe, 20mm x 100m	2	rolls		
50 mm x 3 m PVC Conduit Pipe	8	pcs		
50 mm Male Adaptor w/ Nut	6	sets		
50 mm PVC Elbow	6	pcs		
50 mm dia. C-clamp, metal	20	pcs		
50 mm PVC Coupling	10	pcs		
Entrance cap, 50mm.dia	1	pc		
80 sq mm Solderless Connector	6	pcs		
22 sq mm Solderless Connector	3	pcs		
Plastic Moulding, 3/4" x 8'	12	pcs		
Duct Fan, 11" x 11", 250mm Propeller, 33W, 230V, Ceiling-Mounted	1	set		
4-Wire Heavy Duty Secondary Rack w/ Spool Insulator	2	set		
KW-Hour Meter, 3Phase, Electronic CL200, 240, 30A	1	set		
Safety Breaker 200AT, Nema 3R Enclosure	1	set		
Main Panel Board, 24 Branches	1	set		
Main: 200AT, 3P, 3Φ, Bolt On, MCCB, 230V	1	pc		
Branches: 15AT, 2P, 1Φ, Bolt On, MCCB, 230V	5	pc		
20AT, 2P, 1Φ, Bolt On, MCCB, 230V	8	pc		
30AT, 2P, 1Φ, Bolt On, MCCB, 230V	8	pc		
40AT, 2P, 1Φ, Bolt On, MCCB, 230V	3	pc		
			Sub - TOTAL:	

Temporary Facilities	1	Lot		
Health & Safety	1	Lot		
Mobil/demobil, 1% of MC + LC	1	Lot		
			Sub - TOTAL:	
TOTAL AMOUNT:				

Name of Company	Signature Over Printed Name of Authorized Representative	Date
		