

Metro Manila Subway Project Phase 1 PACKAGE CP104 (Ortigas North and Ortigas South)		
ITEM NO.	REFERENCE CLAUSE/SECTION	ADDENDUM No. 14

Volume IA Part 1: Bill of Quantities (BOQ)
Section IV Bidding Form Bill of Quantities (BOQ)

	Reference	Corrected, Supplemented or Modified
1.	Bill of 6A,6B,7A,7B	Please replace BILL OF QUANTITIES (a Part of Section IV. Bidding Forms) Work Items - Bill No. 6 and Bill No. 7

Volume III Part 2 : Works Requirements
Section VI Works Requirements General Specification Appendix 8 Digital Engineering Employer's Information Requirements

2.	Section VI Works Requirement Appendix 8 Item 2.2 page 30– Licensing Requirements	Please replace the minimum users of Projectwise Construction Management to 5 users.		
		Software	Minimum Users	New Minimum Users
		Projectwise 365 Visa	30	30
		Projectwise Design Integration Visa	20	20
		Projectwise Construction Management	10	5
		Synchro	5	5
		ComplyPro	5	5

Volume III Part 2 : Works Requirements
Section VI Works Requirements Employer's Drawings (DRW)

	Reference	Corrected, Supplemented or Modified
3.	SPL-PB1-S-ON-3001: ORTIGAS NORTH STATION PEDESTRIAN BRIDGE 1	Please replace the phrase as below.

Metro Manila Subway Project Phase 1 PACKAGE CP104 (Ortigas North and Ortigas South)		
ITEM NO.	REFERENCE CLAUSE/SECTION	ADDENDUM No. 14
Volume IA Part 1: Bill of Quantities (BOQ) Section IV Bidding Form Bill of Quantities (BOQ)		
	Reference	Corrected, Supplemented or Modified
	GENERAL NOTES & ABBREVIATIONS - SHT 1 OF 3	4.1 Foundation design was based on 300 kpa soil bearing capacity (based on the nearest borehole location) at 3.0m/2.0m depth from natural grade line or existing ground level. The contractor shall be responsible to verify/make adjustment on foundation design The contractor shall verify on <u>foundation design conditions</u> prior to construction and will be subject to engineer's review and approval.
4.	STN-AR-A-ON/OS-9010	Please replace the number in Mark of STN-AR-A-ON/OS-9010 FCF-01 & FCF-03 FCF-02 & FCF-03
5.	STN-AR-A-ON/OS-9250	Please replace the phrase in Description of GL-05 in finishing schedule as below: 12 mm thick toughened glass with frosted film 12 mm thick toughened glass with design film.
6.	Ortigas South Station Plaza	Ortigas South Station Plaza Replace the drawing below: <ul style="list-style-type: none"> - SPL-C-F-OS-1014 - SPL-C-RD-ON-1033 - SPL-C-RD-ON-1034 - SPL-C-SP-OS-1012 - SPL-C-SP-OS-1013 - SPL-PB1-A-ON-2015 See Annex C for the details

