



#### General Bid Bulletin No. 16 March 25, 2021

IFB NO. 20-031-6

#### SOUTH COMMUTER RAILWAY PROJECT FOR PACKAGES CP S-04, CP S-05, AND CP S-07 CONSTRUCTION OF CIVIL STRUCTURES: VIADUCTS, BRIDGES, NINE (9) STATIONS AND DEPOT

#### TO ALL PROSPECTIVE BIDDERS:

This General Bid Bulletin is issued to amend/clarify certain provisions in the Bidding Documents for the abovementioned project. Please refer to the attached **Annex A** of this General Bid Bulletin duly approved by the End-user and Co-Implementer for details:

- 1. Annex "A" CP S-04 to 07 Responses to Clarifications Requests (Batch 8)
- 2. For Addendum 2, please follow the link: https://drive.google.com/drive/folders/15NiHJX6ZwJPpUKHVVTXwU3XRjKI6deIQ

For your information and guidance.

For the Bids and Awards Committee VI,

(SGD) WEBSTER M. LAUREÑANA Chairperson

| Packages | Vol | Sec                          | Page No. | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request   |  |
|----------|-----|------------------------------|----------|---|--|--|--|
| S-04     | 1   | Section 4<br>Bidding form    | Page 19  | Key personnel   |  | Regarding experience of BIM Coordinator, a project requires 12<br>years as total work experience.<br>Please clarify that this total 12 years experience means<br>construction work or only for BIM work. | Please refe  |
| S-04     | 3   | Volume 3<br>Section 8<br>PCC | PCC-4    | Part A – Contract<br>Data<br>14.1                                     | The following sentence under Clause<br>14.1 shall not apply:<br>Notwithstanding the provisions of<br>subparagraph (b), Contractor's<br>Equipment, including essential spare<br>parts therefor, imported by the<br>Contractor for the sole purpose of<br>executing the Contract shall be<br>exempt from the payment of import<br>duties and taxes upon importation. | Does this reference test means import duties and taxes should be<br>imposed to all items which imported for the Work? And bidder<br>should include that tax in the bid price?                            | The Contra<br>Contractor<br>be imported<br>Certificate |
| S-04     | 2   | Sec.6                        | GS17     | 108.2<br>Vehicles and<br>Motorcycles for the<br>Engineer's Inspectors | remain available until the end of the  |  | Bidder is re<br>Addendum                               |
| S-05     | 3   | Section 8<br>PCC             | PCC-4    | Part A – Contract<br>Data<br>14.1                                     | The following sentence under Clause<br>14.1 shall not apply:<br>Notwithstanding the provisions of<br>subparagraph (b), Contractor's<br>Equipment, including essential spare<br>parts therefor, imported by the<br>Contractor for the sole purpose of<br>executing the Contract shall be<br>exempt from the payment of import<br>duties and taxes upon importation. | Does this reference test means import duties and taxes should be<br>imposed to all items which imported for the Work? And bidder<br>should include that tax in the bid price?                            | The Contra<br>Contractor<br>be imported<br>Certificate |
| S-05     | 2   | Sec.6                        | GS17     | 108.2<br>Vehicles and<br>Motorcycles for the<br>Engineer's Inspectors | The vehicles and motorcycles shall be<br>solely for the use of the Employer and<br>the Engineer and shall<br>remain available until the end of the<br>Defects Notification Period.   |  | Bidder is re<br>Addendum                               |
| S-06     | 3   | Section 8<br>PCC             | PCC-4    | Part A – Contract<br>Data<br>14.1                                     | The following sentence under Clause<br>14.1 shall not apply:<br>Notwithstanding the provisions of<br>subparagraph (b), Contractor's<br>Equipment, including essential spare<br>parts therefor, imported by the<br>Contractor for the sole purpose of<br>executing the Contract shall be<br>exempt from the payment of import<br>duties and taxes upon importation. | Does this reference test means import duties and taxes should be<br>imposed to all items which imported for the Work? And bidder<br>should include that tax in the bid price?                            | The Contra<br>Contractor<br>be imported<br>Certificate |

| Final Response  |
|---|
| fer to Addendum 2.  |
| ractor does not pay for import taxes.<br>or needs to submit in advance a list of items to<br>ted monthly to DOTr, then DOTr will issue a<br>e of Undertaking to the Bureau of Customs.  |
| referred to revised GS Appendix 5 in<br>m 2   |
| ractor does not pay for import taxes.<br>or needs to submit in advance a list of items to<br>ted monthly to DOTr, then DOTr will issue a<br>te of Undertaking to the Bureau of Customs. |
| referred to revised GS Appendix 5 in<br>m 2   |
| ractor does not pay for import taxes.<br>or needs to submit in advance a list of items to<br>red monthly to DOTr, then DOTr will issue a<br>re of Undertaking to the Bureau of Customs. |

| Packages | Vol | Sec  | Page No. | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request   |   |
|----------|-----|--|----------|---|--|--|---|
| S-06     | 2   | Sec.6  | GS17     | 108.2<br>Vehicles and<br>Motorcycles for the<br>Engineer's Inspectors | remain available until the end of the  | Please provide the exact numbers of vehicles and motorcycles during the Defects Notification Period.   | Bidder is ro<br>Addendum                              |
| S-07     | 1   | Section 3<br>Evaluation and<br>Qualification<br>Criteria (EQC) | EQC 23   | 2.4.1 Contracts of<br>Similar Size and<br>Nature                      | 3. At-grade/elevated land transport depot project constructed on a filled site.  | What is the definition of land transport depot and what are the components? We have a land transport facility where our delivery trucks, equipment, vehicles are housed with maintenance and fuel support facilities. Will this qualify? Please confirm.                   | Please refe<br>Addendum<br>depot for la<br>requiremen |
| S-07     | 1   | Section 3<br>Evaluation and<br>Qualification<br>Criteria (EQC) | EQC 23   | 2.4.1 Contracts of<br>Similar Size and<br>Nature                      | 3. At-grade/elevated land transport depot project constructed on a filled site.  | Railway Depot is a maintenance facility with administration<br>offices. Can a steel fabrication plant with land transport and<br>maintenance facility, administration building and offices qualify<br>as a land transport depot equivalent? Please confirm.                | Steel fabric<br>transport d                           |
| S-07     | 1   | Section 3<br>Evaluation and<br>Qualification<br>Criteria (EQC) | EQC 24   | Clause 2.4.2<br>Construction<br>Experience in Key<br>Activities       | ÷  | What is the definition of a retaining structure at least 8 m high?<br>Can this be a steel sheet pile, reinforced concrete retaining wall,<br>diaphragm wall, water reservoir, basement concrete walls of a<br>building, rock slope protection or sea wall? Please confirm. | Please refe<br>Addendum                               |
| S-07     | 1   | Section 3<br>Evaluation and<br>Qualification<br>Criteria (EQC) | EQC 24   | Clause 2.4.2<br>Construction<br>Experience in Key<br>Activities       | 2. At least one (1) project that<br>included major filling with selected<br>material of at least 750,000 m3 and<br>7.5m deep including compaction in<br>layers within a 3 year period. | This project reference caters to a reclamation project more than a railway depot. The filling works whether it is a 3m or 7.5m deep embankment has the same methodology of filling and compaction. Please consider a minimum of 3m high filling works. Please confirm.     | Please refe<br>Addendum                               |
| S-07     | 1   | Section 4  | BF 39    | BIM and CMMS<br>Implementation  | The Contractor is required to develop<br>the BIM to level LOD 500 for as-built<br>drawings()   | What is the exact definition of level LOD 500? Please provide<br>guideline, specification and/or sample LOD 500 model to clarify<br>the level of detail that the as-built deliverables should comply<br>with.  | BIM Mana<br>part of Add                               |

| Final Response  |
|---|
| referred to revised GS Appendix 5 in<br>n 2   |
| fer to the revised EQC to be issued under<br>n 2. The quoted facility can be defined as a<br>land transport, but please take note of other<br>ents as well. |
| ication plant cannot be defined as a land<br>depot project  |
| fer to revised EQC to be issued under<br>n 2  |
| fer to revised EQC to be issued under<br>n 2  |
| agement Information Flow document will be<br>Idendum 2 as GS Appendix 15.   |

| Packages | Vol | Sec       | Page No. | Clause No./Title  | Reference Text<br>(if necessary)  | Clarification<br>Request  |   |
|----------|-----|-----------|----------|---|---|---|---|
| S-07     | 1   | Section 4 | BF 39    | BIM and CMMS<br>Implementation                            | The Contractor is required to develop<br>the BIM to level LOD 500 for as-built<br>drawings()  | According to ITB, the Employer will provide BIM design at level<br>LOD 300<br>1.Is it 2-D design or 3-D design?<br>2.Which SW program is used for BIM design LOD 300?<br>(ex. AUTODESK Revit)<br>3.Which information is included in LOD 300 and how much is<br>detail information included?<br>Ex) assembly accurate, sequences in terms of quantity, size,<br>shape, location, and orientation and etc, except installation<br>information.<br>During the construction stage, Contractor shall manage the<br>PMIS/CMMS based on Aconex as specified in Appendix 9. Does<br>the bidder understand correctly?  | BIM Mana<br>part of Add   |
| S-06     | 1   | Section 3 | EQC 25   | 2.4.2/<br>Construction<br>Experience in Key<br>Activities | If the Bidder's construction<br>experience is a part of a prior Joint<br>Venture, only the Bidder's designated<br>scope of works, under the contracts<br>presented to satisfy the requirements<br>stated here, shall be considered to<br>meet this requirement.   | Regarding this clause, the bidder has a satisfied construction<br>experience as a JV Leader with more than 50% of share. During<br>the construction period, the bidder managed and controlled the<br>whole works including Key activities and overall site operation<br>of the project as a leading company.<br>However, if the bidder's portion is only arithmetically applied<br>on the experience, the applied experience record slightly does not<br>meet the required numbers.<br>(e.g. Bidder has a viaduct construction experience more than<br>6km as a JV Leader with 55% of share.)<br>In this case, please confirm that the bidder's Key Activities are<br>satisfied.  | If the Bidde<br>Joint Ventu<br>and the Bid<br>works in the<br>experience<br>stated here.<br>full details<br>the Joint Ve<br>here. |
| S-06     | 1   | Section 3 | EQC 25   | 2.4.2/<br>Construction<br>Experience in Key<br>Activities | <requirement><br/>For the above or other contracts<br/>executed during the period stipulated<br/>in 2.4.1 above, a minimum<br/>construction experience in the<br/>following key activities:<br/>4. Viaduct works for Railway or<br/>Road (Expressway or Motorway)<br/>more than 4 km using precast<br/>segmental span by span techniques.<br/>Relevant works will also include<br/>bored or precast piling and<br/>construction of reinforced concrete<br/>pile caps and piers.</requirement> | The Requirement 4 of the construction experience in key activity<br>in Clause 2.4.2, Section 3 Evaluation and Qualification, which is<br>the requirement of construction experience for Viaduct works,<br>states as in the left column.<br>Normally, a Specialist Subcontractor for Viaduct works has an<br>experience of Viaduct work only and does not have enough<br>experience of the substructure works such as bored or pre-cast<br>piling, R/C pile caps and piers.<br>Is it all right that the experience of the Viaduct works relied on<br>the Specialist Subcontractor and the experience of the<br>substructure works relied on the Bidder or another Specialist<br>Subcontractor?<br>(e.g. Specialist Subcontractor A for superstructure works +<br>Bidder or another Specialist Subcontractor B for substructure<br>works at each different project) | Please refe   |
| S-05     | 1   | Sec.4     | 45       | BIM and CMMS<br>Implementation                            | BIM design at level LOD300  | What Authoring Tool was used to create the design model for<br>LOD300? (ex. Autodesk Revit, Bentley OpenRail, Tekla etc)  | The success<br>compatible<br>Engineer's<br>Autodesk R   |

nagement Information Flow document will be ddendum 2 as GS Appendix 15.

Ider's construction experience is as a Lead nure partner in an Integrated Joint Venture Bidder has been managing in all aspects of the the contract, the Bidder may claim the ce in such contract to satisfy the requirement re. Otherwise, the Bidder shall demonstrate in ls that Bidder's designated scope of works in Venture can satisfy the requirement stated

fer to revised EQC issued under Addendum 2

essful Contractor shall utilize software which is le with, interoperable, and equivalent, with the 's with the software programme (currently Revit 2020)

| Packages | Vol | Sec       | Page No. | Clause No./Title                | Reference Text<br>(if necessary) | Clarification<br>Request   |   |
|----------|-----|-----------|----------|---------------------------------|----------------------------------|--|---|
| S-05     | 2   |           |          |                                 | BIM Requirement                  | Detailed BIM Requirements are missing within the GS. Please<br>clarify the requirements of BIM.  | BIM Mana<br>part of Ada   |
| S-06     | 1   | Sec.4     | 45       | BIM and CMMS<br>Implementation  | BIM design at level LOD300       | According to "BIM and CMMS Implementation", Contractor<br>must update the design model of the LOD300 to the As-built<br>model of the LOD500 after the award.<br>If we can see the current status of the LOD300 design model that<br>we have to update after the award, we can accurately plan the<br>model development and calculate the cost of input.<br>Can you share the design model of the LOD300? | LOD 300 n   |
| S-06     | 1   | Sec.4     | 45       | BIM and CMMS<br>Implementation  | BIM design at level LOD300       | What Authoring Tool was used to create the design model for LOD300? (ex. Autodesk Revit, Bentley OpenRail, Tekla etc)  | The succes<br>compatible<br>Engineer's<br>Autodesk K  |
| S-06     | 2   |           |          |                                 | BIM Requirement                  | Detailed BIM Requirements are missing within the GS. Please clarify the requirements of BIM.   | BIM Mana<br>part of Ada   |
| S-06     | 2   | Section 6 |          | DWG: NSRP-DWG-<br>VIA00-ST-1271 |                                  | Please kindly advise the extent where noise barrier should be installed on the viaduct structures.   | There is no<br>Note compa<br>noise impa<br>of the EIS<br>Project (Ap<br>Conditions<br>Bidding Do<br>Analysis Ro |

nagement Information Flow document will be ddendum 2 as GS Appendix 15.

model will be provided to the winning Bidder.

essful Contractor shall utilize software which is le with, interoperable, and equivalent, with the 's with the software programme (currently Revit 2020)

nagement Information Flow document will be ddendum 2 as GS Appendix 15.

no noise barrier in CPS-06.

aprehensive study was carried out to assess bacts from the proposed Project. Section 3.3.3 S discusses the Noise assessment for the SC Appendix 6D – Baseline Environmental ns, Impact Assessment & Mitigation of the Documents). The detailed Noise and Vibration Report refer to Annex Volume III of the EIS.

|        |        |  |  |  |   | farmeation Requests (Daten 0)   |  |
|--------|--------|--|--|--|---|---|--|
| Packag | es Vol | Sec  | Page No.   | Clause No./Title   | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |
| S-04   | 2      | 2.2 SCRP<br>General<br>Specification                                     | GS 46  | 117.4 The<br>Contractor's Site<br>Safety Plan                                      | As a part of the Bid, the Contractor<br>shall provide an outline "Site Safety<br>Plan" (as described within ITB<br>Technical Proposal Requirements: I-<br>Safety Management, based upon the<br>requirements of this Specification and<br>Appendix 3 hereto, and the<br>"Guidance for the Management of<br>Safety for Construction Works"<br>published by the Japan International<br>Cooperation Agency (JICA), and<br>demonstrate how that will be<br>developed for this Package to make it<br>site specific. | Please confirm if Safety Management will be based on<br>"Guidance for the Management of Safety for Construction<br>Works" published by the JICA   | Safety Ma<br>a) Local G<br>b) JICA G<br>Constructa<br>c) ADB En<br>Which are<br>Guidelines |
| S-07   | 1      | Section No.3   | Page No. 60<br>(EQC 23)                          | 2.4.1 Contracts of<br>Similar Size and<br>Nature                                   | 1. Road or Railway project of<br>continuous nature, where the value of<br>the Bidder's participation exceeds<br>One Hundred and Fifty Million<br>US Dollars (US\$ 150,000,000).   | Does the Criteria of "the value of \$150 million US Dollars" apply<br>to Road or Railway projects, or is it limited to "The similar work<br>(iii)" and so, only Depots projects with similar construction<br>characteristics?   |  |
| S-07   | 1      | Part I<br>Section 3<br>Evaluation and<br>Qualification<br>Criteria (EQC) | EOC 23 (page<br>60/63)<br>EOC 24 (page<br>61/63) | 2.4 Construction<br>Experience<br>2.4.1 Contracts of<br>Similar Size and<br>Nature | 7   | <ul> <li>2.4.1 Contracts of Similar Size and Nature<br/>For the similar work as specified in EOC, ITD hasn't been<br/>successfully or substantially completed within in last ten years.<br/>as requirements, the bidder shall have 3 ma<br/>Question</li> <li>1. Shall the similar works be necessary including in one<br/>contract?</li> <li>2. Could we please to proposed our project J.2307 Construction<br/>of Satellite Building (B2,B1 and G Floor),Aircraft Aprons and<br/>South Tunnel Extension for Suvarnabhumi Airport Expansion<br/>Project? And we pleased to inform our project J.2307 detail both<br/>the certificate of completion and List of project reference table<br/>that the contract price is more than 150 MUSD)</li> </ul> | Please refo<br>2   |


Management shall be based on the following: I Occupational Safety and Health Standards; Guidance for Management of Safety for action Works; and Environment Safeguards.

tre detailed contents of the IFC General EHS nes referenced as applicable in GS 117.


refer to revised EQC to be issued under Jum 2

efer to the revised EQC issued under Addendum

| Packages | Vol  | Sec  | Page No.   | Clause No./Title  | Reference Text<br>(if necessary)  | Clarification<br>Request   |                  |
|----------|--|--|--|---|---|--|------------------|
| S-07     | 1  | Part I<br>Section 3<br>Evaluation and<br>Qualification<br>Criteria (EQC) | EOC 23 (page<br>60/63)<br>EOC 24 (page<br>61/63) | 2.4 Construction<br>Experience<br>2.4.2 Construction<br>Experience in Key<br>Activities | For the above or other contracts<br>executed during the period stipulated<br>ih 2.4.1 above, a minimum<br>construction experience in the<br>following key activities:<br>1. Construction of major retaining<br>structures at least 8m high of at least<br>500 m length<br>2. At least one (1) project that<br>included major filling with selected<br>material of at least 750,000 cu.m. 7.5<br>m deep including compaction in<br>layers within a 3 year period<br>3. Construction of at least 10,000<br>cu.m. ground floor area of concrete<br>framed buildings on deep filled sites<br>using piled foundation | <ul> <li>2.4.2 Construction Experience in Key Activities</li> <li>Question</li> <li>1.For the Key Activities article 2 , Could we please to proposed our project Construction of Satellite Building (B2,B1 and G Floor), Aircraft Aprons and South Tunnel Extension for</li> <li>Suvarnabhumi Airport Expansion Project? (see attactment for CP S-07 clause : Construction Experience in key activities article 2)</li> <li>2.For the Key Activities article 2 , Could we please to proposed our project job no. 1135 Construction of Ground Improvement for Airside Pavement (November 1997- April 2002)? (Provided in PDF file " List of Reference Project.pdf ")</li> </ul> | Please refe<br>2 |
| S-07     | Volume -1<br>(Part-1)<br>Bidding<br>procedures | Section 3  | EQC-23   | 2.4.1 - Construction<br>Experience-<br>Contracts of Similar<br>Size & Nature            | Participation as a contractor, JV<br>partner, or subcontractor, in at least<br>one contract At-<br>grade/elevated land transport Depot<br>project constructed on a filled site  | <ul> <li>Kindly confirm that the identified 03 activities in this clause viz a viz 1. Road or Railway project of continuous nature, where the value of the Bidder's participation exceeds One Hundred and Fifty Million US Dollars (US\$ 150,000,000).</li> <li>2. A civil works contract including earth works and concrete works of minimum Twenty Million US\$ Dollars (US\$20,000,000).</li> <li>3. At-grade/elevated land transport Depot project constructed on a filled site. can also be met through 02 or 03 different contracts but each activity met through single contract.</li> </ul>  | Please refe      |
| S-07     | Volume -1<br>(Part-1)<br>Bidding<br>procedures | Section 3  | EQC-23   | 2.4.1 - Construction<br>Experience-<br>Contracts of Similar<br>Size & Nature            | Participation as a contractor, JV<br>partner, or subcontractor, in at least<br>one contract At-<br>grade/elevated land transport Depot<br>project constructed on a filled site  | We request for activity No. 3 depot construction for Modern<br>Railway Coach factory should also be allowed for the work of<br>similar physical size & complexity. As Modern Railway Coach<br>factory construction also involves construction of large span Pre-<br>Engineered sheds, circulating areas, staff amenities, road, MEP<br>works, Instrumentation (supply, testing & commissioning) etc.   | Please refe      |
| S-07     | Volume -1<br>(Part-1)<br>Bidding<br>procedures | Section 3  | EQC-24   | 2.4.2 - Construction<br>Experience-<br>Construction<br>Experience in Key<br>Activities  | For the above or other contracts<br>executed during the period stipulated<br>in 2.4.1 above, a minimum<br>construction experience in the<br>following key activities: 1.<br>Construction of major retaining<br>structures at least 8m high of at least<br>500 m length  | We request that minimum length requirement of 500 m in this<br>clause may be reduced to 250 m as agency capable of<br>construction 250 m long retaining wall can always construct<br>longer length as it just need augmentation of same kind of<br>resources, as required for shorter length.  | Please refe      |




| Packages | Vol  | Sec        | Page No. | Clause No./Title   | Reference Text<br>(if necessary)   | Clarification<br>Request   |                  |
|----------|--|------------|----------|--|--|--|------------------|
| S-07     | Volume -1<br>(Part-1)<br>Bidding<br>procedures | Section 3  | EQC-24   | 2.4.2 - Construction<br>Experience-<br>Construction<br>Experience in Key<br>Activities | For the above or other contracts<br>executed during the period stipulated<br>in 2.4.1 above, a minimum<br>construction experience in the<br>following key activities: 3.<br>Construction of at least 10,000 m3<br>ground floor area of concrete framed<br>buildings on deep filled sites using<br>piled foundation             | Kindly clarify whether the requirement in this clause is for at<br>least 10,000 Sqm of ground floor area or at least 10,000 Cum of<br>concrete at Ground floor level. We request concrete framed<br>buildings and/or Pre- Engineered buildings on deep filled sites<br>should be considered in this key activity. Kindly confirm this<br>requirement can be met through more than one contract during<br>the stipulated period.  | Please refe      |
| S-06     | 1  | 3          | EQC 25   | 2.4.2/<br>Construction<br>Experience in Key<br>Activities                              | 4 km using precast segmental span by   | <ul> <li>The bidder is considering to organize the JV with 2 members (e.g. A &amp; B).</li> <li>A member meet a part of Requirement 4 in 2.4.2 Construction Experience in Key Activities. (Only Superstructure : Viaduct works for Railway or Road (Expressway or Motorway) more than 4 km using precast span by span techniques.)</li> <li>B member meet a part of Requirement 4 in 2.4.2 Construction Experience in Key Activities. (Only Substructure : bored or precast piling and construction of reinforced concrete pile caps and piers)</li> <li>Bidders understand that the JV(A&amp;B) meet the Requirement 4 of 2.4.2 in Evaluation and Qualification Criteria. Please clarify it.</li> </ul>   | Please refe<br>2 |
| S-05     | 1A   | Section 4A | -        | GS118(4)<br>PS-1   | GS118(4)<br>Time related charges for<br>Archaeological Monitoring<br>PS-1<br>Archeological Monitoring<br>The Contractor shall be responsible<br>for the charges and fees imposed for<br>the measures and/or works deemed<br>necessary in the event of discovering<br>archeological interest on site. (Refer<br>to GS 118.9.3). | The item number GS118(4) of the Bill No.1 is deemed to be<br>included in PS-1 of the Provisional sum. However, the item is not<br>indicated "Provisional sum" on the Bill No.1. If a coverage of<br>these 2 items is different, please clarify the coverage of each<br>item.<br>Most of the structures and the bridges shown on a list of the<br>Appendix 2 are deemed to be included in the Provisional Sum.<br>Please clarify the structures which are included in the Provisional<br>Sum.<br>GS119 and GS133 of Bill No.1 are indicated as "Included in<br>other BOQ items". But there are subordinate items belong to<br>GS119 and GS133. Please clarity whether the subordinate items<br>are deemed to be included in other BOQ, or the subordinate<br>items shall be priced.<br>Between P717 and 718, the piles, pile-caps and columns of<br>station locates on the road. Clarification to the arrangement is<br>required. | 1. Correlat      |



| Packages | Vol | Sec        | Page No. | Clause No./Title                                | Reference Text<br>(if necessary)  | Clarification<br>Request   |  |
|----------|-----|------------|----------|---|---|--|--|
| S-05     | 2   | Section 6  | -        | Appendix 2                                      | SCRP CP S-05 - List of Historical<br>Sites - Database   | Most of the structures and the bridges shown on a list of the<br>Appendix 2 are deemed to be included in the Provisional Sum.<br>Please clarify the structures which are included in the Provisional<br>Sum.   | 1. Correlati<br>historic stru<br>advised to l<br>2. The Bid<br>caps and co<br>shown in N |
| S-06     | 1A  | Section 4A | -        | GS118(4)<br>PS-1                                | GS118(4)<br>Time related charges for<br>Archaeological Monitoring<br>PS-1<br>Archeological Monitoring<br>The Contractor shall be responsible<br>for the charges and fees imposed for<br>the measures and/or works deemed<br>necessary in the event of discovering<br>archeological interest on site. (Refer<br>to GS 118.9.3).  | The item number GS118(4) of the Bill No.1 is deemed to be<br>included in PS-1 of the Provisional sum. However, the item is not<br>indicated "Provisional sum" on the Bill No.1. If a coverage of<br>these 2 items is different, please clarify the coverage of each<br>item.<br>Most of the structures and the bridges shown on a list of the<br>Appendix 2 are deemed to be included in the Provisional Sum.<br>Please clarify the structures which are included in the Provisional<br>Sum.<br>GS119 and GS133 of Bill No.1 are indicated as "Included in<br>other BOQ items". But there are subordinate items belong to<br>GS119 and GS133. Please clarity whether the subordinate items<br>are deemed to be included in other BOQ, or the subordinate<br>items shall be priced.<br>Between P717 and 718, the piles, pile-caps and columns of<br>station locates on the road. Clarification to the arrangement is<br>required. | 1. Correlati   |
| S-07     | 2   | Section 6  | Page 3   | Sketch 5.1.2.1 -<br>Engineer's Office<br>Layout |   | It mentions that "the Contractor shall provide suitable temporary<br>accommodation to be agreed by the Engineer"<br>Please clarify that how many numbers of temporary<br>accommodation shall be provided and how is the required quality<br>of temporary accommodation (Temporary on Site or<br>accommodation nearby Project Site?)  | Bidder is re<br>Addendum   |
| S-07     | 1   | Vol.1 Sec3 | EQC23    | Criteria-<br>Requirement in the<br>schedule     | The similar work(iii) shall mean a<br>project including the following<br>works:<br>1. Road or Railway project of<br>continuous nature, where the value of<br>the bidder's participation exceeds<br>One Hundred and Fifty Million US<br>Dollars (US\$ 150,000,000)<br>2. A civil works contract including<br>earth works and concrete works of<br>minimum twenty Million US\$ Dollars<br>(US\$ 20,000,000)<br>3. At-grade/elevated land transport<br>Depot project constructed on a filled<br>site | Three different types of work (1, 2, and 3 as in the<br>schedule) were suggested to explain the meaning of the<br>'similar work'<br>Please clarify if a single project should meet all these three<br>requirements. In other words, please confirm if a single<br>project which contains either of those three different works<br>in its scope can be deemed as compliant with experience<br>requirement.  | Please refe<br>Addendum<br>Please note<br>contract/pr                                    |

| tructures is under reassessment and will be<br>obidders in addendum 3.<br>idder's clarification request, re: the piles, pile-<br>columns of station locates on the road as<br>NSRP-DWG-VIA05-ST-0016 Rev 21<br>thion between BOQ and Provision Sums for<br>tructures is under reassessment and will be<br>obidders in addendum 3.<br>idder's clarification request, re: the piles, pile-<br>columns of station locates on the road as<br>NSRP-DWG-VIA05-ST-0016 Rev 21<br>referred to revised GS Appendix 5 in<br>m 2<br>fer to revised EQC to be issued under<br>m 2.<br>te that the Bidder shall have a single | Final Response   |
|--|--|
| tructures is under reassessment and will be<br>bidders in addendum 3.<br>idder's clarification request, re: the piles, pile-<br>columns of station locates on the road as<br>NSRP-DWG-VIA05-ST-0016 Rev 21<br>referred to revised GS Appendix 5 in<br>m 2<br>fer to revised EQC to be issued under<br>m 2.   | ation between BOQ and Provision Sums for<br>tructures is under reassessment and will be<br>bidders in addendum 3.<br>idder's clarification request, re: the piles, pile-<br>columns of station locates on the road as<br>NSRP-DWG-VIA05-ST-0016 Rev 21 |
| m 2<br>fer to revised EQC to be issued under<br>m 2.<br>the that the Bidder shall have a single  | ation between BOQ and Provision Sums for<br>tructures is under reassessment and will be<br>bidders in addendum 3.<br>idder's clarification request, re: the piles, pile-<br>columns of station locates on the road as<br>NSRP-DWG-VIA05-ST-0016 Rev 21 |
| m 2.<br>te that the Bidder shall have a single   | referred to revised GS Appendix 5 in<br>m 2  |
|  | fer to revised EQC to be issued under<br>m 2.<br>The that the Bidder shall have a single<br>project meeting all the requirement.   |

| Packages | Vol | Sec        | Page No. | Clause No./Title                             | Reference Text<br>(if necessary)   | Clarification<br>Request  |                          |
|----------|-----|------------|----------|--|--|---|--------------------------|
| S-07     | 1   | Vol.1 Sec3 | EQC23    | Criteria-<br>Requirement in the<br>schedule  | The similar work(iii) shall mean a<br>project including the following<br>works:<br><br>2. A civil works contract including<br>earth works and concrete works of<br>minimum twenty Million US\$ Dollars<br>(US\$ 20,000,000)  | Regarding no. 2 requirement, please confirm whether the US\$ 20,000,000 cost is (1) specifically for the earthworks and concrete works activities in the project or (2) for the project contract value as a whole scope of work. If the US\$ 20,000,000 requirement is intended for the earthworks and concrete works in a project only, please confirm what would be the acceptable evidence to demonstrate the worth of these works given that the construction certificate and/or payment certificate is in general issued for the whole scope of works rather than for the specific work activity.  | Please refei<br>Addendum |
| S-07     | 1   | Vol.1 Sec3 | EQC23    | Criteria-<br>Requirement in the<br>schedule  | The similar work(iii) shall mean a<br>project including the following<br>works:<br>1. Road or Railway project of<br>2. A civil works contract including<br>earth works and<br>3. At-grade/elevated land transport<br>Depot project constructed on a filled<br>site<br>Notes : (iii) The similarity of the<br>contract(s) in which the Bidder<br>participated shall be based on the<br>physical size, nature of works,<br>complexity, methods, technology or<br>other characteristics of the contract as<br>compared with those Works descried<br>in Part II – Requirements, , Section 6<br>– Employer's Requirements, "IA-<br>Scope of Works". | As the similar nature of the works, 'At-grade/elevated land<br>transport Depot project constructed on a filled site' is<br>suggested in the schedule. And it is also noted that 'the<br>similar work' in the statement was associated with the<br>footnote (iii) which allows wider interpretation of the<br>similarity of the works.<br>In relation to the interpretation of 'Depot project<br>constructed on a filled site', please confirm if the Depot<br>project which is not on a filled site or partially on a filled<br>site can be regarded as meeting this experience requirement.<br>Or please confirm if the Client would require the Bidder to<br>meet this experience requirement strictly to the language of<br>ITB (i.e whole footprint of Depot should be sitting on the<br>filled site) | Please refei<br>Addendum |
| S-07     | 1   | Vol1 Sec3  | EQC24    | Criteria –<br>Requirement in the<br>schedule | 1. Construction of major retaining<br>structures at least 8m high of at<br>least 500 m length  | <ul> <li>Please confirm the following queries</li> <li>(1) if a single project should have the 500m long retaining structure</li> <li>(2) if such 500m long retaining structure should be continuous in nature</li> <li>(3) if the 8m height requirement is for the highest height or the average height</li> </ul>   | Please refer<br>Addendum |
| S-07     | 1   | Vol1 Sec3  | EQC24    | Criteria –<br>Requirement in the<br>schedule | 2. At least one (1) project that<br>included major filling with selected<br>material of at least 750,000 m3 7.5m<br>deep including compaction in layers<br>within a 3-year period  | Please confirm if the 7.5m height requirement is for the average height or the highest height.  | Please refer<br>Addendum |
| S-07     | 1   | Vol1 Sec3  | EQC24    | Criteria –<br>Requirement in the<br>schedule | 3. Construction of at least 10,000<br>m3ground floor area of concrete<br>framed buildings on deep filled sites<br>using piled foundation   | The ground floor area requirement is suggested as 10,000 m3. Please confirm the unit of ground floor area is correct.   | Please refer<br>Addendum |



| Packages | Vol | Sec   | Page No. | Clause No./Title  | Reference Text<br>(if necessary) | Clarification<br>Request  |   |
|----------|-----|---|----------|---|----------------------------------|---|---|
| S-05     | 1   | Volume 1,<br>Section 4A,<br>Bill of<br>Quantities                     | -        | -   | -                                | Based on the contractor's review on the ITB, the basis of the<br>Bill of Quantity (BoQ) associated with the excavation does<br>not appear any of the drawings shown. The contractor<br>would like kindly to request providing the basis of BoQ<br>assocaited with the excavation.   | Please refer<br>drawing ref<br>and Roads.<br>(Architectur<br>Stations / B<br>excavation<br>(Civil) draw<br>Specificatio<br>Excavation.<br>volume of w<br>(Architectur<br>Technical S<br>Section 201 |
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-1401                                | -                                | 38.5 THK Rubber strip gluded to steel pin appears in DWG<br>No. NSRP-DWG-VIA00-ST-1401. However, the material<br>specification associated with the rubber does not appear in<br>any of the document given to the bidder. Please provide the<br>material specification for the rubber.   | Shear Mod<br>Bulk Modu  |
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-0063,<br>NSRP-DWG-<br>VIA00-ST-1301 | -                                | The Bidder understands that OCS poles will be installed on<br>the girder with having regular distances. However, there is<br>no inidcation where OCS poles will be installed. If the<br>bidder does not need to account for the OCS poles within<br>the scope of work by the Civil Contractor, it would be okay.<br>If not, the Bidder kindly requests the Client to provide the<br>locations of OCS poles. | OCS pole lo   |
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>I/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-0801                                | -                                | According to the referred drawing in the ITB, the contractor<br>needs to start up the casting from Segment No. 15. Would<br>you please clarify if we are allowed to switch the sequence<br>of the casting of the precast segment?   | The final co<br>Engineer an<br>casting" an<br>methods. Th<br>be fully cap<br>superstruct<br>the casting   |
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-<br>1501~1561                       | -                                | From the referred drawings in between Drawing No. 1501<br>and No. 1561, there are items that may belong to the E&M<br>systems and Track works (i.e., out of the scope of work<br>within CP S-06). Would you please clarify these items<br>within referred drawings included in this work scope.   | Yes, the translab are par<br>slab are par<br>The details<br>widening for<br>Bond and S  |

#### **Final Response**

fer to Volume 2, 02\_Book 1 (Civil) for the references related to the Viaduct, Drainage ls. Also refer to Volume 2, 02\_Book 2 tural) for the reference drawings related to the 'Buildings Details. Calculate the earthworks / n works based from the appropriate Book 1 awings in conjunction with the Technical tions, TS 100; and the whole of Section 102 on. For the Structure Excavation, calculate the f works based from the appropriate Book 2 tural) drawings in conjunction with the l Specifications, TS 200; and the whole of 01-Structure Excavation and Backfill.

s to be updated indicating rubber properties: ter Hardness = 60 fodulus, G = 0.9MPa dulus, B = 2000 Mpa

WG-VIA00-ST-1401 will be issued as m 3

e location will be provided to bidders in *m* 3

casting sequence shall be agreed with the and shall follow the principles of "match and either the short or longline casting The method proposed by the contractor shall apable of controlling the geometry of the cture both horizontally and vertically during g operation.

rackworks and the equipment on top of the part of E&M and Trackworks. ils are shown as reference for the deck for Electronic Point Machine, Impedance I Shunting Signal.

| Packages | Vol | Sec   | Page No.  | Clause No./Title  | Reference Text<br>(if necessary)  | Clarification<br>Request  |   |
|----------|-----|---|-----------|---|---|---|---|
| S-05     | 2   | Volume 2,<br>01<br>Specification,<br>02 TS                            | TS200-126 | TS 206.18.4.3<br>Form Travelers for<br>Balanced<br>Cantilever<br>Construction | Segmental balanced cantilever<br>construction shall be carried out using<br>form travelers with steel formwork.   | According to the TS, it is required to use the steel form for<br>the construction of Balanced Cantilever (BC) bridge. Based<br>on the Bidder's experience, it is feasible to utilize wooden<br>forms to build up the BC bridge in general in accordance<br>with the technical specification given in the ITB.<br>Please clarify if the Bidder is allowed to adopt this<br>deviation of the specification. | The falsew<br>the liner (fo<br>plywood an<br>smooth sur<br>The expose<br>patters, nai |
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -         | DWG No. NSRP-<br>DWG-<br>VIA05-ST-0101  | -   | The pier reinforcement type for Pier 689~692 is designated<br>as Type 31 in Drawing No. NSRP-DWG-<br>VIA05-ST-0101. However, Pier reinforcement type 31<br>does not appear in any of the Drawing Nos between NSRP-<br>DWG-VIA05-ST-0603 and NSRP-DWG-VIA05-ST-0608<br>where all the Pier reinforcement type appears. Please<br>provide the reinforcement drawings for Type 31.                            | Pier Type H<br>be providea<br>Drawing n<br>revised and                                |
| S-05     | 1   | Volume 1,<br>Section 1  | ITB 20.1  | C Preparation of<br>Bids,   | In addition to the original Bid, the<br>number of copies is Five (5) copies<br>together with Two (2) complete<br>digital copies contained on DVDR<br>disc in Portable Document format<br>(.pdf) and the Bill of Quantities in<br>workable spreadsheet format<br>(.xls/.xlsx). The electronic documents<br>shall be scanned from the "Original"<br>signed document and arranged and<br>indexed in exactly the same manner.<br>Should any discrepancy be found in<br>the electronic copies, the content of<br>the "Original" paper copy shall<br>prevail. The bidder shall also include<br>2 digital copies of the bid<br>programprepared in accordance with<br>Section 4 Technical Proposal,<br>Construction Schedule. | Please provide the definition (or elaborate) of "bid<br>program" which is requested to be included as a part of<br>digital copies for the bid submission.   | The "Bid P<br>as required<br>Programmi  |

#### **Final Response**

work can be either steel or timber. However, (forming the concrete surface) shall be steel or and accurately aligned to produce an even urface.

osed surface shall be free of timber grain ail holes and joints.

e P1 - Type 31 pier reinforcement, details shall led. number NSRP-DWG-VIA00-ST-0609 will be nd issued in Addendum 3

Program" refers to the Construction Schedule ed under Section 4 Technical Proposals ming Proposals - Construction Schedule

| Packages | Vol | Sec  | Page No. | Clause No./Title         | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |
|----------|-----|--|----------|--------------------------|---|---|--|
| S-05     | 2   | Volume 2,<br>01<br>Specification,<br>01 GS | GS 131   | 131.1 General            | Construction activities in the vicinity<br>of any PNR operating railway line<br>and railway protection and<br>safety zones can cause accidents or<br>damage to the existing railway,<br>Activities in the vicinity of<br>Safety considerations shall be<br>adopted<br>Whenever work is to be conducted in<br>close proximity to live railways, the<br>following<br>For Specific PNR conditions refer to<br>Appendix 6 – Works in the Vicinity<br>of the Philippines National Railway. | Although the reference text indicates that Appendix 6<br>Works in the Vicinity of the Philppines National Railway is<br>provided within ITB, the Bidder is not able to locate the<br>referred Appendix 6. The Bidder kindly request the client<br>to provide such document.   | Please refe  |
| S-05     | 2   | Volume 2,<br>01<br>Specification,<br>01 GS | GS 131   | 131.3 Reference<br>Plans | The Contractor shall request from the<br>PNR plans defining the<br>railwayprotection and safety zones.<br>The Contractor shall ensure that no<br>works of any kind are carried out<br>within the railway protection and<br>safety zones without prior approval<br>and that all necessary measures are<br>correctly put into place and managed<br>to ensure safe working at all times.   | It is mentioned that the Contractor shall follow the railway<br>protection and safety zones defined by PNR. In order to<br>account for the railway protection and safety zones defined<br>by PNR during the tender stage, the Bidder would like to<br>kindly request such document for the consideration.   | Please refe  |
| S-05     | 1   | Volume 1,<br>Section 4                     | BF 7     | Schedule                 | -   | Considering work to be completed by the contractor, it is<br>the contractor's understanding that the work would need<br>several items that are not included in the BoQ. For<br>example, the contractor expects to perform site access<br>preparations, sheet pile cofferdams, alignment Service<br>track, berms setup and removal, etc. However, these items<br>are not included in the BoQ given within the ITB. The<br>Bidder was wondering if such omitted items could be added<br>within the BoQ as a part of the proposal. | The Bidder<br>Document<br>paragraph<br>states that<br>General Sp<br>conjunctio<br>(GCC), the<br>the Techni<br>Drawings<br>Contract".<br>works, In o<br>Please refe<br>and the wh |

#### **Final Response**

efer to revised GS 131.4

efer to revised GS 131.4

der is advised to read and evaluate the Bidding nts in whole. Please refer to the third ph of the General Specifications, GS 101, which at "The Scope of Works (SOW) and the Specifications (GS) shall be read in tion with the General Conditions of Contract the Particular Conditions of Contract (PCC), unical Specifications (TS), the Employer's and any other documents forming part of the t". As a sample, for the cofferdams and related n conjunction with the BOQ and Drawings, efer to the Technical Specifications, TS 200, whole of Section 203 - Temporary Works.

| Packages | Vol | Sec                      | Page No. | Clause No./Title                | Reference Text<br>(if necessary) | Clarification<br>Request  |   |
|----------|-----|--------------------------|----------|---------------------------------|----------------------------------|---|---|
| S-05     | 3   | Volume 3,<br>Section 8   | PCC 3    | PCC 6.5                         | -                                | According to PCC 6.5, works on the site is permitted 24<br>hours per day, 7 days per week. For this, the bidder may<br>consider to work out of regular hours per day. However,<br>working out of regular hours for the bidder would result in<br>the Engineer (i.e., any associated engineers working for the<br>Client) working out of regular hours such as the work<br>incurred for witnessing the work activity by the contractor.<br>The Bidder was wondering if the Bidder needed to cover<br>the salary of the Engineer incurred due to the Contractor<br>working overtime. Please clarify.  | No. The Co<br>salary of th<br>required to<br>of hours w |
| S-05     | 1A  | Volume 1A,<br>Section 4A | -        | BILLS OF<br>QUANTITIES<br>(BOQ) | -                                | Other than large creeks (as shown in the ITB drawings)<br>along the project alignment, the contractor is expected to<br>install culverts / drainages across the alignment (i.e., East<br>side<> West side) where the small creeks exist (e.g., Cor<br>CP05, refer to Drawing No. NSRP-DWG-VIA05-ST-0037<br>where the creek exist between P-904 and P-905 and for<br>CP06, refer to Drawing No. NSRP-DWG-VIA06-ST-0015<br>where the creek exist between P-1015 and P-1016).<br>However, quantities associated with these types of culverts /<br>drainages do not appear within the BoQ. This may imply<br>that the contractor is able to disconnect these small creeks<br>across the alignment. Please clarifiy if there is any drainage<br>/ culvert across the alignment. If so, the contractor kindly<br>request the Client to provide the BoQ / basis for all such | and River I<br>Updated B                                |
| S-05     | 1   | Volume 1,<br>Section 1   | ITB 13   | Format and Signing<br>of Bid    | -                                | In regards to the bid documentation and the submisson of<br>original copies, the Bidder kindly request the client to<br>clarify the following:<br>1. Whether or not the submission is required to be printed<br>based on single sided or double sided copy.<br>2. Whether or not the all of the submitted document pages<br>are required to have the signature on every single printed<br>page, especially including the method statement.  | 1. No spect<br>2. All to be<br>stated in th             |
| S-05     | 1   | Volume 1,<br>Section 1   | ITB 13   | Sealing and<br>Marking of Bids  | -                                | Considering the size of the original copy to be printed for<br>the submission, the contractor was wondering if the<br>contractor would be able to submit the original copy more<br>than one box instead of one envolope. The Bidder can<br>instead mark up "Original 1/2" and "Original 2/2", etc so<br>that the Client can easily recognize the order of the<br>document within the submission.<br>Please confirm if submitting the bid proposal in a separate<br>box is acceptable to the Client.   | Considerin<br>for the Bid<br>boxes. "Or<br>procedure    |

Contractor will not be required to cover the the Engineer. However, the Contractor will be to provide the Engineer advance notice of out working

pere are drainage/culvert across the alignment. Pere reflected in At-Grade Mainline Drainage s.

OQ shall be revised to include Drainage across ment under the Bill No. 5 - Drainage System r Bank Protection. BOQ shall be issued as Addendum 2.

ecific requirement. be signed in accordance with requirements the Bidding Documents.

ing size and volume of documents to be printed id, Bidder is allowed to submit Bids in multiple One/Single Envelope'' would refer to the e for Opening and Evaluation of Bids.

| Packages | Vol | Sec  | Page No. | Clause No./Title                          | Reference Text<br>(if necessary)  | Clarification<br>Request   |   |
|----------|-----|--|----------|---|---|--|---|
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings                 | _        | NSRP-DWG-<br>VIA00-ST-0402                | -   | As per "crack control recommendation" on Drawing No.<br>NSRP-DWG-VIA00-ST-0402, maximum temperature of<br>the concrete mixture at the the time of concrete pouring is<br>provided as follows:<br>- Pier Column and Head Stock at 24°C for 40 MPa<br>- Pile Caps at 28°C<br>However, the technical specification shown in TS 206.8.1<br>indicates that the maximum temperature of the concrete<br>mixture at the time of concrete pouring shall be limited to<br>30°C . In addition, DPWH Standard specifies that the<br>maximum temperature of the concrete mixture at the time of<br>concrete pouring shall be limited to 32°C.<br>The Bidder would like the Client kindly to clarify if the<br>Bidder can follow the technical specification (i.e., 30°C) or | The maxim<br>placing sho<br>should be a<br>mixing plan<br>Contractor<br>TS200 Clan<br>TS200 206.<br>the cooling<br>concreting<br>concrete ex<br>Drawing N<br>and issued |
| S-05     | 3   | Volume 3,<br>Section 8                                 | PCC 7    | SUMMARY OF<br>KEY DATES                   | -   | the DPWH standard (i.e., 32°C).<br>In regards to the Key date, the Bidder was wondering if (1)<br>noise barriers (Parapet), (2) protective concrete layer and<br>(3) precast cable trough cover needed to be completed by<br>KD02 or KD06.   | Items (1), (  |
| S-05     | 3   | Volume 3,<br>Section 8                                 | PCC 8    | SUMMARY OF<br>KEY DATES                   | KD 05<br>Provision of Access to Concourse<br>Paid/Unpaid area and<br>Platform area for CP NS-01<br>(trackwork and E&M Systems) to<br>commence installation of AFC and<br>PSD equipment. | Please clarify if the completion of all the roofing<br>membranes for stations is included in KD05 or other key<br>dates.   | All the rooj<br>KD6.  |
| S-05     | 2   | Volume 2,<br>Section 6, IB<br>GeneralSpecifi<br>cation | TS100-25 | 102.2.9 Removal of<br>Unsuitable Material | TS102.2.9<br>If evidence of contaminated soil is<br>foundwaste material.  | <ul> <li>Please clarify the following:</li> <li>(1) if the client measures such potentially contaminated soils within the project site. If so, please provide the Bidder with the data.</li> <li>(2) The BoQ does not contain any item associated with the treatment (or off-site transfer) associated with the contaminated soil. If there is any contaminated soils to be found within the project site, the Bidder kindly requests the client to provide the item within the BoQ that the Bidder can include the cost incurred due to managing contaminated</li> </ul>  | (2)Please of<br>No. 1, Item<br>conjunction<br>118; Sub-S<br>Manageme<br>Waste (whi  |

#### **Final Response**

imum temperature of fresh concrete at time of hould be between 26 to 30 degrees C and e achieved through normal precautions at the lant, for working in hot-humid climates. The or shall comply with the recommendations of lause 206.7.8.4 with regard to pre-cooling and 06.7.8.5 and TS200 Clause 206.7.8.5 regarding ing of the concrete. At no stage during the g process should the temperature of the fresh exceed 35 degrees C.

NSRP-DWG-VIA00-ST-0402 will be revised d in Addendum 3

(2) and (3) are required to complete by KD02.

ofing membranes for station is included in

ontaminated soil is part of GS118. Please refer .5.2 Hazardous waste for its scope.

e refer to the Updated BOQ, Addendum 1, Bill m GS118-Environmental Management in ion with the General Specifications, Section GS -Section 118.5; Clause 118.5.2-Waste ment Plan; Sub-Clause 118.5.2.2-Hazardous hich includes the contaminated soil).

| Packages | Vol | Sec                                    | Page No. | Clause No./Title                      | Reference Text<br>(if necessary)   | Clarification<br>Request  |   |
|----------|-----|--|----------|---------------------------------------|--|---|---|
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings | -        | NSRP-DWG-<br>VIA00-ST-0951            | 21-M12×95 Elephant Foot  | The embedded anchors (i.e., 21-M12×95 Elephant Foot)<br>shown on the drawing do not appear not in the BOQ, please<br>clarify these embedded anchors will be installed by the<br>Bidder or not. If the Elephant Foots is expected to be<br>installed by the bidder, please provide the details on the<br>embedded anchors as a form of drawings together with<br>assocaited BOQ.   | (1) The em<br>Foot) - sho<br>drawing.<br>(2) These of<br>Precast Seg<br>206(3)b and<br>A, Section A<br>Measuremon<br>paragraphs |
| S-05     | 3   | Volume 3,<br>Section 9                 | CF 7     | Contract<br>Agreement                 | Contract Form CF3<br>2. The following documents shall be<br>deemed to form       | According to the CF3, all the documents related to the Bid<br>and the following contract have the order to be read and<br>constructed as part of this Agreement.<br>The Bidder would like kindly the Client to inform the order<br>of all of the clarifications (i.e., queries) submitted to the<br>Client and replied by the Client within the Contract<br>documents in between (a) The Contract Agreement and (l)<br>Extracts from the Bidding Documents as submitted by the<br>Contractor and listed in the attachment-1 hereto. | Bidder is a<br>included in  |
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings | -        | -                                     | -  | Although the Bidder could find out the final elevations for<br>the maintenance road and associated ground elevations<br>along the alignment, the Bidder was not able to find out the<br>final ground elevations (i.e., z axis) to be built across the<br>alignment (i.e., x and y axes). The Bidder would like the<br>Client kindly to provide the final ground elevations that<br>need to be constructed by the Bidder.  | For the fin<br>associated<br>to Drawing<br>bidder refe  |
| S-05     | 2   | Volume 2,<br>Section 6, II<br>Drawings | -        | NSRP-DWG-<br>VIA00-ST-0421            | -  | According to the Typical Elevation shown in Drawing No.<br>NSRP-DWG-VIA00-ST-0421, piercap height is shown to<br>be 2150mm. However, the table shown below indicates the<br>range of the height (i.e., based on DD column) is between<br>2500mm and 3500mm.<br>Please clarify which one is correct.   | Dimension<br>replaced by<br>Drawing N<br>and issued   |
| S-05     | 2   | Volume 2<br>TS-<br>500_Annex A         | 70       | 563.1.1 /<br>Method of<br>Measurement | 563.1.1 Method of Measurement<br>Softscaping works will be a<br>Provisional Sum. | According to the BOQ, there are 3 softscape items; Item<br>No. 563(2)a, 563(4) and 563(5).<br>However, TS-500_Annex_A indicates that "Softscaping<br>works will be a part of the Provisional Sum."The Bidder<br>was wondering if, within any of the scope of work, there<br>are any additional softscape works to be performed.   | TS 563 to b<br>The BOQ<br>Works. Upo  |
| S-05     | 2   | Volume 2,<br>Drawing                   | -        | NSRP-DWG-BIN-<br>EL-5011              | -  | As shown on the single line diagram, each station possesses<br>small-capacity diesel generator.<br>However, the generator is not provided within BOQ. Please<br>advise how we should account for these generators in our<br>pricing.  |   |

#### **Final Response**

mbedded anchors (i.e., 21-M12×95 Elephant hould be installed in accordance with the

e embedded anchors are subsidiary items to the Segmental Box Girder Item Nos. 206(3)a, and 206(3)c. Please refer to the TS 200\_Annex n 206-Concrete Structures, Sub-section 206.1ment and Payment; Clause 206.1.2; Whole hs of Sub-Clause 206.1.2.1-General.

advised that bidder query clarifications will in item (d)

inal elevations for the maintenance road and d ground elevations along the alignment, refer ng NSRP-DWG-VIA05-RD-2002 Note 5.4 for ference.

ons 2150 indicating the pier head depth shall be by "DD".

NSRP-DWG-VIA00-ST-0421 shall be revised d as Addendum 3

be revised and issued as Addendum 3 2 will be revised for the appropriate Softscape [pdated BOQ shall be issued as Addendum 2.

fer to the Updated BOQ, Addendum 1.

| Packages | Vol | Sec   | Page No. | Clause No./Title                                     | Reference Text<br>(if necessary)   | Clarification<br>Request   |   |
|----------|-----|---|----------|--|--|--|---|
| S-05     | 2   | Volume 2,<br>Specification<br>TS 700                    | -        | -  | -  | Please kindly provide Approved/Acceptable brands<br>(BMS/CCTV/Access control/Panelboard/Lighting<br>fixture/Fire Alarm) for the purpose of system integration of<br>all stations at OCC building, system compatibility and ease<br>of maintenance in the future.   | Brands for<br>component<br>equivalent   |
| S-05     | 2   | Volume 2,<br>Specification<br>TS 700                    | -        | -  | -  | In terms of Communication system (BMS/CCTV/Access<br>control) including the fire alarm, the Bidder understands<br>that E&M system contractor will supply and install main<br>equipment, software and testing.<br>Please confirm the Bidder (i.e., Civil contractor) is only<br>responsible for items to be installed inside station as shown<br>on drawings and BOQ, with the confirmation of software<br>being out of the Bidder's scope of work.<br>If above mentioned works are the part of the Bidder's SoW,<br>please provide relevant drawings showing schematic<br>diagram, floor layout, system sequence, point schedule, etc. | Contractor,<br>based on m<br>compliance<br>by specialis                           |
| S-05     | 2   | Volume 2,<br>Specification<br>TS 700                    | -        | 701.3.4  | Provide anti-sway brackets on<br>horizontal tray assemblies at 3 meter<br>intervals.   | Please advise whether cable trays in all areas require anti-<br>sway brackets at every 3 meters.   | Cable tray  |
| S-05     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ              | -        | Conduit and Cable<br>Tray                            | -  | In the BOQ, there are items associated with 150, 400, and 600mm size. However, in the drawing, only 150 and 900mm size exist. Please provide the clarification on this discrepancy.  | Please refe   |
| S-05     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ<br>Volume 2, | -        | NSRP-DWG-STA-<br>EL-5005                             | -  | Cable tray detail drawing shows the divider between<br>lighting and power cables, while the divider does not appear<br>in Panelboard incoming cables. However, the BoQ given to<br>the Bidder does not differentiate the cable trays depending<br>on the presence of the divder with the tray. Please clarify.   | trave tor th  |
| S-05     | 2   | Volume 2,<br>Drawing                                    | -        | NSRP-DWG-STA-<br>EL-5003<br>NSRP-DWG-STA-<br>EL-5004 | -  | There are two different drawings in terms of cable tray<br>support.<br>Please confirm that the Bidder can only follow the support<br>detail with rods.   | Treaded ro<br>EL-5003 w   |
| S-05     | 2   | Volume 2,<br>Specification<br>TS 700                    | -        | 715.1.2  | The surveillance system shall consist<br>of CCTV cameras combination of<br>fixed and equipped with<br>Pan/Tilt/Zoom Lens System (PTZ)<br>located at the lobbies and entrances<br>and exits of Ground and Second<br>floors. | TS 715.1.2 shows "Combination of fixed dome and PTZ<br>camera".<br>However, drawings indicate the box type camera only with<br>housing, which does not appear in any of technical<br>specification.<br>In addition, BoQ only contains "CCTV Camera," which<br>does not appear either in the technical specification or<br>drawings.<br>Please advise if the Bidder follows the drawings or not. If<br>the Bidder follows the drawing, would it be possible to  | The Bidder<br>with the ap<br>Technical S<br>"CCTV Ca<br>General Sta<br>5001 Rev.2 |

#### **Final Response**

or this equipment, devices and other nts shall be UL/NEMA listed or IEC nt approved standard.

or/vendor to validate all system components manufacturer's recommendation in ce with requirements in relevant TS. BMS is list.'

y system shall withstand seismic requirements.

fer to the Updated BOQ, Addendum 1.

) shall be revised to separate/divide the cable the incoming panel boards from the cable trays ghting and Power. Updated BOQ shall be Addendum 3.

rods (Hanger) will be used. NSRP DWG-STAwill be revised and issued as v 21.2.

The should follow the drawing in conjunction appropriate sections and clauses of the I Specifications. The BOQ Item Description Camera" was adopted from the Legends of the Station drawing No. NSRP-DWG-STA-EL-.21.

| Packages | Vol | Sec   | Page No. | Clause No./Title                    | Reference Text<br>(if necessary)  | Clarification<br>Request   |   |
|----------|-----|---|----------|-------------------------------------|---|--|---|
| S-05     | 2   | Volume 2,<br>Specification<br>TS 700            | -        | 706.1.5                             | Prepare a short circuit and<br>coordination study based on the<br>actual overcurrent protection devices<br>proposed for use. The study shall be<br>prepared by a locally registered<br>electrical engineer.   | Please confirm that the Bidder is responsible for support<br>only "Short circuit coordination study report" and others<br>(i.e., E&M contractor) will prepare and submit the report.   | Bidders sha<br>respective s<br>project stak<br>protection o<br>system com<br>lengths. |
| S-05     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ      | -        | BMS                                 | -   | Two items: 713(8) and 713(9) in BoQ are specified as a<br>lump sum price in BMS BOQ.<br>However, the Bidder is not able to figure out quantities<br>since drawings are not provided.<br>Please provide either drawings or quantities of these two<br>items.  | Please refe<br>700_Annex<br>System; Su<br>Clauses 71.<br>Basis of Pa                  |
| S-05     | 2   | Volume 2,<br>Specification<br>TS 700            | -        | 701.2.2.5                           | Provide heavy wall, high impact<br>strength, rigid PVC conforming to the<br>requirements of Philippine code<br>requirements.<br>Conduit and fittings shall be UL 651<br>listed and shall conform to Article<br>347 of the NEC for underground and<br>exposed use. | Please advise if the Bidder can use exposed PVC conduits that comply with Philippine Standard but not UL Listed.   | PVC shall (<br>(concealed)<br>equivalent  |
| S-05     | 2   | Volume 2,<br>Drawing                            | -        | NSRP-DWG-STA-<br>EL-5001            | 25. All lighting at fire exit shall be controlled by motion sensor.   | The Bidder is failed to locate motion sensor in any of the<br>drawings. The Bidder was wondering if the motion sensor<br>is integrated in each lighting fixture on the fire exit.<br>Also, if all lighting at fire exit is controlled by motion<br>sensor, how does the system of operation work since the<br>whole circuit is turned on/off by BMS. | Refer to Dr<br>5006/Motio<br>Addendum   |
| S-05     | 2   | Volume 2,<br>Drawing                            | -        | NSRP-DWG-STA-<br>EL-5001            | -   | Although the drawing only shows PTZ, Fixed dome, the<br>specification deals with several types of CCTV Camera<br>such as PTZ and Fixed dome.<br>Please clarify if the SoW only incudes the box type CCTV<br>Camera.  | The SoW w<br>depending<br>recomment   |
| S-05     | 2   | Volume 2,<br>Specification<br>TS 700            | -        | 716                                 | The work of this section covers the<br>furnishing, installing and placing in<br>operation of an electronically-<br>operated, supervised, conventional<br>fire alarm system.   | Technical Specifications for FDAS requires Conventional<br>type, while FDAS riser diagram and layout implicates Fully-<br>addressable type. Please provide the Technical specs of<br>Fully-addressable type.   | - FDAS is Ad<br>Addendum  |
| S-05     | 2   | Volume 2,<br>Drawing<br>Specification<br>TS 700 | -        | 711.3.1<br>NSRP-DWG-BAN-<br>EL-5601 |   | Based on Technical Specification, HDPE conduits are<br>required for the down conductor.<br>However, PVC conduits are shown on the drawing.<br>Please kindly clarify.   | All non-me<br>be used in<br>be revised i  |

#### **Final Response**

hall also provide and validate based on their e scope and collaborate with other concerned ake holders for the short circuit analysis and n coordination study based on actual electrical omponents nameplate rating and actual circuit

fer to the Technical Specifications, TS ex A; Section 713-Building Management Sub-section 713.1-Measurement and Payment; 713.1.1-Method of Measurement and 713.1.2-Payment.

ll only be used in concrete embedded ed) Installations. PVC shall be UL-listed or at standard.

Drawing no. NSRP-DWG-STA-ELtion Sensor details will be revised and issued in m 3

will include all types of CCTV cameras g on application, based on manufacturer ndation.

Addressable type. See Revised TS 700 issued in m 2

netallic conduits such as HDPE and PVC shall n concrete-embedded applications. TS 700 will l in Addendum 3

| Packages | Vol | Sec   | Page No. | Clause No./Title                                      | Reference Text<br>(if necessary) | Clarification<br>Request  |   |
|----------|-----|---|----------|---|----------------------------------|---|---|
| S-05     | 2   | Volume 2,<br>Specification<br>TS 600                                      | -        | 624 HRV   | -                                | For HRV equipment (All station), what is the design indoor<br>temperature and outdoor temperature?, What is the<br>condition during the stated temperature exchange?  | Refer to up<br>Temperatur<br>ME-5663 N<br>BIN-ME-50<br>Temperatur<br>BIN-ME-0<br>NSRP-CAL |
| S-05     | 2   | Volume 2,<br>drawing  | -        | NSRP-DWG-BIN-<br>SN-6110<br>NSRP-DWG-PTA-<br>SN-6110  | -                                | Please provide the length of collector pipe for 100Ø DS-41 to 48 on platform level as is not reflected from the ground floor, concourse and roof layout plan at Binan (griidline A-D,1; A-D,20), and Pacita station (gridline A-D,1; A-D,20). | Please refe<br>6106 Rev 2<br>21.2. These  |
| S-05     | 2   | Volume 2,<br>drawing  | -        | NSRP-DWG-BIN-<br>SN-6126                              | -                                | Please provide the elevation, material of pipe and isometric drawing of elevated pedestrean walkway at Binan station.   | For Elevati<br>Drain pipe<br>drawing for<br>BIN-6126 v                                    |
| S-05     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ.<br>Volume 2,<br>Specification | -        | 618.2.5 Design<br>conditions                          | -                                | Which shall govern for the flow rate capacity of Waste<br>Water Treatment Plant in the BOQ or Equipment Schedule<br>at layout plans or Technical specification?   | The BOQ s<br>and Techni<br>issued as A  |
| S-05     | 2   | Volume 2,<br>drawing  | -        | -   | -                                | Please confirm if the Bidder considers a scupper drain per<br>downspout at platform level as indicated at blow up detail.   | Scupper Di<br>at the Emer   |
| S-05     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ.<br>Volume 2,<br>drawing       | -        | -   | -                                | Please provide us with drawings and specification<br>associated with Floor Mounted Type Air Conditioning Unit<br>with Air Cooled Condenser Unit (ACUF).   | <i>Refer to up</i><br>5601,NSRF<br><i>ME-</i> 5601, 1                                     |
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-BIN-<br>ME-5608 NSRP-<br>DWG-BIN-ME-<br>5661 | -                                | Total airflow capacity of SEF-02 in schedule does not<br>match with the total airflow capacity of EAG connected.<br>Please clarify.   | Schedule w<br>be revised a<br>each grille.  |
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-BIN-<br>ME-5632                              | -                                | Please indicate the size of the grille connected to HRV-08.   | This must l<br>be revised a   |
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>ME-5662 NSRP-<br>DWG-PTA-ME-<br>5632 | -                                | Airflow Supply/Exhaust of HRV-11 in schedule does not match with the drawing. Please clarify.   | Schedule w<br>NSRP-DW<br>in Addendu   |
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>ME-5631                              | -                                | In the Bidder's view, the size of this seems to be 1400 x 3000 instead of 1400 x 300. Please clarify.   | Please refe   |
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>ME-5632                              | -                                | Please provide the sizes of ducts serving EF-08 and EF-09.  | This must l<br>be revised a   |

#### **Final Response**

pdated drawing. HRV equipment schedule for ure exchange condition NSRP-DWG-SPO-NSRP-DWG-PTA-ME-5662 NSRP-DWG-5662 Rev 21.2. For Indoor and Outdoor ure, please refer to calculations NSRP-CAL-0105\_06, NSRP-CAL-PTA-ME-0102\_06 and AL-SPO-ME-0099\_06.

fer to updated drawing NSRP-DWG-BIN-SN-21.2 and NSRP-DWG-PTA-SN-6104 Rev se DS have been reflected at ground floor.

ation, please refer to architectural drawings. be would be PVC Series 1000. the isometric for Binan Pedestrian Walkway NSRP-DWG-6 will be revised and issued in Addendum 3

shall be revised to conform with the Drawing nical Specifications. Updated BOQ shall be Addendum 2.

Drain is only for DS-41 to DS-48 as these are ergency Staircase roof deck.

pdated drawing NSRP-DWG-SPO-ME-RP-DWG-SPO-ME-5661, NSRP-DWG-PTA-, NSRP-DWG-PTA-ME-5661, NSRP-DWG-5601, NSRP-DWG-BIN-ME-5661, Rev 21.2. NSRP-DWG-SPO-ME-5638 Rev 21. Refer to WG-PTA-ME-5638, NSRP-DWG-BIN-ME-21.1. For specifications, please see TS 600.

will govern. NSRP-DWG-BIN-ME-5608 will and issued in Addendum 3. Must be 1571 lps le.

t be 300x300. NSRP-DWG-BIN-ME-5632 will l and issued in Addendum 3

will govern, must be 14 lps design drawing. WG-PTA-ME-5632 will be revised and issued dum 3

fer to NSRP-DWG-PTA-ME-5631 Rev 21

t be 300x150. NSRP-DWG-PTA-ME-5632 will l and issued in Addendum 3

| Packages | Vol | Sec   | Page No. | Clause No./Title  | Reference Text<br>(if necessary) | Clarification<br>Request   | Final Response   |
|----------|-----|---|----------|---|----------------------------------|--|--|
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>SN-6104  | -                                | Is this 50-diameter ACDS-04 going to 250 diameter drain pipe as well? Same goes with other ACDS.   | ACDS will be going to 250mm drain pipe.  |
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>SN-6104  | -                                | Where will these 100-diameter downspouts come from?  | These downspouts are from the canopy.  |
| S-05     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>FS-6608  | -                                | Provide RN sizes.  | Please refer to Riser Nipple Schedule at NSRP-DWG-<br>PTA-FS-6608 Rev 21.1   |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-1401                                | -                                | 38.5 THK Rubber strip gluded to steel pin appears in DWG<br>No. NSRP-DWG-VIA00-ST-1401. However, the material<br>specification associated with the rubber does not appear in<br>any of the document given to the bidder. Please provide the<br>material specification for the rubber.  | Drawings to be updated to indicate rubber properties:<br>Durometer Hardness = 60<br>Shear Modulus, G = 0.9MPa<br>Bulk Modulus, B = 2000 Mpa<br>NSRP-DWG-VIA00-ST-1401 will be issued in<br>Addendum 3  |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-0063,<br>NSRP-DWG-<br>VIA00-ST-1301 | -                                | The Bidder understands that OCS poles will be installed on<br>the girder with having regular distances. However, there is<br>no inidcation where OCS poles will be installed. If the<br>bidder does not need to account for the OCS poles within<br>the scope of work by the Civil Contractor, it would be okay.<br>If not, the Bidder kindly requests the Client to provide the<br>locations of OCS poles.  | <b>OCS</b> location will be provided to bidders in Addendum 3  |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-0801                                | -                                | According to the referred drawing in the ITB, the contractor<br>needs to start up the casting from Segment No. 15. Would<br>you please clarify if we are allowed to switch the sequence<br>of the casting of the precast segment?  | The final casting sequence shall be agreed with the<br>Engineer and shall follow the principles of "match<br>casting" and either the short or longline casting<br>methods. The method proposed by the contractor shall<br>fully capable of controlling the geometry of the<br>superstructure both horizontally and vertically during<br>the casting operation. |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-1301                                | -                                | The loading condition for OCS poles appeared in the<br>drawing. However, there is no indication of whether the<br>installation of OCS poles belong to the Bidder's scope of<br>work. In addition, the Bidder believes that there should be<br>any type of foundation for OCS poles embedded within the<br>grider would be required (e.g., anchoring). Please clarify (1)<br>if the bidder needs to know any detail associated with the<br>foundation of OCS poles, (2) if so, please provide the<br>details associated with supporting the OCS pole. | <b>OCS</b> location will be provided to bidders in Addendum 3  |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -        | DWG No. NSRP-<br>DWG-<br>VIA00-ST-<br>1501~1561                       | -                                | From the referred drawings in between Drawing No. 1501<br>and No. 1561, there are items that may belong to the E&M<br>systems and Track works (i.e., out of the scope of work<br>within CP S-06). Would you please clarify these items<br>within referred drawings included in this work scope.  | Yes, the trackworks and the equipment on top of the<br>slab are part of E&M and Trackworks.<br>The details are shown as reference for the deck<br>widening for Electronic Point Machine, Impedance<br>Bond and Shunting Signal.  |

| Packages | Vol | Sec   | Page No.  | Clause No./Title  | Reference Text<br>(if necessary)  | Clarification<br>Request  |   |
|----------|-----|---|-----------|---|---|---|---|
| S-06     | 2   | Volume 2,<br>01<br>Specification,<br>02 TS                            | TS200-126 | TS 206.18.4.3<br>Form Travelers for<br>Balanced<br>Cantilever<br>Construction | Segmental balanced cantilever<br>construction shall be carried out using<br>form travelers with steel formwork.   | Please clarify if the Bidder is allowed to adopt this   | The falsewe<br>the liner (fo<br>plywood an<br>smooth surj<br>The expose<br>patters, nai |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings(Civi<br>l/Maintenance<br>Road) | -         | DWG No. NSRP-<br>DWG-<br>VIA05-ST-0101  | -   | deviation of the specification.<br>The pier reinforcement type for Pier 689~692 is designated<br>as Type 31 in Drawing No. NSRP-DWG-<br>VIA05-ST-0101. However, Pier reinforcement type 31<br>does not appear in any of the Drawing Nos between NSRP-<br>DWG-VIA05-ST-0603 and NSRP-DWG-VIA05-ST-0608<br>where all the Pier reinforcement type appears. Please<br>provide the reinforcement drawings for Type 31. | Pier Type F<br>be provided<br>Drawing n<br>issued in Ad                                 |
| S-06     | 1   | Volume 1,<br>Section 1  | ITB 20.1  | C Preparation of<br>Bids,   | In addition to the original Bid, the<br>number of copies is Five (5) copies<br>together with Two (2) complete<br>digital copies contained on DVDR<br>disc in Portable Document format<br>(.pdf) and the Bill of Quantities in<br>workable spreadsheet format<br>(.xls/.xlsx). The electronic documents<br>shall be scanned from the "Original"<br>signed document and arranged and<br>indexed in exactly the same manner.<br>Should any discrepancy be found in<br>the electronic copies, the content of<br>the "Original" paper copy shall<br>prevail. The bidder shall also include<br>2 digital copies of the bid<br>programprepared in accordance with<br>Section 4 Technical Proposal,<br>Construction Schedule. | Please provide the definition (or elaborate) of "bid<br>program" which is requested to be included as a part of<br>digital copies for the bid submission.   | The "Bid P<br>as required<br>Programmi  |

#### **Final Response**

work can be either steel or timber – however (forming the concrete surface) shall be steel or and accurately aligned to produce an even urface.

osed surface shall be free of timber grain ail holes and joints

e P1 - Type 31 pier reinforcement details shall led. number NSRP-DWG-VIA00-ST-0609 will be Addendum 3

Program" refers to the Construction Schedule ed under Section 4 Technical Proposals ming Proposals - Construction Schedule

| Packages | Vol | Sec  | Page No. | Clause No./Title         | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |
|----------|-----|--|----------|--------------------------|---|---|--|
| S-06     | 2   | Volume 2,<br>01<br>Specification,<br>01 GS | GS 131   | 131.1 General            | Construction activities in the vicinity<br>of any PNR operating railway line<br>and railway protection and<br>safety zones can cause accidents or<br>damage to the existing railway,<br>Activities in the vicinity of<br>Safety considerations shall be<br>adopted<br>Whenever work is to be conducted in<br>close proximity to live railways, the<br>following<br>For Specific PNR conditions refer to<br>Appendix 6 – Works in the Vicinity<br>of the Philippines National Railway. | Although the reference text indicates that Appendix 6<br>Works in the Vicinity of the Philppines National Railway is<br>provided within ITB, the Bidder is not able to locate the<br>referred Appendix 6. The Bidder kindly request the client<br>to provide such document.   | Please refe  |
| S-06     | 2   | Volume 2,<br>01<br>Specification,<br>01 GS | GS 131   | 131.3 Reference<br>Plans | The Contractor shall request from the<br>PNR plans defining the<br>railwayprotection and safety zones.<br>The Contractor shall ensure that no<br>works of any kind are carried out<br>within the railway protection and<br>safety zones without prior approval<br>and that all necessary measures are<br>correctly put into place and managed<br>to ensure safe working at all times.   | It is mentioned that the Contractor shall follow the railway<br>protection and safety zones defined by PNR. In order to<br>account for the railway protection and safety zones defined<br>by PNR during the tender stage, the Bidder would like to<br>kindly request such document for the consideration.   | Please refe  |
| S-06     | 1   | Volume 1,<br>Section 4                     | BF 7     | Schedule                 | -   | Considering work to be completed by the contractor, it is<br>the contractor's understanding that the work would need<br>several items that are not included in the BoQ. For<br>example, the contractor expects to perform site access<br>preparations, sheet pile cofferdams, alignment Service<br>track, berms setup and removal, etc. However, these items<br>are not included in the BoQ given within the ITB. The<br>Bidder was wondering if such omitted items could be added<br>within the BoQ as a part of the proposal. | The Bidder<br>Document<br>paragraph<br>states that<br>General Sp<br>conjunctio<br>(GCC), the<br>the Techni<br>Drawings<br>Contract".<br>works, In o<br>Please refe<br>and the wh |

#### **Final Response**

efer to revised GS131.34

efer to revised GS131.34

der is advised to read and evaluate the Bidding nts in whole. Please refer to the third ph of the General Specifications, GS 101, which at "The Scope of Works (SOW) and the Specifications (GS) shall be read in tion with the General Conditions of Contract the Particular Conditions of Contract (PCC), unical Specifications (TS), the Employer's and any other documents forming part of the t". As a sample, for the cofferdams and related n conjunction with the BOQ and Drawings, efer to the Technical Specifications, TS 200, whole of Section 203 - Temporary Works.

| Packages | Vol | Sec                      | Page No. | Clause No./Title                | Reference Text<br>(if necessary) | Clarification<br>Request  |   |
|----------|-----|--------------------------|----------|---------------------------------|----------------------------------|---|---|
| S-06     | 1A  | Volume 1A,<br>Section 4A | -        | BILLS OF<br>QUANTITIES<br>(BOQ) | -                                | Other than large creeks (as shown in the ITB drawings)<br>along the project alignment, the contractor is expected to<br>install culverts / drainages across the alignment (i.e., East<br>side<> West side) where the small creeks exist (e.g., Cor<br>CP05, refer to Drawing No. NSRP-DWG-VIA05-ST-0037<br>where the creek exist between P-904 and P-905 and for<br>CP06, refer to Drawing No. NSRP-DWG-VIA06-ST-0015<br>where the creek exist between P-1015 and P-1016).<br>However, quantities associated with these types of culverts /<br>drainages do not appear within the BoQ. This may imply<br>that the contractor is able to disconnect these small creeks<br>across the alignment. Please clarifiy if there is any drainage<br>/ culvert across the alignment. If so, the contractor kindly<br>request the Client to provide the BoQ / basis for all such | 1.) Yes, ther<br>alignment. I<br>Drainage D<br>2.)The BOQ<br>across the a<br>System and<br>Updated BO |
| S-06     | 1   | Volume 1,<br>Section 1   | ITB 13   | Format and Signing<br>of Bid    | -                                | In regards to the bid documentation and the submisson of<br>original copies, the Bidder kindly request the client to<br>clarify the following:<br>1. Whether or not the submission is required to be printed<br>based on single sided or double sided copy.<br>2. Whether or not the all of the submitted document pages<br>are required to have the signature on every single printed<br>page, especially including the method statement.  | 1. No specij<br>2. All to be<br>stated in the   |
| S-06     | 1   | Volume 1,<br>Section 1   | ITB 13   | Sealing and<br>Marking of Bids  | -                                | Considering the size of the original copy to be printed for<br>the submission, the contractor was wondering if the<br>contractor would be able to submit the original copy more<br>than one box instead of one envolope. The Bidder can<br>instead mark up "Original 1/2" and "Original 2/2", etc so<br>that the Client can easily recognize the order of the<br>document within the submission.<br>Please confirm if submitting the bid proposal in a separate<br>box is acceptable to the Client.   | Considering<br>for the Bid,<br>boxes. "On<br>procedure f  |

here were drainage/culvert across the t. Details were reflected in At-Grade Mainline P Drawings.

OQ shall be revised to include Drainage e alignment under the Bill No. 5 - Drainage nd River Bank Protection. BOQ shall be issued as Addendum 2.

cific requirement. be signed in accordance with requirements the Bidding Documents.

ing size and volume of documents to be printed id, Bidder is allowed to submit Bids in multiple One/Single Envelope" would refer to the e for Opening and Evaluation of Bids.

| Packages | Vol | Sec  | Page No. | Clause No./Title                          | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |
|----------|-----|--|----------|---|---|---|--|
|          |     | Volume 2,  |          | NSPR DWC                                  |   | As per "crack control recommendation" on Drawing No.<br>NSRP-DWG-VIA00-ST-0402, maximum temperature of<br>the concrete mixture at the the time of concrete pouring is<br>provided as follows:<br>- Pier Column and Head Stock at 24°C for 40 MPa<br>- Pile Caps at 28°C<br>However, the technical specification shown in TS 206.8.1   | The maxim<br>placing sho<br>should be a<br>mixing plan<br>Contractor<br>TS200 Clau                                   |
| S-06     | 2   | Section 6, II<br>Drawings                              | -        | NSRP-DWG-<br>VIA00-ST-0402                | -   | indicates that the maximum temperature of the concrete<br>mixture at the time of concrete pouring shall be limited to<br>30°C. In addition, DPWH Standard specifies that the<br>maximum temperature of the concrete mixture at the time of<br>concrete pouring shall be limited to 32°C.  | TS200 206.<br>the cooling<br>concreting<br>concrete ex   |
|          |     |  |          |   |   | The Bidder would like the Client kindly to clarify if the<br>Bidder can follow the technical specification (i.e., 30°C) or<br>the DPWH standard (i.e., 32°C).   | Drawing N<br>Addendum  |
| S-06     | 3   | Volume 3,<br>Section 8                                 | PCC 7    | SUMMARY OF<br>KEY DATES                   | -   | In regards to the Key date, the Bidder was wondering if (1) noise barriers (Parapet), (2) protective concrete layer and (3) precast cable trough cover needed to be completed by KD02 or KD06.  | Item (1), (2   |
| S-06     | 3   | Volume 3,<br>Section 8                                 | PCC 8    | SUMMARY OF<br>KEY DATES                   | KD 05<br>Provision of Access to Concourse<br>Paid/Unpaid area and<br>Platform area for CP NS-01<br>(trackwork and E&M Systems) to<br>commence installation of AFC and<br>PSD equipment. | Please clarify if the completion of all the roofing<br>membranes for stations is included in KD05 or other key<br>dates.  | Roofing sh   |
| S-06     | 2   | Volume 2,<br>Section 6, IB<br>GeneralSpecifi<br>cation | TS100-25 | 102.2.9 Removal of<br>Unsuitable Material | TS102.2.9<br>If evidence of contaminated soil is<br>foundwaste material.  | <ul> <li>Please clarify the following:</li> <li>(1) if the client measures such potentially contaminated soils within the project site. If so, please provide the Bidder with the data.</li> <li>(2) The BoQ does not contain any item associated with the treatment (or off-site transfer) associated with the contaminated soil. If there is any contaminated soils to be found within the project site, the Bidder kindly requests the client to provide the item within the BoQ that the Bidder can include the cost incurred due to managing contaminated</li> </ul> | (2)Please r<br>No. 1, Item<br>conjunction<br>118; Sub-S<br>Manageme<br>Waste (whi                                    |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings                 | -        | NSRP-DWG-<br>VIA00-ST-0951                | 21-M12×95 Elephant Foot   | The embedded anchors (i.e., 21-M12×95 Elephant Foot)<br>shown on the drawing do not appear not in the BOQ, please<br>clarify these embedded anchors will be installed by the<br>Bidder or not. If the Elephant Foots is expected to be<br>installed by the bidder, please provide the details on the<br>embedded anchors as a form of drawings together with<br>assocaited BOQ.   | The embed<br>Foot) - sho<br>drawing. The<br>to the Prece<br>206(3)b and<br>A, Section 2<br>Measurement<br>paragraphs |

imum temperature of fresh concrete at time of hould be between 26 to 30 degrees C and e achieved through normal precautions at the lant, for working in hot-humid climates. The or shall comply with the recommendations of lause 206.7.8.4 with regard to pre-cooling and 06.7.8.5 and TS200 Clause 206.7.8.5 regarding ing of the concrete. At no stage during the g process should the temperature of the fresh exceed 35 degrees C.

NSRP-DWG-VIA00-ST-0402 will be issued in m 3

(2) and (3) shall be completed by KD02

shall be completed by KD06.

aminated soil is part of GS118. Please refer to 2 Hazardous waste for its scope.

e refer to the Updated BOQ, Addendum 1, Bill m GS118-Environmental Management in ion with the General Specifications, Section GS -Section 118.5; Clause 118.5.2-Waste ment Plan; Sub-Clause 118.5.2.2-Hazardous hich includes the contaminated soil).

edded anchors (i.e., 21-M12×95 Elephant hould be installed in accordance with the These embedded anchors are subsidiary items ecast Segmental Box Girder Item Nos. 206(3)a, and 206(3)c. Please refer to the TS 200\_Annex in 206-Concrete Structures, Sub-section 206.1ment and Payment; Clause 206.1.2; Whole hs of Sub-Clause 206.1.2.1-General.

| Packages | Vol | Sec                                    | Page No. | Clause No./Title                      | Reference Text<br>(if necessary)   | Clarification<br>Request  |   |
|----------|-----|--|----------|---------------------------------------|--|---|---|
| S-06     | 3   | Volume 3,<br>Section 9                 | CF 7     | Contract<br>Agreement                 | Contract Form CF3<br>2. The following documents shall be<br>deemed to form       | According to the CF3, all the documents related to the Bid<br>and the following contract have the order to be read and<br>constructed as part of this Agreement.<br>The Bidder would like kindly the Client to inform the order<br>of all of the clarifications (i.e., queries) submitted to the<br>Client and replied by the Client within the Contract<br>documents in between (a) The Contract Agreement and (l)<br>Extracts from the Bidding Documents as submitted by the<br>Contractor and listed in the attachment-1 hereto. | Bidder is a<br>included in                        |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings | -        | -                                     | -  | Although the Bidder could find out the final elevations for<br>the maintenance road and associated ground elevations<br>along the alignment, the Bidder was not able to find out the<br>final ground elevations (i.e., z axis) to be built across the<br>alignment (i.e., x and y axes). The Bidder would like the<br>Client kindly to provide the final ground elevations that<br>need to be constructed by the Bidder.  | For the fin<br>associated<br>to Drawing           |
| S-06     | 2   | Volume 2,<br>Section 6, II<br>Drawings | -        | NSRP-DWG-<br>VIA00-ST-0421            | -  | According to the Typical Elevation shown in Drawing No.<br>NSRP-DWG-VIA00-ST-0421, piercap height is shown to<br>be 2150mm. However, the table shown below indicates the<br>range of the height (i.e., based on DD column) is between<br>2500mm and 3500mm.<br>Please clarify which one is correct.   | Dimension<br>replaced by<br>Drawing N<br>Addendum |
| S-06     | 2   | Volume 2<br>TS-<br>500_Annex A         | 70       | 563.1.1 /<br>Method of<br>Measurement | 563.1.1 Method of Measurement<br>Softscaping works will be a<br>Provisional Sum. | According to the BOQ, there are 3 softscape items; Item<br>No. 563(2)a, 563(4) and 563(5).<br>However, TS-500_Annex_A indicates that "Softscaping<br>works will be a part of the Provisional Sum."The Bidder<br>was wondering if, within any of the scope of work, there<br>are any additional softscape works to be performed.   | TS 563 Me<br>revised and                          |
| S-06     | 2   | Volume 2,<br>Drawing                   | -        | NSRP-DWG-BIN-<br>EL-5011              | -  | As shown on the single line diagram, each station possesses<br>small-capacity diesel generator.<br>However, the generator is not provided within BOQ. Please<br>advise how we should account for these generators in our<br>pricing.  |   |
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700   | -        | -                                     | -  | Please kindly provide Approved/Acceptable brands<br>(BMS/CCTV/Access control/Panelboard/Lighting<br>fixture/Fire Alarm) for the purpose of system integration of<br>all stations at OCC building, system compatibility and ease<br>of maintenance in the future.  | Brands for<br>component<br>equivalent             |

| Final Response   |
|--|
| advised that bidder query clarifications will<br>in item (d)   |
| nal elevations for the maintenance road and<br>I ground elevations along the alignment, refer<br>ng NSRP-DWG-VIA06-RD-2002 Note 5.4. |
| ns 2150 indicating the pier head depth shall be by "DD".   |
| NSRP-DWG-VIA00-ST-0421 will be issued in m 3   |
| lethod of Measurement and Payment will be<br>ad issued in Addendum 3   |
| fer to the Updated BOQ, Addendum 1.  |
| or this equipment, devices and other<br>nts shall be UL/NEMA listed or IEC<br>t approved standard.                                   |

| Packages | Vol | Sec   | Page No. | Clause No./Title                                     | Reference Text<br>(if necessary)   | Clarification<br>Request   |  |
|----------|-----|---|----------|--|--|--|--|
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700                    | -        | -  | -  | In terms of Communication system (BMS/CCTV/Access<br>control) including the fire alarm, the Bidder understands<br>that E&M system contractor will supply and install main<br>equipment, software and testing.<br>Please confirm the Bidder (i.e., Civil contractor) is only<br>responsible for items to be installed inside station as shown<br>on drawings and BOQ, with the confirmation of software<br>being out of the Bidder's scope of work.<br>If above mentioned works are the part of the Bidder's SoW,<br>please provide relevant drawings showing schematic<br>diagram, floor layout, system sequence, point schedule, etc. | It is confirm<br>and Fire D<br>the scope of<br>refer to the<br>2 and 4-3; J<br>Works cove<br>Detection &<br>Please refer<br>02_Book2 ( |
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700                    | -        | 701.3.4  | Provide anti-sway brackets on<br>horizontal tray assemblies at 3 meter<br>intervals.   | Please advise whether cable trays in all areas require anti-<br>sway brackets at every 3 meters.   | Cable tray :<br>requiremen<br>per manufo<br>validate.  |
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ              | -        | Conduit and Cable<br>Tray                            | -  | In the BOQ, there are items associated with 150, 400, and 600mm size. However, in the drawing, only 150 and 900mm size exist. Please provide the clarification on this discrepancy.  | Details on a<br>updated to<br>Please refe<br>following it<br>3.<br>PIN 707(1,<br>100mm(H)<br>PIN 707(1,<br>100mm(H)                    |
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ<br>Volume 2, | -        | NSRP-DWG-STA-<br>EL-5005                             | -  | Cable tray detail drawing shows the divider between<br>lighting and power cables, while the divider does not appear<br>in Panelboard incoming cables. However, the BoQ given to<br>the Bidder does not differentiate the cable trays depending<br>on the presence of the divder with the tray. Please clarify.   | trave tor in   |
| S-06     | 2   | Volume 2,<br>Drawing                                    | -        | NSRP-DWG-STA-<br>EL-5003<br>NSRP-DWG-STA-<br>EL-5004 | -  | There are two different drawings in terms of cable tray<br>support.<br>Please confirm that the Bidder can only follow the support<br>detail with rods.   | Treaded ro<br>EL-5003 w  |
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700                    | -        | 715.1.2  | The surveillance system shall consist<br>of CCTV cameras combination of<br>fixed and equipped with<br>Pan/Tilt/Zoom Lens System (PTZ)<br>located at the lobbies and entrances<br>and exits of Ground and Second<br>floors. | TS 715.1.2 shows "Combination of fixed dome and PTZ<br>camera".<br>However, drawings indicate the box type camera only with<br>housing, which does not appear in any of technical<br>specification.<br>In addition, BoQ only contains "CCTV Camera," which<br>does not appear either in the technical specification or<br>drawings.<br>Please advise if the Bidder follows the drawings or not. If<br>the Bidder follows the drawing, would it be possible to  | The Bidder<br>with the ap<br>Technical S<br>"CCTV Ca<br>General Sta<br>5001 Rev.2  |

#### **Final Response**

irmed that the Station BMS, Security System Detection and Alarm System are covered by of work of the civil works contractor. Please he Updated BOQ, Addendum 1; Bill Nos. 4-1, 4-; Part F.5-Electrical Works - for the Scope of vering BMS, Security System and Fire & Alarm System. For the drawing references, fer to the Bidding Documents, Volume 2; 2 (Architectural); 05\_S06 MPFS.

y system shall withstand earthquake (seismic ents). Supports and other fasteners shall be as facturer's recommendation, vendor to

*i drawings to be followed. BOQ already o match drawings.* 

fer to Addendum 2 which includes only the items for the Cable Tray in Bill Nos. 4-1 to 4-

(1)a --- Cable Tray w/ Cover, 900mm(W) x I) (1)e --- Cable Tray w/ Cover, 150mm(W) x I)

) shall be revised to separate / divide the cable incoming panel boards from the cable trays for ing and Power. Updated BOQ shall be issued dum 3.

ods (Hanger) will be used. NSRP DWG-STAwill be revised and issued as v 21.2z.

er should follow the drawing in conjunction appropriate sections and clauses of the I Specifications. The BOQ Item Description Camera" was adopted from the Legends of the Station drawing No. NSRP-DWG-STA-EL-.21.

| Packages | Vol | Sec  | Page No. | Clause No./Title | Reference Text<br>(if necessary)  | Clarification<br>Request   |   |
|----------|-----|--|----------|------------------|---|--|---|
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700                               | -        | 715.3            | A standby power pack shall be<br>provided capable of operating the<br>CCTV system continuously for eight<br>(8) hours minimum without<br>recharging.  | Although both drawings and BOQ specifies 2 hours UPS<br>for CCTV system, TS700 specifies eight (8) hours<br>operation minimum without recharging.<br>Please clarify this discrepancy in between.   | 1) c/o Desig<br>Drawings a<br>PIN 715(1)<br>for CCTV S<br>3, Part F.5<br>following d<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW |
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700                               | -        | 706.1.5          | Prepare a short circuit and<br>coordination study based on the<br>actual overcurrent protection devices<br>proposed for use. The study shall be<br>prepared by a locally registered<br>electrical engineer.   | Please confirm that the Bidder is responsible for support<br>only "Short circuit coordination study report" and others<br>(i.e., E&M contractor) will prepare and submit the report.   | Bidders sha<br>respective s<br>project stak<br>protection c<br>system com<br>lengths.                                 |
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ                         | -        | BMS              | -   | Two items: 713(8) and 713(9) in BoQ are specified as a<br>lump sum price in BMS BOQ.<br>However, the Bidder is not able to figure out quantities<br>since drawings are not provided.<br>Please provide either drawings or quantities of these two<br>items.  | Please refer<br>700_Annex<br>System; Sun<br>Clauses 713<br>Basis of Pa  |
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ<br>Volume 2,<br>Drawing | -        | -                | -   | In terms of quantities, there are several discrepancies<br>between BOQ and Drawings.<br>For example, quantities of cables, wires, conduits and trays<br>do not match in between BoQ and the drawing.<br>Please advise if the Bidder shall consider additional cost in<br>BOQ provided to the Bidder without revising quantities.<br>(For example, cables in BOQ is 100m, but shown to be<br>150m in the drawing. In this case the Bidder takes price<br>associated with 150m-long cable and plug in BOQ instead<br>of keeping the price associated with 100m-long cable) | The BOQ s<br>items for ca<br>BOQ shall  |
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ<br>Volume 2,<br>Drawing | -        | -                | -   | In terms of capacity, there are several discrepancies<br>between BOQ and Drawings.<br>For example, capacity of generator (250kVA and 313kVA)<br>and ATS (800AT and 225AT) are different in between the<br>BoQ and the drawing.<br>Please confirm which one is correct.   | The BOQ so<br>of the gener<br>Addendum  |
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700                               | -        | 701.2.2.5        | Provide heavy wall, high impact<br>strength, rigid PVC conforming to the<br>requirements of Philippine code<br>requirements.<br>Conduit and fittings shall be UL 651<br>listed and shall conform to Article<br>347 of the NEC for underground and<br>exposed use. | Please advise if the Bidder can use exposed PVC conduits that comply with Philippine Standard but not UL Listed.   | PVC shall o<br>(concealed)<br>equivalent s  |

#### **Final Response**

sign Team --- to clarify discrepancy between and TS

(1)h --- UPS, Backup Time: 2 Hours or more / System under BOQ Bill Nos. 4-1, 4-2, and 4-5 --- Electrical Works is based on the drawings:

*WG-CAB-EL-5803; WG-BAN-EL-5803; and, WG-CAL-EL-5803, rev. 21.2* 

hall also provide and validate based on their e scope and collaborate with other concerned ake holders for the short circuit analysis and n coordination study based on actual electrical opponents nameplate rating and actual circuit

fer to the Technical Specifications, TS ex A; Section 713-Building Management Sub-section 713.1-Measurement and Payment; 713.1.1-Method of Measurement and 713.1.2-Payment.

shall be revised for the appropriate work cables, wires, conduits and trays. Updated ll be issued as Addendum 2.

*Shall be revised for the appropriate capacities nerator sets. Updated BOQ shall be issued as m 2.* 

ll only be used in concrete embedded ed) Installations. PVC shall be UL-listed or at standard.

| Packages | Vol | Sec   | Page No. | Clause No./Title                                     | Reference Text<br>(if necessary)  | Clarification<br>Request   |   |
|----------|-----|---|----------|--|---|--|---|
| S-06     | 2   | Volume 2,<br>Drawing                            | -        | NSRP-DWG-STA-<br>EL-5001                             | 25. All lighting at fire exit shall be controlled by motion sensor.   | The Bidder is failed to locate motion sensor in any of the<br>drawings. The Bidder was wondering if the motion sensor<br>is integrated in each lighting fixture on the fire exit.<br>Also, if all lighting at fire exit is controlled by motion<br>sensor, how does the system of operation work since the<br>whole circuit is turned on/off by BMS. | Refer to Dr<br>5006/Motio<br>3  |
| S-06     | 2   | Volume 2,<br>Drawing                            | -        | NSRP-DWG-STA-<br>EL-5001                             | -   | Although the drawing only shows PTZ, Fixed dome, the<br>specification deals with several types of CCTV Camera<br>such as PTZ and Fixed dome.<br>Please clarify if the SoW only incudes the box type CCTV<br>Camera.  | The SoW w<br>depending<br>recomment   |
| S-06     | 2   | Volume 2,<br>Specification<br>TS 700            | -        | 716  | The work of this section covers the<br>furnishing, installing and placing in<br>operation of an electronically-<br>operated, supervised, conventional<br>fire alarm system. | Technical Specifications for FDAS requires Conventional<br>type, while FDAS riser diagram and layout implicates Fully-<br>addressable type. Please provide the Technical specs of<br>Fully-addressable type.   | FDAS is A<br>700  |
| S-06     | 2   | Volume 2,<br>Drawing<br>Specification<br>TS 700 | -        | 711.3.1<br>NSRP-DWG-BAN-<br>EL-5601                  | -   | Based on Technical Specification, HDPE conduits are<br>required for the down conductor.<br>However, PVC conduits are shown on the drawing.<br>Please kindly clarify.   | All non-me<br>be used in<br>be revised o  |
| S-06     | 2   | Volume 2,<br>Specification<br>TS 600            | -        | 624 HRV  | -   | For HRV equipment (All station), what is the design indoor<br>temperature and outdoor temperature?, What is the<br>condition during the stated temperature exchange?   | Refer to up<br>temperatur<br>5663 NSRI<br>ME-5663 I<br>temperatur<br>0114_06, N<br>CAL-ME-0 |
| S-06     | 2   | Volume 2,<br>drawing                            | -        | NSRP-DWG-BIN-<br>SN-6110<br>NSRP-DWG-PTA-<br>SN-6110 | -   | Please provide the length of collector pipe for 100Ø DS-41 to 48 on platform level as is not reflected from the ground floor, concourse and roof layout plan at Binan (griidline A-D,1; A-D,20), and Pacita station (gridline A-D,1; A-D,20).  | Please refe<br>6106 Rev 2<br>. These DS   |
| S-06     | 2   | Volume 2,<br>drawing                            | -        | NSRP-DWG-SPO-<br>SN-6108                             | -   | Please provide the layout of collector pipe line for 50Ø WS from concourse level to ground level for San Pedro station (gridline A,2; A,7; A,18; F,2; F,5; F,7; F,13).   | To be refle<br>SN-6104 w  |
| S-06     | 2   | Volume 2,<br>drawing                            | -        | NSRP-DWG-BIN-<br>SN-6126                             | -   | Please provide the elevation, material of pipe and isometric drawing of elevated pedestrean walkway at Binan station.  | For Elevat<br>Drain pipe<br>drawing fo<br>BIN-6126  |

| Final Response  |
|---|
| Drawing no. NSRP-DWG-STA-EL-<br>tion Sensor details will be issued in Addendum  |
| will include all types of CCTV cameras<br>g on application based on manufacturer's<br>ndation.  |
| Addressable type. See Revised Addendum 2 TS   |
| netallic conduits such as HDPE and PVC shall<br>n concrete-embedded applications. TS 700 to<br>l and issued as Addendum 3   |
| updated drawing HRV equipment schedule for<br>ure exchange condition NSRP-DWG-CAB-ME-<br>RP-DWG-BAN-ME-5662 NSRP-DWG-CAL-<br>REV 21.2. For outdoor and indoor<br>ure, please refer to NSRP-CAL-BAN-ME-<br>NSRP-CAL-CAB-ME-0111_05, NSRP-CAL-<br>-0117_05. |
|   |

fer to updated drawing NSRP-DWG-BIN-SN-21.2 and NSRP-DWG-PTA-SN-6104 Rev 21.2 OS have been reflected at Ground Level.

lected at the Ground Level. NSRP-DWG-SPOwill be revised and issued in Addendum 3

ation please refer to architectural drawings. De would be PVC Series 1000. isometric for Binan Pedestrian Walkway NSRP-DWG-6 will be issued in Addendum 3

| Packages | Vol | Sec   | Page No. | Clause No./Title                                      | Reference Text<br>(if necessary)   | Clarification<br>Request   |  |
|----------|-----|---|----------|---|--|--|--|
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ.<br>Volume 2,<br>Specification | -        | 607.2.2 Polyvinyl<br>Chloride Pipe and<br>Fittings    | <ol> <li>Polyvinyl chloride pipes and<br/>fittings shall be used for:</li> <li>a) Soil, waste, vents and drain pipe<br/>and fittings and downspouts</li> </ol> | For the pipe material used in Rainwater line downspout, the<br>Bidder has found the discrepancy in between the general<br>notes with BOQ (i.e., refers to Stainless steel) and the<br>technical specification (i.e., refers to PVC).<br>Please clarify which one the Bidder must follow. | Please adh<br>Stainless Si<br>drawing No<br>the Drawin<br>Material Sp                    |
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ.<br>Volume 2,<br>Specification | -        | 618.2.5 Design<br>conditions                          | -  | Which shall govern for the flow rate capacity of Waste<br>Water Treatment Plant in the BOQ or Equipment Schedule<br>at layout plans or Technical specification?  | Technical S<br>Please refe   |
| S-06     | 1   | Volume 1,<br>Part IA,<br>Section 4A<br>BOQ.<br>Volume 2,<br>drawing       | -        | -   | -  | Please provide us with drawings and specification<br>associated with Floor Mounted Type Air Conditioning Unit<br>with Air Cooled Condenser Unit (ACUF).  | Refer to up<br>NSRP-DW<br>5601, NSR<br>ME-5601, 1<br>NSRP-DW<br>5638 Rev 2<br>Rev 21. Fo |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-BIN-<br>ME-5608 NSRP-<br>DWG-BIN-ME-<br>5661 | -  | Total airflow capacity of SEF-02 in schedule does not<br>match with the total airflow capacity of EAG connected.<br>Please clarify.  | Schedule w<br>will be revi,<br>grille.   |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-BIN-<br>ME-5632                              | -  | Please indicate the size of the grille connected to HRV-08.  | This must l<br>5632 will b   |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>ME-5662 NSRP-<br>DWG-PTA-ME-<br>5632 | -  | Airflow Supply/Exhaust of HRV-11 in schedule does not match with the drawing. Please clarify.  | Schedule w<br>Sheet NSR<br>issued in au  |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>ME-5631                              | -  | In the Bidder's view, the size of this seems to be 1400 x 3000 instead of 1400 x 300. Please clarify.  | Please refe  |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>ME-5632                              | -  | Please provide the sizes of ducts serving EF-08 and EF-09.   | This must l<br>5632 to be  |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>SN-6104                              | -  | Is this 50-diameter ACDS-04 going to 250 diameter drain pipe as well? Same goes with other ACDS.   | ACDS will  |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>SN-6104                              | -  | Where will these 100-diameter downspouts come from?  | These down   |
| S-06     | 2   | Volume 2,<br>Drawing  | -        | NSRP-DWG-PTA-<br>FS-6608                              | -  | Provide RN sizes.  | Please refe<br>PTA-FS-66   |
| S-07     | 2   | Volume 2, 02<br>Book 1<br>(CIVIL), 04<br>CP S07<br>DPSFE                  | 151      | NSRP-DWG-DEP-<br>DR-2709                              | NSRP-South Depot Manhole Detail<br>Type I  | Please provide specification of manhole cover  | Refer to TS<br>BASINS.   |

#### **Final Response**

*The re to the BOQ Item. The BOQ Item, Steel Rain Water Pipe is consistent with the No. NSRP-DWG-STA-SN-8001 Rev. 21; Below ing's General Notes, Please refer to the Specifications, Downspout.* 

Specification & Drawings shall govern.

fer to the latest BOQ issued in Addendum 2

updated drawing NSRP-DWG-CAB-ME-5601, WG-CAB-ME-5661, NSRP-DWG-BAN-ME-RP-DWG-BAN-ME-5661,NSRP-DWG-CAL-, NSRP-DWG-CAL-ME-5661 Rev 21.2. Refer WG-BAN-ME-5638, NSRP-DWG-CAL-ME-21.1. Refer to NSRP-DWG-CAB-ME-5638 For specification, please see TS600.

will govern. Sheet NSRP-DWG-BIN-ME-5608 vised in Addendum 3. Must be 1571 lps each

t be 300x300. Sheet NSRP-DWG-BIN-MEbe revised and issued in Addendum 3

will govern, must be 14 lps design drawing. RP-DWG-PTA-ME-5632 will be revised and addendum 3

fer to NSRP-DWG-PTA-ME-5631 Rev 21

t be 300x150. Sheet NSRP-DWG-PTA-MEe revised in addendum 3

*Il be going to 250mm drain pipe.* 

vnspouts are from the canopy.

fer to Riser Nipple Schedule at NSRP-DWG-6608 Rev 21.1.

TS 111 MANHHOLES, INLETS AND CATCH

|   | Packages | Vol | Sec   | Page No. | Clause No./Title                 | Reference Text<br>(if necessary)          | Clarification<br>Request   |  |
|---|----------|-----|---|----------|----------------------------------|---|--|--|
|   | S-07     | 2   | Volume 2, 02<br>Book 1<br>(CIVIL), 04<br>CP S07<br>DPSFE    | 155      | NSRP-DWG-DEP-<br>DR-2714         | NSRP-South Depot Manhole Detail<br>Type M | Please provide specification of cover  | Refer to TS<br>BASINS.   |
| - | S-07     | 1   | Volume 1,<br>Sec.4A BOQ                                     | 161      | Bill of Quanitites<br>No. 4-2.12 | Supply and Fire Water Tank 1              | <ol> <li>Please confirm if the quantites of following items are<br/>included in the pay item BOQ 4-2.13 Pump House for Fire<br/>Water Tank 1, if not, please provide pay item:</li> <li>1.a) Structural Concrete for Beam</li> <li>1.b) Structural Concrete for Reinforced Concrete Wall<br/>(RCW)</li> <li>1.c) Structural Concrete for Elevated Slab</li> </ol>  | It is confirm<br>Concrete fo<br>Concrete W<br>Slab are ind<br>BOQ, Adde<br>405(9)b, an |
|   | S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07 Struc | 4 of 9   | NSCRP-DWG-<br>WPH1-ST-4201       | Waterproofing Membrane                    | <ul> <li>2. In TS 514.1.1 Elastomeric Waterproofing are for water tanks such as potable tanks, domestic and fire tanks, waste water tanks and swimming pool, Liquid Polyurethane waterproofing are for decks, balconies and roof slab.</li> <li>Query : Please confirm that Polyurethane Membrane System Waterproofing as per BOQ will be used in External Wall. If yes, Is there any requirements of waterproofing in the Internal Wall. If yes, please provide pay item</li> </ul> | Pump Roon<br>NSRP-DW   |
| - | S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07 Arch  | 4 of 6   | NSRP-DWG-<br>WPH1-AR-3201        | Pump House for Fire Water Tank 1          | 1. Please provide specification and pay item for<br>Waterproofing at RC Water Tank Slab  | Please refer<br>4-2.13, Part<br>Please also<br>500, Section                            |
|   | S-07     | -   | -   | 4 of 6   | NSRP-DWG-<br>WPH2-AR-3201        | Pump House for Fire Water Tank 2          | 1. Please provide specification and pay item for<br>Waterproofing at 150mm thk RC Water Tank Slab  | Please refer<br>4-2.15, Part<br>Please also<br>500, Section                            |

**Final Response** 

TS 111 MANHHOLES, INLETS AND CATCH

irmed that the quantities of Structural for Beam, Structural Concrete for Reinforced Wall, and Structural Concrete for Elevated included the BOQ. Please refer to the Updated dendum 1; Bill No. 4-2.13, Item Nos. 405(8)b, and 405(10)b.

oom also has PU waterproofing, please refer to WG-WPH1-AR-3201.

fer to the Updated BOQ, Addendum 1; Bill No. art C.2, Waterproofing, Item No. D514(2). so refer to the Technical Specifications, TS ion 514-Waterproofing. fer to the Updated BOQ, Addendum 1; Bill No.

art C.2, Waterproofing, Item No. D514(2). so refer to the Technical Specifications, TS ion 514-Waterproofing.

| Pack | cages | Vol | Sec   | Page No.                                    | Clause No./Title   | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
|------|-------|-----|---|---|--|--|---|--|
| S-6  | 07    | 2   | Volume 2, 01<br>Specification,<br>02 TS,<br>SCRP_TS<br>500_Annex A<br>Volume 2, 02<br>Book 2<br>(Architectural)<br>, 02 SO7<br>STRUC and<br>01 SO7<br>ARCH<br>Volume 1A<br>Sec.4A BOQ | TS-500–<br>Annex A - 18<br>5 of 5<br>5 of 5 | Panels and<br>Accessories<br>a. NSRP-DWG-<br>LGS-ST-4131 and<br>NSRP-DWG-LGS-<br>AR-3601<br>Bill of Quantities 4 | TS 512.1.1 Pre-painted Hot Dip<br>Galvanized Steel Sheet Roofing<br>(ZAM) is measured in "Square<br>Meter" and rate shall be with<br>T=30mm Non-Combustible Splayed<br>Polyurethane Form (please refer to<br>Drawings for proper description)<br>BOQ - D512(2) - Pre-painted Hi-Rib<br>Zinc-Aluminum-Magnesium (ZAM)<br>Roofing  | <ul> <li>There is conflict in Specification, Structural Drawing,<br/>Architectural Drawing, and Schedule of Finishes and BOQ:</li> <li>a. Structural Drawing (NSRP-DWG-LGS-ST-4131) -</li> <li>0.50mm thk Pre-painted GI Roofing</li> <li>b. Architectural Drawing (NSRP-DWG-LGS-AR-3601) -</li> <li>0.60mm thk Composite Metal Roofing w/ 108mm thk<br/>Polyisocyanurate Foam Insulation; Prepainted Finish</li> <li>c. Schedule of Finishes on Architectural Drawing (NSRP-<br/>DWG-LGS-AR-3601) - 0.60mm thk Long Span Rib Type<br/>Metal Roofing; Fluoro Urethane Pre-Painted Finish</li> <li>Query: Please verify conflict.</li> </ul> | a. Structura<br>DWG-LGS-<br>b. "Pre-pai<br>(ZAM) roof<br>AR-3601 to<br>Addendum<br>c. "Pre-pai<br>(ZAM) roof<br>AR-3601 to<br>Addendum |
| S-(  | 07    | 1   | Volume 1, 1.3<br>CP S-07<br>Vol.1A<br>Sec.4A BOQ,<br>Bill No. 3   | 30 of 225                                   | Bill of Quantites<br>No. 3<br>Depot Underpass  | BOQ - 125 (1) Sidewalk (t=100mm)   | Please confirm our understanding that the pay item 125 (1)<br>Sidewalk (t=100mm) shall be the 100mm thk PCC<br>Pavement for Road 10 Shared Use Path   | It is confirm<br>(t=100mm)<br>for Road 10  |
| S-(  | 07    | 2   | Volume 2, 01<br>Specification,<br>02 TS,<br>SCRP_TS<br>200_Annex A<br>Volume 1A<br>Section 4A<br>BOQ  | TS-200–<br>Annex A - 15<br>24 - 25 of 225   | of Measurement,<br>Geosynthetic  | TS 205.1.1<br>The measurement for payment for<br>Structural Concrete and Reinforcing<br>Steel shall be measured and paid for,<br>in accordance with Section 206<br>Concrete Structures, and Section 207<br>Reinforcing Steel.<br>The construction of Geosynthetics<br>Reinforcement Soil (GRS) consisting<br>of reinforced backfill and cast in<br>place concrete wall shall be measured<br>in "square meter".<br>BOQ<br>205(8) Embankment for GRS<br>Retaining Wall (Selected Borrow<br>Material)<br>206(6)a Structural Cast in Situ<br>Concrete, 40 Mpa for GRS<br>207(1)c Reinforcing Steel Grade 60<br>for Structure in Depot<br>205(2) Geogrid, 37.50 kn/m<br>205(3) Geogrid, 75 kn/m | <ol> <li>Please confirm the following:         <ol> <li>a. Embankment for GRS Retaining Wall is included in pay item 205(8)</li> <li>b. Cast in Place Concrete for GRS is included in pay item 206(6)a</li> <li>c. Reinforcing Steel for GRS is included in pay item 207(1)c</li> <li>d. Pay item 205(2) &amp; 205(3) are for area per layer of Geogrid</li> </ol> </li> </ol>  | 1.a. Yes. Co<br>1.b. Yes. Co<br>1.c. Yes. Co<br>1.d. Yes. Co   |

#### **Final Response**

ural drawings to be updated. Sheet NSRP-SS-ST-4131 will be issued in Addendum 3 painted Hi-Rib Zinc-Aluminum-Magnesium pofing" will govern. Sheet NSRP-DWG-LGSto be revised as Rev21.2 will be issued in m 3 painted Hi-Rib Zinc-Aluminum-Magnesium

pofing" will govern. Sheet NSRP-DWG-LGSto be revised as Rev21.2 will be issued in m 3

irmed that Pay Item 125(1) - Sidewalk n) pertains to the 100mm thk. PCC Pavement 10 shared use path.

Confirmed. Confirmed. Confirmed. Confirmed.

| Packages | Vol | Sec   | Page No.   | Clause No./Title  | Reference Text<br>(if necessary)  | Clarification<br>Request   |   |
|----------|-----|---|--|---|---|--|---|
| S-07     | 2   | Volume 2, 02<br>Book 1<br>(Civil),  | 34 of 127  | NSRP-DWG-DEP-<br>RD-1928                                    | GRS Retaining Wall Type 3,<br>Reinforced Concrete Slab  | Please provide pay item for Reinforced Concrete Slab   | The quantit<br>pay item 20                              |
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 02 S07<br>STRUC  | 2 of 13<br>8 of 13   | NSRP-DWG-TMO<br>ST-4101<br>NSRP-DWG-TMO<br>ST-4301          | Track Maintenance Office - Pile Cap   | Please verify conflict in Pile Cap Schedule, indicated in Pile<br>Setout Plan sheet NSRP-DWG-TMO-ST-4101, dimensions<br>is 850mm x 850mm x 1250mm, while in Reinforcement<br>Details sheet NSRP-DWG-TMO-ST-4301, it is 850mm x<br>700mm x 1600mm. Kindly confirm which dimensions shall<br>govern.   | The pile cap<br>1600mm. S<br>NSRP-DW                    |
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 02 S07<br>STRUC<br>Bid_Bulletin<br>No. 11,<br>Volume 1A<br>Sec 4A BOQ            | 4 of 19  | NSRP-DWG-WRS<br>ST-4121<br>Bill of quantities 4-<br>2.2 WRS | Wheel Re-Profiling Shop - Concrete<br>Topping at Service Pit<br>405(7)b Structural Concrete, Class<br>"AAA" (31 Mpa) for Slab on Fill (At-<br>Grade Beam) | Our understanding, the Concrete Topping with thickness of 500mm to 800mm is included in pay item 405(7)b, if not, please provide pay item  | Yes, Item 4   |
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 02 S07<br>STRUC and<br>01 S07 ARCH   | 2 of 57  | NSRP-DWG-LRS-<br>ST-4121<br>NSRP-DWG-LRS-<br>AR-3005        | LRS - Slabs on Fill elevation   | <ul> <li>Please verify conflict in Grid 16 and 24 plan,</li> <li>a) Ground Floor Framing Plan sheet NSRP-DWG-LRS-ST-4121, elevation of ground floor slabs of rooms is FGL -50,</li> <li>b) Schedule of Finishes sheet NSRP-DWG-LRS-AR-3005, room nos. 108-112, 113, and 104-105 are FGL -100, FGL - 300, and FGL -500, respectively.</li> <li>Which shall govern.</li> </ul> | a. Elevation<br>LRS-ST-41<br>b. this will<br>3005 Rev21 |
| S-07     | 2   | Bid_Bulletin<br>No. 11,<br>Volume 2,<br>02_Book 2,<br>02_S07<br>STRUC, CP S-<br>07_07_DHS_<br>ST                                | NSRP-DWG-<br>DHS-ST-<br>4101_[21.1]<br>and NSRP-<br>DWG-DHS-<br>ST-<br>4111_[21.1] | Hazardous Store<br>Structural                               | Foundation (F1)   | Please verify conflict in plan, dimension for Foundation<br>(F1) as shown in plan.   | Sheet NSRI<br>and updated                               |
| S-07     | 2   | Bid_Bulletin<br>No. 11<br>Addendum#1<br>and Site Data,<br>Volume 2,<br>02_Book 2,<br>02_S07<br>STRUC, CP S-<br>07_07_DHS_<br>ST | NSRP-DWG-<br>DHS-ST-<br>4121_[21.1]  | Hazardous Store<br>Structural                               | Lean Concrete thickness   | Please verify conflict in plan, lean concrete thickness in<br>typical Section Footing (F1) detail is 100mmthk while in<br>Section 3 is 50mmthk. which shall govern.  | Sheet NSRI<br>and update                                |

# **Final Response** ntity of reinforced concrete slab is included in 206(6)i. cap schedule to be 850mm x 850mm x Sheets NSRP-DWG-TMO-ST-4101 and WG-TMO-ST-4301 will be revised and issued dum 3 405(7)b includes the concrete topping. ons on the drawings on sheet NSRP-DWG-4121 will be revised and issued in Addendum 3 ill govern, see issued NSRP-DWG-LRS-AR-21. **RP-DWG-DHS-ST-4101** details to be revised ted in Addendum 3 **RP-DWG-DHS-ST-4121** details to be revised ted in Addendum 3

| Packages | Vol | Sec  | Page No.                            | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request  | Final Response  |
|----------|-----|--|-------------------------------------|---|--|---|---|
| S-07     | 2   | Bid_Bulletin<br>No. 11,<br>Volume 2,<br>02_Book 2,<br>02_S07<br>STRUC, CP S-<br>07_07_DHS_<br>ST   | NSRP-DWG-<br>DHS-ST-<br>4101_[21.1] | Hazardous Store<br>Structural -<br>Foundation Plan                        | Thickness of Slab on Fill  | Please verify conflict in slab thickness, in foundation plan is 180mm while in section 1 is 200mm. Which shall prevail.   | Sheet NSRP-DWG-DHS-ST-4101 details to be revised<br>and updated in Addendum 3   |
| S-07     | 2   | Bid_Bulletin<br>No. 11,<br>Volume 2,<br>02_Book 2,<br>02_S07<br>STRUC, CP S-<br>07_07_DHS_<br>ST<br>Bid_Bulletin<br>No. 11,<br>Volume 1A<br>Sec 4A BOQ | NSRP-DWG-<br>DHS-ST-<br>4111_[21.1] | Hazardous Storage<br>Bill of Quanitites<br>No. 4-2.6<br>Hazardous Storage | BOQ - 412(4) CHB Wall, Non-Load<br>Bearing, (Including Reinforcing             | <ul> <li>a) Drawing NSRP-DWG-DHS-ST-4111_[21.1] and NSRP-DWG-DHS-AR-3201 - walls are reinforced concrete</li> <li>b) Schedule of Finishes NSRP-DWG-DHS-AR-3601 - RC wall dimension is 200mm x 800mm</li> <li>c) BOQ 412 (4) CHB Wall NLB (42 sq.m.) and 405(8)b (2 cu.m.only)</li> <li>Query: Please verify conffict</li> </ul> | The BOQ shall be revised for the appropriate quantity<br>and Item of Work for the Reinforced Concrete Wall.<br>Updated BOQ shall be issued as Addendum 3. |
| S-07     | 1A  | Bid_Bulletin<br>No. 11,<br>Volume 1A<br>Sec 4A BOQ   |                                     | Bill of Quanitites<br>No. 4-2.6<br>Hazardous Storage                      |  | Please verify BOQ pay item D544(3), please provide drawing.   | The BOQ shall be revised to delete Item D544(3).<br>Updated BOQ will be issued as Addendum 3  |
| S-07     | 2   | Bid Bulletin<br>11, Volume 2,<br>01Specificatio<br>n, 02 TS  | TS 500 - 60                         | 9) Roofing Works<br>and Exterior<br>Finishing<br>a. Metal Canopy          |  | If specification will govern please verify BOQ item D512(2).  | The BOQ shall be revised for the appropriate Item of<br>Work. Updated BOQ shall be issued as Addendum 3.  |
| S-07     | 2   | Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch   | NSRP-DWG-<br>DEP-AR-<br>3401        | <b>,                               </b>                                   | 0.6mmthk Long Span Rib Type Metal<br>Roofing, Flourourethane painted<br>Finish | If specification will govern please verify BOQ item D512(2).  | The BOQ shall be revised for the appropriate Item of<br>Work. Updated BOQ shall be issued as Addendum 3.  |
| S-07     | -   | -  | -                                   | Typical Section   | -  | If specification will govern please verify BOQ item D512(2).  | The BOQ shall be revised for the appropriate Item of<br>Work. Updated BOQ shall be issued as Addendum 3.  |
| S-07     | 1A  | Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ  | -                                   | Bill of Quantities 4-<br>3.2 Pedestrian Shed                              | BOQ D512(2) Pre-painted Hi-Rib   | If specification will govern please verify BOQ item D512(2).  | The BOQ shall be revised for the appropriate Item of<br>Work. Updated BOQ shall be issued as Addendum 3.  |
| S-07     | 2   | Bid Bulletin<br>11, Volume 2,<br>01Specificatio<br>n, 02_TS  | TS 500 - 60                         | 9) Roofing Works<br>and Exterior<br>Finishing<br>a. Metal Canopy          |  | If specification will govern please verify BOQ item D512(2).  | The BOQ shall be revised for the appropriate Item of<br>Work. Updated BOQ shall be issued as Addendum 3.  |
| S-07     | 2   | Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch   | NSRP-DWG-<br>BPS-AR-3601            |   | 0.6mmthk Long Span Rib Type Metal<br>Roofing, Flourourethane painted<br>Finish | If specification will govern please verify BOQ item D512(2).  | The BOQ shall be revised for the appropriate Item of<br>Work. Updated BOQ shall be issued as Addendum 3.  |

| Packages  | Vol | Sec  | Page No.   | Clause No./Title   | Reference Text   | Clarification   |  |
|-----------|-----|--|--|--|--|---|--|
| i uchuges |     | Sec  | I age 110.   |  | (if necessary)   | Request   |  |
| S-07      | -   | -  | -  | Typical Section  | 0.6mmthk Long Span Rib Type Metal<br>Roofing, Flourourethane painted<br>Finish | If specification will govern please verify BOQ item D512(2).  | The BOQ s<br>Work. Upd   |
| S-07      | 1A  | Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ  | -  |  | BOQ D512(2) Pre-painted Hi-Rib<br>Zinc-Aluminum-Magnesium (ZAM)<br>Roofing     | If specification will govern please verify BOQ item D512(2).  | The BOQ s<br>Work. Upd   |
| S-07      | 2   | Bid Bulletin<br>11, Volume 2,<br>01Specificatio<br>n, 02_TS  | TS 500 - 60  | <ul><li>9) Roofing Works<br/>and Exterior<br/>Finishing</li><li>a. Metal Canopy</li></ul>  | Zinc coated steel sheet T=0.6mm,<br>H=25mm                                     | If specification will govern please verify BOQ item D512(2).  | The BOQ s<br>Work. Upd   |
| S-07      | 2   | Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch   | NSRP-DWG-<br>MPS-AR-<br>3601   | Typical Roof Plan  | 0.6mmthk Long Span Rib Type Metal<br>Roofing, Flourourethane painted<br>Finish | If specification will govern please verify BOQ item D512(2).  | The BOQ s<br>Work. Upd   |
| S-07      | -   | -  | -  | Typical Section  | Pre-painted Hi-Rib Zinc - Aluminum -<br>Magnesium (ZAM) Roofing                | If specification will govern please verify BOQ item D512(2).  | The BOQ s<br>Work. Upd   |
| S-07      | 1A  | Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ  | -  | Bill of Quantities4-<br>2.18 Depot<br>Motorbike Parking<br>Shed  | BOQ D512(2) Pre-painted Hi-Rib<br>Zinc-Aluminum-Magnesium (ZAM)<br>Roofing     | If specification will govern please verify BOQ item D512(2).  | The BOQ s<br>Work. Upd   |
| S-07      | 1A  | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07<br>ARCH<br>Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ | NSRP-DWG-<br>LOS-AR-<br>3201 AND<br>NSRP-DWG-<br>LOS-AR-<br>3501<br>NSRP-DWG-<br>LOS-AR-<br>3601 | <ul> <li>2/-: Right Side <ul> <li>(East) Elevation</li> <li>3/-: Left Side</li> </ul> </li> <li>(West) Elevation</li> <li>4/-: Rear Side</li> <li>(South) Elevation</li> <li>6/-: Blow Up <ul> <li>Section</li> </ul> </li> <li>Exterior Schedule <ul> <li>Of Finishes: Chb</li> <li>Wall</li> </ul> </li> <li>Bill Of Quantities 4</li> <li>2.5 Oil Storage For</li> <li>Light Repair Shop</li> </ul> |  | a) Drawing NSRP-DWG-LOS-ST-4111_[21.1] and NSRP-<br>DWG-LOS-AR-3201 - walls are reinforced concrete<br>b) Schedule of Finishes NSRP-DWG-LOS-AR-3601 -<br>150mmthk CHB w/ 25mm plastered both sides, paint finish<br>c) BOQ 412 (4) CHB Wall NLB (32 sq.m. ) and 405(8)b (1<br>cu.m.only)<br>Query: Please verify conlfict | 1.) Archited<br>3601 to be t<br>2.) Yes it sl<br>issued in At<br>412(4) - Cl<br>Reinforcing<br>405(8)b - S<br>for Reinfor<br>revised). |

#### **Final Response**

Shall be revised for the appropriate Item of odated BOQ shall be issued as Addendum 3.

Shall be revised for the appropriate Item of odated BOQ shall be issued as Addendum 3.

Shall be revised for the appropriate Item of odated BOQ shall be issued as Addendum 3.

Shall be revised for the appropriate Item of odated BOQ shall be issued as Addendum 3.

*9 shall be revised for the appropriate Item of odated BOQ shall be issued as Addendum 3.* 

Shall be revised for the appropriate Item of odated BOQ shall be issued as Addendum 3.

tectural drawing sheet NSRP-DWG-AR-LOSe revised and issued in Addendum 3 should be RC Wall. BOQ will be revised and Addendum 3 CHB Wall, Non-Load Bearing, (Including ing Steel); t=150mm (to be deleted); and - Structural Concrete, Class "AAA" (31 Mpa)

Forced Concrete Wall (RCW) (quantity to be

| Packages | Vol | Sec   | Page No.   | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request  |   |
|----------|-----|---|--|---|--|---|---|
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07<br>ARCH   | TS 500 - 394<br>NSRP-DWG-<br>FPH1-AR-<br>3201<br>NSRP-DWG-<br>FPH1-AR- | TS 548 Painting<br>Exterior Schedule<br>Of Finishes<br>3/-: Left Side (West<br>Elevation)                   | elastomeric painted finish   | please verify conflict in plan. which paint finish shall<br>govern.   | a) Schedule<br>Plaster on b<br>govern. She<br>revised and                           |
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07 Arch<br>Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ | 3101   | 4/-: Right Side<br>(East Elevation)<br>Pump House for<br>Fire Water Tank 1<br>Bill of Quanitities 4<br>2.13 | wall with Semi Gloss Latex<br>Trench Drain w/ Stainless Steel<br>Grating<br>BOQ  | Please verify there is trench drain in plan, Please confirm if<br>the concrete and reinforcement is included in BOQ payitem<br>405(7)b and 403(1) respectively. |   |
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07 Arch<br>Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ | NSRP-DWG-<br>WPH2-AR-<br>3201  | 2.15  | BOQ<br>405(7)b Structural Concrete, Class<br>"AAA" (31 Mpa) for Slab on Fill (At-<br>Grade Beam)<br>403(1) Reinforcing Steel, Grade 40 | Please verify there is trench drain in plan, Please confirm if<br>the concrete and reinforcement is included in BOQ payitem<br>405(7)b and 403(1) respectively. |   |
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07<br>ARCH   | WRS-AR-<br>3501  | Meeting room blow<br>up plan<br>Interior schedule of<br>finishes: meeting<br>room - floor                   | 600mm x 600mm x13mm<br>Homogenous Floor Tile   | Please verify conflict in plan, which shall govern  | "600mm x (<br>will govern.<br>revised and   |
| S-07     | 2   | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07<br>ARCH   | NSRP-DWG-<br>WRS-AR-<br>3501<br>NSRP-DWG-<br>WRS-AR-<br>3601           | 3/-: Section<br>Interior Schedule<br>Of Finishes:<br>Meeting Rm - Wall<br>Finishes                          | On Standard Metal Framing  | Please verify conflict in plan, which shall govern  | "0.60 mm t<br>102mm Thl<br>Painted Fin<br>Lining At I<br>govern. She<br>revised and |

ule of Finishes: 150mmthk with 25mmthk n both sides, elastomeric painted finish will Theet NSRP-DWG-FPH1-AR-3101 will be nd issued in Addendum 3


fer to drawing No. NSRP-DWG-WPH1-AR-21. It is confirmed that the BOQ Item 405(7)b e (structural) concrete while Item 403(1) to the reinforcement (i.e. Reinforcing Steel, )

fer to drawing No. NSRP-DWG-WPH2-AR-21. It is confirmed that the BOQ Item 405(7)b e (structural) concrete while Item 403(1) to the reinforcement (i.e. Reinforcing Steel,

x 600mm x13mm Homogenous Floor Tile" rn. Sheet NSRP-DWG-WRS-AR-3601 will be nd issued in Addendum 3

n thk Composite Metal Wall Panel With Thk Polyisocyanura Te Foam Insulation; Pre-Finish With 12mmthk Gypsum Board Dry t Interior On Standard Metal Framing" will Theet NSRP-DWG-WRS-AR-3601 will be nd issued in Addendum 3

|    | Packages | Vol    | Sec   | Page No.                                 | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |             |            |
|----|----------|--------|---|--|---|--|---|--|-------------|------------|
|    | S-07     | Book 2 | Volume 2, 02<br>Book 2                                | NSRP-DWG-<br>WRS-AR-<br>3301             | Reflected Ceiling<br>Plan: Toilet Rm -<br>Ceiling Finishes      | WRS<br>600mm x 600mm x 12mmthk.<br>Acoustic Board With Foil Backing  | Please verify conflict in plan, which shall govern  | Schedule of<br>3301 will be                                |             |            |
|    |          |        | ARCH WR   | NSRP-DWG-<br>WRS-AR-<br>3601             | Interior Schedule<br>Of Finishes: Toilet<br>Ceiling Finishes    | 12mmthk Moisture Resistant Gypsum<br>Board on Standard Metal Frame (M-<br>BAR) with Painted Finish   |   |  |             |            |
| •  |          |        | Volume 2, 02<br>Book 2<br>(Architectural)<br>, 01 S07 |  | 2) Site Work  | Reinforced concrete with Stainless<br>Steel grating  |   |  |             |            |
|    | S-07     | 2      | ARCH  | TS 500<br>Architectural<br>Works         | MPS Exterior<br>Schedule Of<br>Finishes                         | 9mmthk. Stainless Steel grating  | Please verify conflict in plan. Please confirm if Stainless   | Stainless sta<br>drawing shi                               |             |            |
|    | 5 07     | 2      | 2   |  | NSRP-DWG-<br>MPS-AR-<br>3601                                    | 2/-: Motorbike<br>Parking Shed<br>Section  | 325mm x 350mm Catch Basin with<br>9mmthk. Cast Iron Gratings  | Steel Grating shall govern as per Technical Specs and BOQ. | revised and |            |
|    |          |        | Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ   |  | Bill Of Quantities4-<br>2.18 Depot<br>Motorbike Parking<br>Shed | BOQ D506(3)f Stainless Steel<br>Gratings for Catch Basin   |   |  |             |            |
| S- | S-07     | 2      | · · · · ·   |  | Gf Reflected<br>Ceiling Plan                                    |  | Please verify conflict in plan for Ceiling finishes of Kitchen and Dining Area. Which shall govern. | DWG-CNI  |             |            |
|    |          |        |   |  | , 01 S07<br>ARCH  | NSRP-DWG-<br>CNT-AR-<br>3601   | Interior Schedule<br>Of Finishes  | rior Schedule 12mmthk Moisture Resistant Gypsum            |             | Addendum . |
|    | S-07     |        | Bo<br>2 (Archi  | Volume 2, 02<br>Book 2<br>CNT-AR-        | Floor Plan & 2/-:<br>South Elevation                            | Canteen<br>D2 (1100x2700mm Single-Leaf Fire-<br>Rated Steel Flush Door W/ Glass &<br>Louver Transom; In Flourourethane<br>Oven-Baked Fin. Steel Sheet T=1.6<br>Frame Glass Pane: 6.0 Thk. Frosted<br>Refer To W1 For The Finish Of Glass<br>Panel & Aluminum Louver Transom) | Please verify conflict in plan. Which shall govern.   | Schedule of<br>DWG-CNT-<br>Addendum                        |             |            |
|    |          |        | ARCH  | DRG. NO.<br>NSRP-DWG-<br>CNT-AR-<br>3601 | Schedule Of Door  | D3: 900x2100mm Single-Leaf Sliding<br>Hanger Door; In Flourourethane<br>Oven-Baked Fin. Steel Sheet T=1.6<br>Frame Glass Pane: 6.0 Thk. Frosted<br>Louver: Louver W/ Stainless Insect<br>Screen  |   |  |             |            |



| Packages | Vol | Sec   | Page No.   | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request   |                              |
|----------|-----|---|--|---|--|--|------------------------------|
| S-07     | 2   | Bid Bulletin<br>11, Volume 2,<br>01Specificatio<br>n, 02_TS   | TS 500 - 60  | <ul><li>9) Roofing Works<br/>and Exterior<br/>Finishing</li><li>a. Metal Canopy</li></ul> | Zinc coated steel sheet T=0.6mm,<br>H=25mm   | If specification will govern please verify BOQ item D512(2).                                   | TS500 will                   |
| S-07     | 2   | Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch  | DRG. NO.<br>NSRP-DWG-<br>SH1-AR-3101<br>/ NSRP-DWG-<br>SH1-AR-3601 | Of Finishes   | Pre-Painted Hi-Rib Zinc - Aluminum -<br>Magnesium (Zam) Roofing:<br>Alzinc Steel Sheet T=0.6mm,<br>H=25mm  | If specification will govern please verify BOQ item D512(2).                                   | Architectur<br>will be revis |
| S-07     | -   | -   | DRG. NO.<br>NSRP-DWG-<br>SH1-AR-3101                               | & 8/-: Longitudinal   | 0.6mm Thk. Long Span Rib Type<br>Metal Roofing, Flourourethane<br>Painted Finish   | If specification will govern please verify BOQ item D512(2).                                   | Architectur<br>will be revis |
| S-07     | -   | -   | DRG. NO.<br>NSRP-DWG-<br>SH1-AR-3201                               | Elevations  | Pre-Painted Insulated Roof Panels<br>With Polyisocyanurate (Pir)<br>Insulation; Flourourethane Pre-<br>Painted Finished:<br>Composite Roof Panel: Top &<br>Bottom Skin Alzinc Steel Sheet<br>Thk.= 0.6mm, H-<br>108,;Polyisocyanurate (Pir) Density:<br>32-35kg/M3   | If specification will govern please verify BOQ item D512(2).                                   | Architectur<br>will be revis |
| S-07     | 1A  | Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ   |  | Bill of Quantities4-<br>2.16 Security<br>House 1  | BOQ D512(2) Pre-painted Hi-Rib<br>Zinc-Aluminum-Magnesium (ZAM)<br>Roofing   | If specification will govern please verify BOQ item D512(2).                                   | Architectur<br>3101, 3201    |
| S-07     | 2   | Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch<br>Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ |  | 2/-: Section  | Security House 1<br>D1: 600x2100mm Single-Leaf Fire-<br>Rated Steel Flush Door W/ Bottom<br>Louver; In Flourourethane Oven-<br>Baked Fin. Steel Sheet T=1.6 Frame<br>Louver: Ss Sheet T-2.0 W/ Insect<br>Screen<br>PVC Door with Louver<br>D526(18)a D1 for Security House:<br>W600mm x H2100mm, Single Leaf<br>Fire-Rated Steel Flush Door with<br>Bottom Louver, Fluoroure Baked<br>Finish | Please verify conflict in plan. Which shall govern.<br>a. if PVC Door, please provide pay item | Door sched<br>3503 will be   |

| Final Response   |
|--|
| ll be revised in Addendum 3  |
| ural drawing sheet NSRP-DWG-SH1-AR-3101<br>vised and issued in Addendum 3          |
| ural drawing sheet NSRP-DWG-SH1-AR-3101<br>vised and issued in Addendum 3          |
| ural drawing sheet NSRP-DWG-SH1-AR-3201<br>vised and issued in Addendum 3          |
| ural drawing sheet NSRP-DWG-SH1-AR-<br>)1 will be revised and issued in Addendum 3 |
| edule will govern. Sheet NSRP-DWG-SH1-AR-<br>be revised and issued in Addendum 3   |

|          |                             |   |                                      | -  |  |  |                              |
|----------|-----------------------------|---|--------------------------------------|--|--|--|------------------------------|
| Packages | Vol                         | Sec   | Page No.                             | Clause No./Title                                 | Reference Text<br>(if necessary)   | Clarification<br>Request                                     |                              |
|          |                             | Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch      |                                      | Exterior Schedule<br>Of Finishes                 | 0.50mm Thk. Pre-Painted Spandrel<br>Metal Ceiling                                    |  |                              |
| S-07     | 2                           |   | DRG. NO.<br>NSRP-DWG-<br>SH1-AR-3601 | Interior Schedule<br>Of Finishes                 | Exposed Underside Of Pir Insulated<br>Steel Roofing                                  | Please verify conflict in plan. Which shall govern.          | Architectur<br>will be revis |
| _        |                             | Bid Bulletin<br>11, Volume<br>1A, Section<br>4A BOQ             |                                      | Bill of Quantities4-<br>2.16 Security<br>House 1 | BOQ D544(3) Pre-Painted Spandrel<br>Metal Ceiling                                    |  |                              |
| S-07     | 2                           | 2<br>Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch | NSRP-DWG-<br>LRS-AR-3006             | LRS Interior<br>Schedule Of<br>Finishes          | LRS<br>Cf3: 600 X 600 X 12mm Thk<br>Acoustic Ceiling Boards With Foil<br>Backing     | For Lactation Room Ceiling Finishes, please verify conflict  |                              |
|          |                             |   | NSRP-DWG-<br>LRS-AR-3812             | Reflected Ceiling<br>Plan - Ground<br>Level      | Cf4: 12mm Thk Moisture-Resistant<br>Gypsum Board On Metal Frames,<br>Paint Finish    | in plan. Which shall govern.                                 | be revised a                 |
| S-07     | 07 2                        | 2 Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch    | NSRP-DWG-<br>LRS-AR-3418             | Sections<br>Reflected Ceiling                    | LRS<br>12mm Thk Moisture-Resistant<br>Gympsum Board On Metal Frames,<br>Paint Finish | For Managers Room Toilet Ceiling Finishes, please verify     | "12mm Thi<br>Metal Fram      |
|          |                             |   | NSRP-DWG-<br>LRS-AR-3812             | Plan - Ground                                    | Cf3: 600 X 600 X 12mm Thk<br>Acoustic Ceiling Boards With Foil<br>Backing            | conflict in plan. Which shall govern.                        | DWG-LRS-<br>Addendum         |
| S-07     | 2                           | Volume 2,<br>02_Book 2  | NSRP-DWG-<br>LRS-AR-3006             | LRS Interior<br>Schedule Of<br>Finishes          | LRS<br>Cf3: 600 X 600 X 12mm Thk<br>Acoustic Ceiling Boards With Foil<br>Backing     | For Pantry Ceiling Finishes, please verify conflict in plan. | CF3 will go                  |
|          | 2                           | 2 (Architectural)<br>, 01 S07 Arch                              | NSRP-DWG-<br>LRS-AR-3812             | Reflected Ceiling<br>Plan - Ground<br>Level      | Cf1: Exposed Underside Of Metal<br>Roofing   | Which shall govern.  | reised and i                 |
| S-07     | 2 02_Book 2<br>(Architectur | Volume 2,<br>02_Book 2  | NSRP-DWG-<br>LRS-AR-3006             | LRS Interior<br>Schedule Of<br>Finishes          | LRS<br>W3: 12mm Thk Moisture-Resistant<br>Gympsum Board On Metal Frames,             | for Pantry Wall Type/Finishes, Please verify conflict in     | W9 to gover                  |
|          |                             | 2 (Architectural)<br>, 01 S07 Arch                              | NSRP-DWG-<br>LRS-AR-3831             | Wall Schedule And<br>Details                     | Paint Finish<br>W9: 2h- 200mm Thk Chb Wall   | plan. Which shall govern                                     | revised and                  |

| Final Response  |
|---|
| ural drawing sheet NSRP-DWG-SH1-AR-3601<br>vised and issued in Addendum 3   |
| govern. Sheet NSRP-DWG-LRS-AR-3006 will<br>I and issued in Addendum 3   |
| Thk Moisture-Resistant Gypsum Board On<br>times, Paint Finish" will govern. Sheet NSRP-<br>S-AR-3812 will be revised and issued in<br>m 3 |
| govern. NSRP-DWG-LRS-AR-3812 will be<br>d issued in Addendum 3  |
| vern. NSRP-DWG-LRS-AR-3006 will be<br>nd issued in Addendum 3   |
|   |

| Packages | Vol | Sec   | Page No.   | Clause No./Title                             | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |
|----------|-----|---|--|--|---|---|--|
| S-07     | 2   | Bid Bulletin<br>11, Volume 2,<br>01_Spec-02<br>TS, Part 2 Sec<br>IC TS 500<br>Architectural<br>20201216 |  | 524 Roof<br>Accessories<br>524.2.2 Materials | Skylight In Clark International<br>Airport (Cia) Station Shall Be 4mm<br>Thick One (1)-Piece Pyramidal<br>Polycarbonate Dome And 900 X<br>900mm In Size As Per Engineer's<br>Design And Dimension | Please verify conflict in Technical Specification. Which shall govern.  | NSRP-SL s<br>skylight roo<br>drawings.   |
| S-07     | 2   | Volume 2,<br>02_Book 2<br>(Architectural)<br>, 01 S07 Arch  | NSRP-DWG-<br>LRS-AR-3402<br>NSRP-DWG-<br>LRS-AR-3582 | Light Repair Shop -                          | Reinforced Concrete Pit   | Please provide longitudinal section and structural details of<br>the reinforced concrete pit (as shown) for Light Repair<br>Shop (LRS) Service Pit.   | To be revis<br>DWG-LRS<br>Addendum   |
| S-05     | 1   | Volume 1 &<br>Sec No 1-3  | EQC 16   | `EQC 1.4.3                                   | Capability of mobilizing the key<br>personnel for each individual package<br>shall be evaluated.  | Personel to be used for CP S05, can be used the same<br>person to CP S06 or CP S01? How is the evaluate?  | The evalua<br>stated in th<br>Where pers<br>individual of<br>detail the co<br>and on time<br>personnel i |
| S-05     | -   | -   | -  | -  | -   | <ul> <li>Bidder would like to seek information in case of change in the proposed subcontractor/supplier and/or personnel in the Bid during the implementation of the Contract;</li> <li>Is it possible to propose such changes?</li> <li>If so, Bidder would like to understand if there are any provisions or regulations by the Employer in relation to such change.</li> </ul> | In certain o<br>changes in<br>detailed jus   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)  | SS15 & SS16-<br>ST-4312,<br>SS18-ST-<br>4311         | -  | Cinder Concrete   | As per the drawings, the Cinder Concrete is applied on the foundation. However the same is not measured in the BOQ. $\rightarrow$ Kindly provide the item and quantity with specification.  | The BOQ s<br>Concrete. U   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)  | SS18-AR-<br>3022                                     | -  |   | The Sub-station No 18 is not introduced the Sub-station<br>Building Type in the drawing.<br>→ Please provide the Sub-station Building Type for No 18.   | SS18 is Bu<br>SS00-AR-3  |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC Technical<br>Specifications)   | TS-500- 488  | TS 500                                       | 564 HARDSCAPE (External Works)<br>AND RELATED FACILITIES  | <ul> <li>564.1.2 Termite Control</li> <li>It is specified 'Termite Control shall be carried out whole</li> <li>Station area'. But not measured BOQ.</li> <li>→ If the same is required, please provide the BOQ with</li> <li>specification and demarcation on the drawings.</li> </ul>  | (1)Please r<br>No.s 4-1, 4<br>Poisoning.<br>Design Tea   |

*C shall use 4mm thk. polycarbonate sheet coofing at locations as specified in the* 

vise/added in architectural drawings NSRP-RS-AR-3402, 3582 will be revised and issued in m 3

*uation will be purely based on the requirements the Bidding Documents.* 

rsonnel can be reasonably shared between l contracts, the Bidder shall demonstrate in contracts can be implemented simultaneously me. The acceptance of proposed shared l is subject to full discretion of the Employer.

n circumstances, it may be possible to propose in subcontractors and or personnel with ustification subject to the Engineer's approval

shall be revised to include the Cinder Updated BOQ shall be issued as Addendum 3.

Suilding Type-2. Please refer to NSRP-DWG--3009.

refer to the Updated BOQ, Addendum 1; Bill 4-2 and 4-3; Item No. 502(6)-Soil Treatment / g. (2)Drawings (for demarcation) care-of the leam.

| Packages | Vol | Sec   | Page No.              | Clause No./Title | Reference Text<br>(if necessary)                              | Clarification<br>Request  |   |
|----------|-----|---|-----------------------|------------------|---|---|---|
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC Technical<br>Specifications) | TS-500- 488           | TS 500           | 564 HARDSCAPE (External Works)<br>AND RELATED FACILITIES      | BOQ Item 564(28) - 95mm x 905mm x 100mm Loading<br>Dock Rubber Buffer<br>→ The specification does not provide the same item. Kindly<br>provide the specification and detail drawings.   | Refer to TS<br>specificatio   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC Technical<br>Specifications) | TS 500-79             | TS 500           | 502. ARCHITECTURAL<br>CONCRETE FINISHES                       | <ul> <li>6) of 502.1.1 General</li> <li>It is specified 'Termite Control and damp-proofing under the Architectural Concrete on grade shall be carried'. But the same is not shown on the drawings and BoQ.</li> <li>→ Kindly advise which item bidder include the same and provide the location on the drawings.</li> </ul>   | (1)Please re<br>No.s 4-1, 4-<br>Poisoning.<br>(2)Specific<br>issued in Ad   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC Technical<br>Specifications) | TS 500-79             | TS 500           | 502. ARCHITECTURAL<br>CONCRETE FINISHES                       | <ul> <li>4) of 502.1.4 Submittals</li> <li>It is specified 'Mock-up: The Contractor shall provide Insitu Terrazo finish Bench of 600mm x 2500mm with materials on the reinforcement concrete base at the site'. But there is no relevant items in BOQ.</li> <li>→ Kindly clarify whether it is under bidder's scope.</li> </ul>   | The BOQ s<br>BOQ shall  |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC Technical<br>Specifications) | TS-500- 440           | TS 500           | 555.1.6 Billboard Signs                                       | It is specified that Billboard signs shall be erected by the<br>Contractor at the entrances to the car parking area (2 signs),<br>at the entrance to the auto-rickshaw parking area (1 sign)<br>and at the entrance to the rickshaw parking area (1 sign), all<br>adjacent to the Station Buildings. Billboard signs shall also<br>be placed at the egress points from the same parking areas<br>(5 signs).<br>But the quantities in BoQ are as below;<br>1) CABUYAO STATION: Item No P555(4) - 6 Nos<br>2) BANLIC STATION: Item No P555(4) - 8 Nos<br>3) CALAMBA STATION: Item No P555(4) - 10 Nos<br>→ Kindly advise which one is bidder's consideration. |   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC Technical<br>Specifications) | TS-500- 489           | TS 500           | 565 TOUCH VOLTAGE<br>INSULATION AND<br>WATERPROOFING MEMBRANE | <ul> <li>565.1.2 Work of this Section</li> <li>1) Bituminous Primer</li> <li>2) Bituminous Asphalt Compound</li> <li>3) Touch Voltage Insulation Membrane</li> <li>→ Kindly clarify whether the cost for the above works are included in ITEM 565 (1) in BoQ or considered as separate items.</li> </ul>  | The BOQ I<br>Bituminous<br>Insulation J<br>Specificatio<br>Touch Volt<br>Membrane,<br>"The work<br>manufactus<br>voltage insu<br>including a<br>this Specifi<br>or as establ<br>the Sub-Cla |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                    | SS00-AR-<br>3009,3015 | -                | GAS CYLINDER ROOM   | There is shown the Gas Cylinder Room in the plan<br>drawings. But the detail drawings for structure, finishes<br>with door are not provided.<br>→ Kindly provide the relevant drawings, if it is under<br>bidder's scope.   | Drawings v  |

#### **Final Response**

**S400 Sec 417 Elastomecti Bearing Pad for** ions.

refer to the Updated BOQ, Addendum 1; Bill 4-2 and 4-3; Item No. 502(6)-Soil Treatment /

*fication and Drawings will be revised and Addendum 3* 

shall be revised to include the bench. Updated *II be issued as Addendum 2.* 

OQ Items for the Billboard are based from the Nos. NSRP-DWG-CAB-AR-3631 to 3633; WG-BAN-AR-3631 to 3633 and NSRP-DWG-3631 to 3633. (2)Technical Specification , care-of the Design Team/Specifications

2 Item 565(1) covers the Bituminous Primer, nus Asphalt Compound and Touch Voltage n Membrane as set forth in the Technical tions. Please refer to TS 500, Section 565oltage Insulation and Waterproofing ne, Clause 565.1-The Work, which states that the this section shall consist of the ture/supply, delivery and installation onsite of asulation and waterproofing membrane system, all anchorage provisions, in accordance with ification and in conformity with the Drawings ablished by the Engineer". Please also refer to Clause 565.1.2-Work of this Section.

will be provided in Addendum 3

| Packages | Vol | Sec   | Page No.                                    | Clause No./Title | Reference Text<br>(if necessary)                            | Clarification<br>Request  |   |
|----------|-----|---|---|------------------|---|---|---|
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                    | SS00-AR-<br>3005, 3009,<br>3015             | -                | Sub-station/ DOOR SCHEDULE                                  | Please clarify the metal door in the Sub-station. There is<br>discrepancy between the Schedule, BOQ and DWG. The<br>Schedule and BOQ shows only (D1) door however, DWG<br>shows (D2) door.  | The BOQ s<br>shall be issu  |
| S-06     | 1A  | Volume 1A &<br>Section 4A                                   | Bill No 6                                   | Item 526         | WINDOWS   | As per the drawing No SS00-AR-3009/3012/3015, W1 is shown on the drawings. But not measured in the BoQ. $\rightarrow$ Kindly provide the item with quantity.  | The BOQ s<br>shall be iss   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                    | CAB-ST-4111<br>CAB-ST-4302                  | -                | -   | Ref. drawing show discrepancies between pile cap<br>dimension. Please confirm which one to follow in order for<br>us to evaluate and price accordingly.   | The pile ca<br>sheets NSR<br>CAB-ST-43  |
| S-06     | 1A  | Volume 1A &<br>Section 4A                                   | Bill No 4                                   | -                | External Works (Hard Scape)                                 | The following items are not provided the drawings<br>Bill No 4-1: Item No 129(2)a, 129(2)b, 130(2)d, 131(2)e,<br>129(4), 129(5)<br>Bill No 4-2: Item No 129(2)a, 129(2)b, 129(2)d, 129(4)<br>Bill No 4-3: Item No 129(2)a, 129(2)d, 129(2)e, 129(2)f,<br>129(4)<br>$\rightarrow$ Kindly provide the detail drawings.                                      | For road si<br>drawings:<br>CABUYAC<br>SERIES<br>BANLIC S<br>SERIES<br>CALAMBA<br>SERIES                            |
| S-06     | 1A  | Volume 1A &<br>Section 4A                                   | Bill No 4                                   | -                | External Works (Hard Scape) /<br>External Works (Softscape) | The relevant drawing provided for each station is only<br>layout.<br>→ Kindly provide more detail drawings in order to review<br>& evaluate the cost.   | Refer to res<br>AR-3570.  |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC Technical<br>Specifications) | TS 500-246                                  | -                | TENSILE MEMBRANE ROOF<br>STRUCTURE (TMRS)                   | <ul> <li>As per the sub-clause 523.1.1 (General) 523.2.3</li> <li>(Fabrication), there are the following requirements for suppliers.</li> <li>Experience: 20 years (Inc. Philippines) / 20 MTR Stations</li> <li>Own factory with a solid background of over 20 years</li> <li>Capacity: over 5,000 m2/mth</li> <li>→ Are the above mandatory?</li> </ul> | Yes, Bidder<br>The Bidder<br>demonstrat<br>supplier wit   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                    | STA-AR-<br>3556,<br>CAB/BAN/C<br>AL-STL4522 | -                | BEAM BUFFERING  | → Kindly provide the size and specification for Rubber<br>buffer.   | The size of<br>DWG-CAB<br>NSRP-DW<br>For specifi<br>Elastomeri<br>2. Use 300<br>(between st<br>Detail will<br>3556. |

#### **Final Response**

Shall be revised to include W1. Updated BOQ ssued as Addendum 3

shall be revised to include W1. Updated BOQ ssued as Addendum 2.

cap dimensions have already been updated on SRP-DWG-CAB-ST-4111 and NSRP-DWG-4302 rev 21.2

signs drawings, please refer to the following

AO STATION: NSRP-DWG-VIA6-CW-2000

STATION: NSRP-DWG-VIA06-CW-2000

BA STATION: NSRP-DWG-VIA06-CW-2000

esponse to query above and NSRP-DWG-STA-

er shall comply with the requirements. For shall submit detailed justification to ate the capacity should the Bidder propose a with slghtly different experience as required.

of the Buffer Beaming is provided on NSRP-IB-ST-4522, NSRP-DWG-BAN-ST-4522, and WG-CAL-ST-4522 rev. 21

*ifications, refer to TS 400 Sec. 417 ric Bearing Pad* 

00mm x 900mm fabric-reinforced laminated structural steel angles) rubber dock bumper. Il be added on sheet NSRP-DWG-STA-AR-

| Packages | Vol | Sec                       | Page No.  | Clause No./Title   | Reference Text<br>(if necessary)  | Clarification<br>Request   |   |
|----------|-----|---------------------------|-----------|--|---|--|---|
| S-06     | 1A  | Volume 1A &<br>Section 4A | Bill No 6 | -  | 102(1)a: Unsuitable Excavation at dry<br>103(1)a: Embankment (Selected<br>Borrow Materials) | Regarding the Item no 102(1)a & 103(1)a in Bill No 6-1 to<br>4, the quantities provided are not verified due to no<br>drawings.<br>$\rightarrow$ Kindly advise the computations.   | PIN 102(1)<br>is the volum<br>Substation<br>(SDP), neco<br>Improveme<br>103(1)a: E<br>the volume<br>Developme<br>structures d |
| S-06     | -   | -                         | -         | Electrical   | -   | Please note that as per the drawing NSRP-DWG-CAB-EL-<br>5900, the rating of ATS is shown as 225A. However as per<br>the Item No 718(1)a of Bill of Quantities No 4-1, the rating<br>is shown as 150A. Kindly confirm the rating to be<br>considered. | Rating of A   |
| S-06     | -   | -                         | -         | Electrical   | -   | Please note that as per the drawing NSRP-DWG-BAN-EL-<br>5900, the rating of ATS is shown as 225A. However as per<br>the Item No 718(1)a of Bill of Quantities No 4-2, the rating<br>is shown as 150A. Kindly confirm the rating to be<br>considered. | Rating of A<br>DWG-CAB  |
| S-06     | -   | -                         | -         | Electrical   | -   | Please note that Bill of Quantities No 4-1 & 4-3 measures<br>Item No 718(1)b - 'ATS, 1200A, 4P in NEMA 4x<br>Enclosure'. However the same item is not measured in Bill<br>of Quantities No 4-2. Kindly clarify.                                      | There is no<br>DB, is 800A  |
| S-07     | 2   | Volume 2                  | -         | S07_DWG List   | CP S-07_23_AR_CNT   | Please provide Architectural Drawing of Canteen Building.  | Canteen Ai<br>issued Rev2   |
| S-07     | -   | BOQ                       | -         | Bill No.2 Part D<br>Item 206(6)b   | Electrical Manhole  | Please provide electrical manhole drawings.  | Electrical n<br>Addendum  |
| S-07     | -   | BOQ &<br>Drawing          | -         | Bill No.2 Part D<br>Item 206(10)i1<br>NSRP-DWG-DEP-<br>RD-1926<br>NSRP-DWG-DEP-<br>RD-8504 | Crash stone layer (200mm)   | As per BOQ the crash stone are included, however in the drawings it is not shown. Please clarify.  | Drawing to  |
| S-07     | -   | Drawing                   | -         | NSRP-DWG-OCC-<br>ST-4201 & 4211  | W30   | Please provide detail of "W30" as shown in the drawing.  | Detail for V<br>4342 which  |
| S-07     | -   | Drawing                   | -         | NSRP-DWG-DEP-<br>RD-8014   | OCS Pole  | Please provide layout plan for the locations of OCS pole.  | Location oj   |
| S-07     | -   | Drawing                   | -         | NSRP-DWG-DEP-<br>RD-1827   | Column rebar ties   | Please provide spacing of 10mm rebar ties for column.  | Drawing to  |

#### **Final Response**

(1)a: Unsuitable Excavation at dry conditions ume of soil to be removed in the whole of an area, including the Site Development Plan ecessary for the installation of Soil ment by Crushed Stones.

Embankment (Selected Borrow Materials) is ne of soil to necessary to backfill the Site nent area after Crushed Stones and other s are completed.

FATS is 150 AT. Kindly refer to drawing NSRP-B-EL-5900 rev 21.2

<sup>c</sup> ATS is 150 AT. Kindly refer to drawing NSRP-|B-EL-5900 rev 21.2

no ATS rating 1200A. Rating of ATS for FP-0A,4P in Nema 4x Enclosure.

Architectural drawings were provided. See w21 (NSRP-DWG-CNT-AR-3001 to 3861).

l manhole drawing details will be issued in *m* 3

to be revised and updated under rev.21.2

of OCS poles will be provided in Addendum 3

to be revised and updated under rev.21.2

| Packages | Vol | Sec  | Page No. | Clause No./Title   | Reference Text<br>(if necessary)               | Clarification<br>Request  |   |
|----------|-----|--|----------|--|--|---|---|
| S-07     | -   | Drawing  | -        | NSRP-DWG-OCC-<br>AR-3531 & 3532  | CHB wall rebar                                 | Please provide rebar detail of CHB wall.  | These sheet<br>architecture<br>Rev21.                               |
| S-07     | -   | BOQ<br>Drawing   | -        | Bill No.2 Part D<br>Item 206(6)i<br>NSRP-DWG-DEP-<br>RD-8504   | Concrete Strength for<br>L-Type Retaining Wall | The concrete strength of retaining wall structure as per<br>BOQ is 40MPa, while as per drawing NSRP-DWG-DEP-<br>RD-8504 note 1 is 28MPa. Please clarify.  | The BOQ s<br>strength of<br>shall be issu                           |
| S-07     | -   | Drawing  | -        | NSRP-DWG-DEP-<br>DR-2710   | -  | Please provide rebar detail of Manhole Type J & K.  | Rebar detai<br>schedule lo  |
| S-07     | -   | BOQ  | -        | Bill no. 4-2.3 item<br>402(7)<br>Bill no. 4-2.8 item<br>402(7)<br>Bill no. 4-2.9 item<br>402(7)<br>Bill no. 4-2.10 item<br>402(7)<br>Bill no. 6.1 item<br>402(7) | -  | Please clarify the unit measurement of test pile, "l.m." or "nos."  | The unit m<br>shall be rev<br>Test Pile. U                          |
| S-07     | -   | BOQ  | -        | Bill no.4-1.2 item<br>D607(4)b & a<br>Bill no.4-2.1 item<br>D607(4)b & a<br>Bill no.4-2.2 item<br>D607(4)b & a   | Compressed Air System                          | Please advise if we will Supply & Install the Air<br>Compressors, Air Receivers and Air Dryers. In BOQ, the<br>line items only include piping works.  | The supply<br>Receivers a<br>of Work (Se                            |
| S-07     | -   | Drawing<br>Specification   | -        | NSRP-DWG-OCC-<br>AR-3414<br>Section 6 – 552.2.2  | -  | There is conflict in the specs of toilet partition.<br>Architectural specs material description is S/S hairline<br>finish while the Architectural Plan material description is <sup>3</sup> / <sub>4</sub><br>phenolic. Which will prevail? | 3/4 phenoli   |
| S-07     | -   | BOQ  | -        | Bill no. 4-1.1 item<br>D536(5)   | -  | Please provide us details/specs of granite slab countertop and granite lintel.  | Already pro<br>3415. See K  |
| S-07     | -   | BOQ  | -        | Bill no.4-1.1 item<br>D527(1) e to h   | Aluminum mechanical louver/false<br>louver     | Please provide us the schedule and drawing of the<br>following Aluminum Mechanical Louver/False Louver:<br>W73100mm x H600mm<br>W56550nn x H600mm<br>W7000mm x H600mm<br>W17000mm x H600mm  | This is to be<br>DWG-OCC<br>issued in A                             |
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-1.2<br>Light Repair Shop  | -  | Pre-Painted Hi-Rip Zinc-Aluminum0Magnesium Roofing<br>: Please explain which section this material is applied to.<br>We can't find it in the drawing.   | The Pre-Pa<br>(ZAM) Roo<br>Please refe<br>3006 Rev21<br>Finishes, M |

## **Final Response** eets cover wall schedule details. See ural drawing NSRP-DWG-OCC-AR-3531,3531 shall be revised for appropriate concrete of the retaining wall structure. Updated BOQ ssued as Addendum 3. tails of manholes will follow reinforcement located in NSRP-DWG-DEP-DR-2701. measurement of Test Pile is "Im". The BOQ evised for the appropriate unit measurement of Updated BOQ shall be issued as Addendum 2. ly and installation of the Air Compressors, Air and Air Dryers are excluded from the Scope (SoW). plic board will prevail. See Rev 21 provided in drawing NSRP-DWG-OCC-AR-*Rev 21*

be added to the architectural drawing NSRP-CC-AR-3621, 2641-3642 will be revised and Addendum 3

Painted Hi-Rib Zinc Aluminum Magnesium oofing shall be used for the Canopy Roofing. fer to the drawing No. NSRP-DWG-LRS-AR-21; Light Repair Shop Exterior Schedule of Mark 4 - Canopy Roofing.

| Packages | Vol | Sec  | Page No. | Clause No./Title                                       | Reference Text<br>(if necessary) | Clarification<br>Request  |  |
|----------|-----|--|----------|--|----------------------------------|---|--|
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-1.2<br>Light Repair Shop                    |                                  | There is no slab to H=3600 on the drawing In the office<br>area. Please confirm where to hang the ceiling board. And,<br>Please confirm also Height of CHB(150,300) and Gysum<br>Board Wall. It means the actual Construction Height. | For ceiling,<br>(see issued 1<br>Sep21,2020,<br>3524 & 353                                 |
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.2<br>Wheel Re-Profiling<br>Shop           | -                                | High-Performance Urethane Coatings (Masonry Painting)<br>: There are not Masonry(CHB) wall area in LRS. Please<br>confirm which section this material is applied.   | Bill No. 4-2<br>For the WR<br>Coatings sh<br>refer to drav<br>Rev21; Inte<br>Finishes, Ita |
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.2<br>Wheel Re-Profiling<br>Shop           | -                                | There is no detailed drawing. Please confirm which section<br>this material is applied.<br>- T=50mm, Plain Cement Troweled Finish with Hardner<br>- T=200mm, Tampered Concrete Including Wire Mesh with<br>Hardner                    | Updated BC   |
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.2<br>Wheel Re-Profiling<br>Shop           | -                                | High-Performance Urethane Coatings (Masonry Painting)<br>: There are not Masonry(CHB)wall area in WRS. Please<br>confirm which section this material is applied.  | The BOQ si<br>works. Upd   |
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.5<br>Oil Storage For<br>Light Repair Shop | -                                | High-Performance Urethane Coatings (Masonry Painting)<br>: There are not CHB wall area in LOS. Please confirm<br>which section this material is applied. (Quantity of BOQ :<br>32m2   | Please refer<br>Rev21; Exte  |
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.5<br>Oil Storage For<br>Light Repair Shop | -                                | High-Performance Urethane Coatings (Masonry Painting)<br>: There are not Masonry(CHB)wall area in LOS. Please<br>confirm which section this material is applied.  | Please refer<br>Rev21; Exte  |
| S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.9<br>Track Maintenance<br>Office          | -                                | There is no detailed drawing. Please confirm which section<br>this material is applied.<br>- T=50mm, Plain Cement Troweled Finish with Hardner  | The BOQ si<br>works. Upd   |

#### **Final Response**

ng, it was suspended from structural frames ed NSRP-DWG-LRS-AR-3521 as Rev21 20). CHB has 150 height (see DWG-LRS-AR-531 as Rev21)

1-2.2 is the Wheel Re-Profiling Shop (WRS). WRS, the High-Performance Urethane shall be applied for the Work Area. Please rawing No. NSRP-DWG-WRS-AR-3601 nterior Schedule of Finishes; Work Area, Wall Item (B).

BOQ shall be issued as Addendum 3.

Shall be revised for appropriate painting polated BOQ shall be issued as Addendum 3.

fer to drawing No. NSRP-DWG-LOS-AR-3601 xterior Schedule of Finishes, Item CHB Wall.

fer to drawing No. NSRP-DWG-LOS-AR-3601 xterior Schedule of Finishes, Item CHB Wall.

Shall be revised for appropriate finishing oddeted BOQ shall be issued as Addendum 3.

|   |          |     |  |          | -   |  |  |   |
|---|----------|-----|--|----------|---|--|--|---|
|   | Packages | Vol | Sec  | Page No. | Clause No./Title                                      | Reference Text<br>(if necessary)                                     | Clarification<br>Request   |   |
| - | S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.9<br>Track Maintenance<br>Office         | -  | Based on the drawing, the section where the double wall is<br>applied cannot be found. Please check which section is<br>applied  | We shall no<br>different fin<br>workspace.<br>section is th<br>insulated we<br>gypsum boo<br>as Rev21). |
|   | S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.9<br>Track Maintenance<br>Office         | -  | High-Performance Urethane Coatings (Masonry Painting)<br>: There are not Masonry(CHB)wall area in TMO. Please<br>confirm which section this material is applied.   | The BOQ si<br>works. Upd  |
| - | S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.11<br>Distribution Board<br>Space 1      | -  | There is no detailed drawing. Please confirm which section<br>this material is applied.<br>- T=50mm, Plain Cement Troweled Finish with Hardner   | The Design<br>Drawings s  |
|   | S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.15<br>Pump House for<br>Fire Water Tank2 | -  | There is no detailed drawing. Please confirm which section<br>this material is applied.<br>- T=50mm, Plain Cement Troweled Finish with Hardner   | The BOQ si<br>works. Upd  |
|   | S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 4-2.20<br>Canteen                            | -  | There is no detailed drawing. Please confirm which section<br>this material is applied.<br>- T=200mm, Tampered Concrete Including Wire Mesh with<br>Hardner  | The BOQ si<br>Updated BO  |
|   | S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 6-1<br>S.Depot Sectioning<br>Post            | -  | High-Performance Urethane Coatings (Masonry Painting)<br>: CHB Wall in DSP are applied with Plaster finish. But,<br>The quantity of CHB in the BOQ is 213m2. Please confirm<br>which section this material is applied. | The BOQ si<br>and quantit<br>Addendum   |
|   | S-07     | 1A  | Volume 1A<br>Section 4A<br>Bidding Forms<br>– Bill of<br>Quantities<br>(BOQ) | -        | Bill No. 6-1<br>S.Depot Sectioning<br>Post            | -  | Quantity of 150mm THK CHB Wall and Plain Cement<br>Plastered are higher than our Quantity. (70% Difference)<br>Please confirm and send us detail drawing or another<br>drawing.  | The BOQ si<br>and quantit<br>Addendum   |
|   | S-07     | 1   | Volume 1<br>1.3 CP S-07<br>Vol.1A<br>Sec.4A BOQ                              | -        | Bill No. 4-1.1 F5                                     | Duplex Receptacle, 15A, 250V,<br>3W Grounding Type, Floor<br>Mounted | There is No Duplex Receptacle, 15A, 250V, 3W Grounding<br>Type, Floor Mounted (27EA) on the BOQ.<br>Please clarify.  | Please refet<br>4-1.1, Part<br>Item D708(   |

#### **Final Response**

not use a double wall and instead, we shall use finishes for the maintenance area and e. What were specified in the drawing and that for maintenance area, we shall use wall panel and or workspace is 12mm thk poard (see issued NSRP-DWG-TMO-AR-3501

Shall be revised for appropriate painting oddeed BOQ shall be issued as Addendum 3.

gn Team shall issue detailed drawing. The s shall be issued as Addendum 2.

Shall be revised for appropriate finishing oddeed BOQ shall be issued as Addendum 3.

) shall be revised for appropriate item of work. BOQ shall be issued as Addendum 3.

Shall be revised for appropriate item of work tity. Updated BOQ shall be issued as m 3.

*Shall be revised for appropriate item of work tity. Updated BOQ shall be issued as m 3.* 

fer to the Updated BOQ, Addendum 1; Bill No. rt F.5-Electrical Works, Receptacle Outlet, 18(4)u.

| Packages | Vol | Sec   | Page No. | Clause No./Title   | Reference Text<br>(if necessary) | Clarification<br>Request  |   |
|----------|-----|---|----------|--|----------------------------------|---|---|
| S-07     | 1   | Volume 1<br>1.3 CP S-07<br>Vol.1A<br>Sec.4A BOQ | -        | Bill No. 4-1.2 F5  | Smoke Detector                   | It is believed that the quantity of Smoke Detector on the<br>BOQ (88EA) is only for the Shop Floor (NSRP-DWG-LRS-<br>EL-6111) without counting of Lower & Upper Maintenance<br>Deck (NSRP-DWG-LRS-EL-6112).<br>Please clarify.  | •   |
| S-07     | 1   | Volume 1<br>BOQ                                 | -        | Bill No. 4-1.1   | OCC                              | <ul> <li>Please clarify below items' discrepancy between BOQ and Drawing.</li> <li>1. ITEM NO : D611(1)aq ACC-312 <ul> <li>BOQ : 2 SET / DWG : 1 SET</li> </ul> </li> <li>2. ITEM NO : D611(1)bx ACC-506 <ul> <li>BOQ : 2 SET / DWG : 1 SET</li> </ul> </li> <li>3. ITEM NO : D624(1)b HRV-02 <ul> <li>BOQ : 10 EA / DWG : 11 EA</li> </ul> </li> <li>4. ITEM NO : D624(1)c HRV-03 <ul> <li>BOQ : 5 EA / DWG : 4 EA</li> </ul> </li> <li>5. ITEM NO : D619(16) Electric Water Instantaneous Water Heater <ul> <li>BOQ : 32 SET / DWG : 37 SET</li> <li>6. ITEM NO : D615(1)c Sewage Sump Pump <ul> <li>BOQ : 8 EA / DWG : 4 EA</li> </ul> </li> </ul></li></ul> | The BOQ so<br>of each iten<br>Addendum    |
| S-07     | 1   | Volume 1<br>BOQ                                 | -        | Bill No. 4-1.2   | LIGHT REPAIR SHOP                | <ul> <li>Please clarify below items' discrepancy between BOQ and Drawing.</li> <li>1. ITEM NO : D611(2)g ACW-09 <ul> <li>BOQ : 2 SET / DWG : 5 SET</li> </ul> </li> <li>2. ITEM NO : D611(2)l ACW-14 <ul> <li>BOQ : 2 SET / DWG : 6 SET</li> </ul> </li> <li>3. ITEM NO : D611(2)y VF-01 <ul> <li>BOQ : 22 SET / DWG : 23 SET</li> </ul> </li> </ul>  | The BOQ s<br>of each iten<br>Addendum     |
| S-07     | 1   | Volume 1<br>BOQ<br>Volume 2<br>Drawings         | -        | Bill No. 4-1.2<br>CP S-<br>07_02_MPFS_LRS<br>NSRP-DWG-LRS-<br>FS-7641                | LIGHT REPAIR SHOP                | <ul> <li>Please clarify below items' discrepancy between BOQ and Drawing.</li> <li>1. ITEM NO : D630(9) Fire Sprinkler Pendent Type</li> <li>- BOQ : 316 EA / DWG : 1048 EA</li> <li>※ Additionally, from Contractor's point of view, quantity of various pipes pertaining to Fire Sprinkler should be also considered.</li> </ul>  | The BOQ si<br>of each iten<br>Addendum    |
| S-07     | 1   | Volume 1<br>BOQ                                 | -        | Bill No. 4-1.2   | LIGHT REPAIR SHOP                | Please clarify that we can see below items on the drawings<br>but can't find them on the BOQ.<br>- Fire Extinguisher(CLEAN AGENT 4.5kg) 24EA  | Please refer<br>4-1.2, Part               |
| S-07     | 2   | Volume 2<br>01_Specificati<br>on<br>01_GS       | -        | Sec.6 IB Appendix<br>12 COVID-19<br>Sec.6 IB Appendix<br>5 Facilities for Emp<br>Eng | -                                | If all Employers, staffs and workers get vaccinated of COVID-19 before commencement of Project, does it necessary to apply social distancing on office area & facilities?   | The bidder<br>specific He<br>local regula |

# **Final Response** fer to the Updated BOQ, Addendum 1; Bill No. rt F.5-Electrical Works, Fire Detection and stem, Item D716(4). shall be revised for the appropriate quantity em of work. Updated BOQ shall be issued as *m 2*. *Shall be revised for the appropriate quantity* tem of work. Updated BOQ shall be issued as *m 2*. shall be revised for the appropriate quantity em of work. Updated BOQ shall be issued as *m 2*. fer to the Updated BOQ, Addendum 1; Bill No. rt F.4, Item No. D630(4)b.

er must comply with the contents of their Covid Jeath and Safety Plan including all relevant ulations

| Packages | Vol | Sec  | Page No.   | Clause No./Title                           | Reference Text<br>(if necessary) | Clarification<br>Request  |  |
|----------|-----|--|--|--|----------------------------------|---|--|
| S-07     | 2   | Volume 2<br>Section 7<br>SOUTH<br>DEPOT<br>ARCHITECT<br>URAL<br>DRAWINGS | OCC<br>BUILDING<br>ARCHITECT<br>URAL<br>DRAWINGS | NSRP-DWG-OCC-<br>AR-3503                   | -                                | Based on drawing "OCC-AR-3503", finishing of steel<br>column in front of external curtainwall is shown as<br>STAINLESS STEEL POST CADDING, however, the item<br>is not shown on BOQ. Please clarify.  | The BOQ s<br>post / pillar<br>Addendum   |
| S-07     | 2   | Volume 2<br>Section 7<br>SOUTH<br>DEPOT<br>ARCHITECT<br>URAL<br>DRAWINGS | OCC<br>BUILDING<br>ARCHITECT<br>URAL<br>DRAWINGS | -  | -                                | Regarding the waterproofing type of toilet on OCC<br>building, drawing shows as Crystalline Cementitious Type<br>which we assume to be applied on concrete, however,<br>Specification shows as Cementitious Type. Please clarfy<br>which type shall be applied.<br>Also, please review quantity of cementitious waterproofing<br>as it is not enough.   | The BOQ s<br>post / pillar<br>Addendum   |
| S-07     | 2   | Volume 2<br>Section 7<br>SOUTH<br>DEPOT<br>ARCHITECT<br>URAL<br>DRAWINGS | OCC<br>BUILDING<br>ARCHITECT<br>URAL<br>DRAWINGS | -  | -                                | Based on the OCC building drawing, Polyurethane<br>Membrane System Waterproofing / Asphalt Membrane   | The BOQ s<br>of waterpro<br>Addendum   |
| S-07     | 2   | Volume 2<br>Section 7<br>SOUTH<br>DEPOT<br>ARCHITECT<br>URAL<br>DRAWINGS | OCC<br>BUILDING<br>ARCHITECT<br>URAL<br>DRAWINGS | -  | -                                | There is "CHB Wall t=300mm" on drawing, however, BOQ does not show the item. Please add the related item on BOQ and review the CHB wall quantity.   |  |
| S-07     | 2   | Volume 2<br>Section 7<br>SOUTH<br>DEPOT<br>ARCHITECT<br>URAL<br>DRAWINGS | OCC<br>BUILDING<br>ARCHITECT<br>URAL<br>DRAWINGS | NSRP-DWG-OCC-<br>AR-3319                   | -                                | The item on drawing "OCC-AR-3319" shows<br>ALUMINUM MECHCANICAL LOUVER/FALSE<br>LOUVER and also there is the same item on BOQ.<br>However, there is another item as "Air Louver on<br>mechanical. Please clarify if the same item is double with<br>different name or not.<br>Also, based on drawing "OCC-AR-3319" curtain wall area,<br>upper part of each floor seems to be connected to outer side<br>of building and there is insulation on ceiling. Please clarify | "ALUMIN<br>LOUVER"<br>basically th<br>Curtain wa<br>Correct, ple<br>reference. |
| S-07     | 2   | Volume 2<br>Book 2<br>(Architectural)<br>Architectural<br>Plan           | -  | NSRP-DWG-LRS-<br>AR<br>NSRP-DWG-LRS-<br>ST | -                                | There is a difference in the Structural Level between<br>Architecture and Structure Drawing. Please confirm which<br>drawing shold be applied in the BOQ.<br>* Please check Drawing<br>: NSRP-DWG-LRS-AR-3005(See the strucral Level in the<br>schedule)<br>NSRP-DWG-LRS-ST-4121(See the strucral Level)  | BOQ to fold<br>See issued 1  |

*Q* shall be revised to include the stainless steel lar cladding. Updated BOQ shall be issued as *m* 3.

*Q shall be revised to include the stainless steel far cladding. Updated BOQ shall be issued as m 3.* 

Shall be revised for the appropriate quantity roofing. Updated BOQ shall be issued as m 3.

fer to the Updated BOQ, Addendum 1. Please the 300mm CHB wall is 2-150mm CHB. fer to the drawing No. NSRP-DWG-OCC-AR-21; Wall Types, Tag 4 (300mm-350mm Thk.

NUM MECHANICAL LOUVER/FALSE R" and "AIR LOUVER" on Mechanical are the same item. Insulation on ceiling - Correct. wall area seems to be connected to outer sideplease see Section 1, OCC-AR-3319 for c.

*follow architectural plans for Structural level. d NSRP-DWG-LRS-AR-3005 as Rev21.* 

| Package | s Vol | Sec                                     | Page No.               | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
|---------|-------|---|------------------------|---|--|---|--|
| S-07    | 1A    | Volume 1A<br>Section 4A                 | 13 Page                | PS-1 Archeological<br>Monitoring  | -  | There is Archeological Monitoring item on Provisional Sum<br>with PHP 1,000,000, however, Time Related Charges for<br>Archeological Monitoring exists on Prelimianry (BOQ).<br>Please clarify if Time Related Charges for Archeological<br>Monitoring cost is included in provisional sum amount, or<br>we need to quote separately.  | The BOQ is<br>Related Cha<br>theses items<br>Updated BO  |
| S-07    | 1     | Volume 1<br>Section 2 Bid<br>Data Sheet | BDS 5                  | ITB 20.2  | -  | Please clarify whether Power of Attorney must be notarized?   | Please refe<br>requiremen  |
| S-07    | 1     | Volume 1<br>Section 3                   | EQC 24                 | 2.4.2 Construction<br>Experience in Key<br>Activities<br>GBB No. 6 Pg. 47 | "Construction of at least 10,000<br>m3 ground floor area of concrete<br>framed buildings on deep filled<br>sites using piled foundation"<br>"At least one (1) project of at least<br>10,000 m2 floor area of concrete<br>framed buildings" | There is an ambiguity in Key Activities Qualification<br>Criteria between Bidding Documents and GBB No. 6<br>(issued on Jan. 7th, 2021).<br>Please confirm what we understand shown as below;<br>"At least one (1) project of at least 10,000 m2 ground floor<br>area of concrete<br>framed buildings"<br>If so, please amend the Bidding Documents and provide us<br>with the Addendum.  | Please refe<br>No. 2   |
| S-04    | 1A    | S-04<br>Vol.1A<br>Sec.4A                | Alabang<br>BOQ No. 4-4 | -   | -  | According to structure dwg, concrete specification for Alabang<br>station is followings;<br>- Pile cap, foudation, columns, wall, tie beam(under GL) :<br>36MPa<br>- Slab, columns, beam(Above GL) : 36MPa<br>However, BOQ indicate two type of concrete below;<br>- Pile cap, foudation, columns, wall, tie beam(under GL) :<br>36MPa<br>- Slab, columns, beam(Above GL) : 31MPa<br>Please confirm which is correct.<br>(Same issue in S-06 Cabuyado, Calamba BOQ) | Drawings a<br>Addendum<br>The Alaba<br>for the colu<br>correct mat<br>updated to<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW |
| S-04    | 1A    | S-04<br>Vol.1A<br>Sec.4A                | Alabang<br>BOQ No. 4-4 | -   | -  | PSD is contract's work scope? We can not find this item in BOQ.   | The installa<br>Bidder's/Co<br>refer to GS<br>on the Inter   |

#### **Final Response**

*D* is deleted from the Bill No. 1 the Time Charges for Archeological Monitoring. Instead, ms shall be covered by the Provisional Sum. BOQ will be issued in Addendum 2.

fer to ITB 20.2 and BDS 20.2 for the ent

fer to the revised EQC issued under Addendum

s are correct. BOQ will be revised and issued in m 3

bang and Calamba Station structural drawings olumns schedule are to be updated to show the paterial strength. The following sheets will be o rev 21.3 in Addendum 3 WG-ALA-ST-4411 WG-ALA-ST-4412 WG-CAL-ST-4413 WG-CAL-ST-4412 WG-CAL-ST-4412 WG-CAL-ST-4413

*llation of PSD is not part of Contractor's scope of work (SOW). Please SS126 for the responsibility of the Contractor terfacing Works* 

| Packages | Vol | Sec            | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request  |   |
|----------|-----|----------------|----------|------------------|----------------------------------|---|---|
| S-04     | 1   | Vol.1<br>Sec.4 | BF 45    | -                | BIM and CMMS Implementation      | The BIM design LOD 300, as provided by the Employer, will<br>be handed-over via what kind of format and generated using<br>which software? Do you have a BIM Guideline? | The succes.<br>compatible<br>Engineer's<br>Autodesk R<br>Bidder to ra<br>Addendum<br>GS Append<br>GS Append |
| S-04     | 1   | Vol.1<br>Sec.4 | BF 45    | -                | BIM and CMMS Implementation      | Does the Employer know how many individual models will comprise the final Federated (Merged Model) at LOD 300?  | The approx<br>models for  |
| S-05     | 1   | Vol.1<br>Sec.4 | BF 43    | -                | BIM and CMMS Implementation      | The BIM design LOD 300, as provided by the Employer, will<br>be handed-over via what kind of format and generated using<br>which software? Do you have a BIM Guideline? | The success<br>compatible<br>Engineer's<br>Autodesk R<br>Bidder to re<br>Addendum<br>GS Append<br>GS Append |
| S-05     | 1   | Vol.1<br>Sec.4 | BF 43    | -                | BIM and CMMS Implementation      | Does the Employer know how many individual models will comprise the final Federated (Merged Model) at LOD 300?  | The approx<br>models for  |
| S-06     | 1   | Vol.1<br>Sec.4 | BF 44    | -                | BIM and CMMS Implementation      | The BIM design LOD 300, as provided by the Employer, will<br>be handed-over via what kind of format and generated using<br>which software? Do you have a BIM Guideline? | The success<br>compatible<br>Engineer's<br>Autodesk R<br>Bidder to ra<br>Addendum<br>GS Append<br>GS Append |
| S-06     | 1   | Vol.1<br>Sec.4 | BF 44    | -                | BIM and CMMS Implementation      | Does the Employer know how many individual models will<br>comprise the final Federated (Merged Model) at LOD 300?   | The approx<br>models for  |

#### **Final Response**

essful Contractor shall utilize software which is le with, interoperable, and equivalent, with the 's with the software programme (currently Revit 2020)

refer to the following documents issued in m 2 for the BIM Guidelines:

*Endix 15 BIM Information Management Flow andix 17 Informaton Management Flow* 

oximate number is more or less 20 individual r each station/building/viaduct.

essful Contractor shall utilize software which is le with, interoperable, and equivalent, with the 's with the software programme (currently Revit 2020)

refer to the following documents issued in m 2 for the BIM Guidelines:

*Endix 15 BIM Information Management Flow andix 17 Informaton Management Flow* 

oximate number is more or less 20 individual or each station/building/viaduct.

essful Contractor shall utilize software which is le with, interoperable, and equivalent, with the 's with the software programme (currently Revit 2020)

refer to the following documents issued in m 2 for the BIM Guidelines:

endix 15 BIM Information Management Flow endix 17 Informaton Management Flow

oximate number is more or less 20 individual r each station/building/viaduct.

| Packages | Vol | Sec   | Page No.   | Clause No./Title   | Reference Text<br>(if necessary)   | Clarification<br>Request   |   |
|----------|-----|---|--|--|--|--|---|
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ<br>Vol.2<br>Book 1<br>03_CP S-05<br>VIA05 | NSRP-DWG-<br>VIA05-ST-<br>0101<br>~<br>0106  | PIER SCHEDULE  | Bored Pile (1000mmφ), (in dry<br>conditions)<br>Bored Pile (1200mmφ), (in dry<br>conditions)<br>Bored Pile (1500mmφ), (in dry<br>conditions) | Please clarify discrepancy between sum of bored pile length in<br>drawings and BOQ.<br>ITEM No. 204(2)a<br>ITEM No. 204(2)b<br>ITEM No. 204(2)c                            | BOQ and d<br>Addendum   |
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ<br>Vol.2<br>Book 2<br>03_CP S-05<br>STRUC | NSRP-DWG-<br>SPO,<br>PTA,<br>BIN,<br>SRO<br>-ST-4101<br>NSRP-DWG-<br>SPO,<br>PTA,<br>BIN,<br>SRO<br>-ST-4301 | PILE SETOUT<br>PLAN<br>REINFORCEMEN<br>T DETAILS<br>BORED PILE   | Bored Pile (800mm diameter)<br>Bored Pile (1000mm diameter)<br>Bored Pile (1200mm diameter)<br>Bored Pile (1500mm diameter)                  | Please clarify discrepancy between sum of bored pile length in<br>drawings and BOQ.<br>ITEM No. 401(8)<br>ITEM No. 401(9)<br>ITEM No. 401(10)<br>ITEM No. 401(11)          | The quantity<br>per latest differences of the second<br>latest BOQ<br>The quantity<br>latest drawn<br>NSRP-DW<br>latest BOQ<br>The quantity<br>diameter 12<br>(NSRP-DW<br>ST-4301 re<br>Addendum<br>will be revis<br>The quantity<br>as per lates<br>21, NSRP-1<br>SRO-ST-40<br>rev. 21.2, N<br>NSRP-DW<br>latest BOQ |
| S-05     | 1   | Vol.1<br>Sec.4A   | -  | BOQ No.2<br>BOQ No.3<br>BOQ No.4-1<br>BOQ No.4-2<br>BOQ No.4-3<br>BOQ No.4-3<br>BOQ No.4-4<br>BOQ No.5<br>BOQ No.6-1<br>BOQ No.6-2<br>BOQ No.6-3<br>BOQ No.6-3<br>BOQ No.6-5 | -  | Please provide criteria to calculate backfill/foundation fill<br>volume.<br>What is clear meaning of backfill and foundation fill?<br>ITEM No. 201(4)d<br>ITEM No. 201(4)e | Backfill rej<br>refill the ho<br>related wor<br>Foundatio<br>that is plac<br>the grade a<br>ground sur  |

drawings are the same. Refer to drawings in m 3 and BOQ in Addendum 2

tities of bored piles for San Pedro is correct as drawings (NSRP-DWG-SPO-ST-4101 rev. 21 DWG-SPO-ST-4301 rev. 21.1). Please refer to Q issued in Addendum 2

ntities of bored piles for Pacita is correct as per wings (NSRP-DWG-PTA-ST-4101 rev. 21 & WG-PTA-ST-4301 rev. 21.1). Please refer to Q issued in Addendum 2

ntities of bored piles for Binan is correct for 1200mm and 1500mm as per latest drawings WG-BIN-ST-4101 rev. 21 & NSRP-DWG-BINrev. 21.1). Please refer to latest BOQ issued in m 2. For diameter 800mm and 1000mm, BOQ vise in Addendum 3

ntities of bored piles for Santa Rosa is correct est drawings (NSRP-DWG-SRO-ST-4101 rev. P-DWG-SRO-ST-4301 rev. 21.1, NSRP-DWG-4601 rev. 21.1, NSRP-DWG-SRO-ST-4621 NSRP-DWG-SRO-ST-4701 rev. 21.2, & WG-SRO-ST-4721 rev. 21.2). Please refer to Q issued in Addendum 2

efers to a volume of suitable material used to hole or foundation, once excavation, and the ork have been completed.

ion Fill refers to a volume of suitable material aced and compacted for the purpose of raising above the level of the existing surrounding urface.

| Packages | Vol | Sec                     | Page No.  | Clause No./Title   | Reference Text<br>(if necessary)   | Clarification<br>Request   |   |
|----------|-----|-------------------------|-----------|--|--|--|---|
| S-05     | 1   | Vol.1<br>Sec.4A         | -         | BOQ No.2<br>BOQ No.3<br>BOQ No.6-1<br>BOQ No.6-2<br>BOQ No.6-3<br>BOQ No.6-4<br>BOQ No.6-5 | -  | Please kindly let us know how to calculate unsuitable excavation<br>volume.<br>There is no information about depth of unsuitable material in<br>drawings.<br>ITEM No. 102(1)a<br>ITEM No. 201(5)b                | For Bill No<br>item to be o<br>For Bill N<br>conditions<br>Annex A fo |
| S-05     | 1   | Vol.1<br>Sec.4A         | -         | BOQ No.3<br>BOQ No.4-1<br>BOQ No.4-2<br>BOQ No.4-3<br>BOQ No.4-4                           | -  | Please provide criteria to estimate quantity (depth, nos.) of<br>geotechnical investigation works by contractor. How is the<br>quantity of geotechnical investigation works estimated in BOQ?<br>ITEM No. 204(1) | For viaduc<br>section 204<br>2.7.2.                                   |
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ | BOQ No. 3 | Sub-Structural<br>Work (Pier Work)   | Structural Cast in situ Concrete, 40<br>MPa for Pier Head<br>Structural Cast in Situ Concrete, 50<br>Mpa for Cross Beam (Portal Pier)                                    | Please clarify discrepancy between sum of pier work in drawings<br>and BOQ.<br>ITEM No. 206(1)c<br>ITEM No. 206(1)d  | BOQ and a<br>drawings a   |
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ | BOQ No. 3 | Super-structural<br>work (Segmental<br>Box Girder-Pre-<br>Cast Segment<br>Method)          | Fabrication and Erection of Structural<br>Concrete Class 50 MPa for Precast<br>Segmental Box Girder (W=10.3m,<br>H=2.4m)<br>Fabrication and Erection of Structural       | Please clarify discrepancy between sum of segmental box girder-<br>pre-cast-segment method in drawings and BOQ.  | BOQ and c<br>issued in A  |
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ | BOQ No. 3 | Super-structural<br>work (Balanced<br>Cantilever Box<br>Girder)                            | Structural Cast in situ Concrete, 50<br>Mpa for Cast-in-situ Balanced<br>Cantilever Box Girder   | Please clarify discrepancy between sum of balanced cantilever<br>box girder in drawings and BOQ.<br>ITEM No. 206(2)a   | BOQ and a issued in A   |
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ | BOQ No. 3 | Super-structural<br>work (Cast-In-Situ,<br>Viaduct)  | in-situ Construction on Falseworks   | Please clarify discrepancy between sum of cast-in-situ construction on falseworks in drawings and BOQ.<br>ITEM No. 206(2)b   | BOQ and a issued in A   |
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ | BOQ No. 3 | Miscellaneous<br>Work  | Structural Concrete, 40 Mpa for<br>Protective Concrete Topping<br>Structural Cast in Situ Concrete, 40<br>MPa to Cable Trough Upstands<br>Pre-cast Parapet Wall (H=2.0m) | Please clarify discrepancy between sum of miscellaneous work in<br>drawings and BOQ.<br>ITEM No. 206(8)c<br>ITEM No. 206(11)a<br>ITEM No. 229(1)   | BOQ and a issued in A   |

No. 2, Item No. 102(1)a is only an assumption, e deleted in Addendum 3

No. 3 Item 201(5)b Pile cap Excavation (in dry ns) (Unsuitable Material), refer to TS 201 for the method of measurement.

*uct and bridges, refer to TS 200 Annex A* 204.1.1.2 and TS 200 Specifications section 204.

drawings are the same. Refer to Addendum 3 and Addendum 2 BOQ

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

| Packages | Vol | Sec                     | Page No.    | Clause No./Title                   | Reference Text<br>(if necessary)   | Clarification<br>Request   |   |
|----------|-----|-------------------------|-------------|------------------------------------|--|--|---|
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ | BOQ No. 4-1 | Building Works<br>Structural Works | Structural Concrete, Class "AAA" (31<br>MPa) for Column<br>Structural Concrete, Class "AAA" (36<br>Mpa) for tie beam (At-Grade Beam)<br>Structural Concrete, Class "AAA" (31<br>Mpa) for Slab on Fill (At-Grade<br>Beam)<br>Structural Concrete, Class "AAA" (31<br>Mpa) for Beam  | Please clarify discrepancy between sum of building structural<br>works in drawings and BOQ.<br>ITEM No. 405(3)b<br>ITEM No. 405(6)a<br>ITEM No. 405(7)ba<br>ITEM No. 405(10)b                    | The BOQ is<br>rev. 21.2 No<br>are 36 MPa<br>MPa. In NS<br>says, colum |
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ | BOQ No. 4-2 | Building Works<br>Structural Works | Structural Concrete, Class "AAA" (36<br>Mpa) for Pile Cap/ Footing<br>Structural Concrete, Class "AAA" (31<br>MPa) for Column<br>Structural Concrete, Class "AAA" (36<br>MPa) for Tie Beam (At-Grade Beam)<br>Structural Concrete, Class "AAA" (31<br>MPa) for Elevated Slab/Concrete<br>Stairs/Concrete Gutter<br>Structural Concrete, Class "AAA" (31<br>MPa) for Beam | Please clarify discrepancy between sum of building structural<br>works in drawings and BOQ.<br>ITEM No. 405(1)a<br>ITEM No. 405(3)b<br>ITEM No. 405(6)a<br>ITEM No. 405(9)b<br>ITEM No. 405(10)b | The BOQ is<br>21 Note #3<br>MPa. In NS<br>says, colum                 |

*Q is correct. In NSRP-DWG-SPO-ST-4111 2 Note #3 says, foundation girders and pile caps Pa. Note #4 says, columns and walls are 31 NSRP-DWG-SPO-ST-4121 to 4141 Note #3 umns, slabs, and beams are 31 MPa.* 

*b* is correct. In NSRP-DWG-PTA-ST-4111 rev. 43 says, foundation girders and pile caps are 36 NSRP-DWG-PTA-ST-4121 to 4141 Note #3 mns, slabs, and beams are 31 MPa.

| Packages | Vol | Sec                                     | Page No.                                    | Clause No./Title                                 | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
|----------|-----|---|---|--|--|---|--|
| S-05     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                 | BOQ No. 4-3                                 | Building Works<br>Structural Works               | Structural Concrete, Class "AAA" (31<br>MPa) for Column<br>Structural Concrete, Class "AAA" (36<br>MPa) for Tie Beam (At-Grade Beam)<br>Structural Concrete, Class "AAA" (31<br>Mpa) for Slab on Fill (At-Grade<br>Beam)<br>Structural Concrete, Class "AAA" (31<br>MPa) for Reinforced Concrete Wall<br>(RCW)<br>Structural Concrete, Class "AAA" (31<br>MPa) for Elevated Slab/Concrete<br>Stairs/Concrete Gutter<br>Structural Concrete, Class "AAA" (31<br>MPa) for Beam | Please clarify discrepancy between sum of building structural<br>works in drawings and BOQ.<br>ITEM No. 405(3)b<br>ITEM No. 405(6)a<br>ITEM No. 405(7)b<br>ITEM No. 405(8)b<br>ITEM No. 405(8)b<br>ITEM No. 405(9)b<br>ITEM No. 405(10)b  | The BOQ a<br>rev. 21 Not<br>are 36 MP<br>NSRP-DW<br>columns, s |
| S-05     | 2   | Vol.2<br>NSRP-DWG-<br>SPO-EL-5011       | -   | LOW VOLTAGE<br>POWER SINGLE<br>LINE DIAGRAM<br>1 | -  | We can't find detail specification for this generator set in Book2.<br>Specification for electrical work.<br>Please inform us detail spec for this generator set.   | Refer to up<br>regarding<br>and Specif<br>manufactu            |
| S-05     | 2   | Vol.2<br>NSRP-DWG-<br>PTA-EL-5011       | -   | LOW VOLTAGE<br>POWER SINGLE<br>LINE DIAGRAM<br>1 | -  | We can't find detail specification for this generator set in Book2.<br>Specification for electrical work.<br>Please inform us detail spec for this generator set.   | Refer to up<br>regarding<br>and Specif<br>manufactu            |
| S-05     | 2   | Vol.2<br>NSRP-DWG-<br>BIN-EL-5011       | -   | LOW VOLTAGE<br>POWER SINGLE<br>LINE DIAGRAM<br>1 | -  | We can't find detail specification for this generator set in Book2.<br>Specification for electrical work.<br>Please inform us detail spec for this generator set.   | Refer to up<br>Regarding<br>and Specif<br>manufactu            |
| S-05     | 2   | Vol.2<br>NSRP-DWG-<br>VIA05-DR-<br>4021 | -   | -  | -  | As per drawing, NSRP-DWG-VIA05-DR-4021, "Realigned<br>Canal" is mentioned in the drawing.<br>Please clarify Canal realignment work is under contractor's<br>responsibility.<br>If not, please provide the completion dates for Canal realignment.<br>Will it be handed over before commencement of construction ? | The realig   |
| S-05     | 2   | Vol.2<br>Book 1<br>03_CP S-05<br>VIA05  | NSRP-DWG-<br>VIA05-ST-<br>0027(REV21.<br>1) | GENERAL<br>ARRAGENMENT                           | SAN VICENTE BINAN RIVER<br>FLOOD LVL.  | Please clarify the "FLOOD LVL." indicates a employer's request<br>for river-crossing temporary work.<br>And please provide the return-year of the flood level, cloud<br>marked, and the flowrate as well.   | Flood heig<br>local inter                                      |

## **Final Response** 0 is correct. In NSRP-DWG-BIN-ST-4111 21 *Note #3 says, foundation girders and pile caps* IPa, & columns and walls are 31 MPa. In WG-BIN-ST-4121 to 4141 Note #3 says, , slabs, and beams are 31 MPa. updated TS-700, SCRP Vol 2, page 196, g Generator including Conditions of Contract cification. Contractor to validate based on cturer's data of approved material. updated TS-700, SCRP\_Vol 2, page 196, g Generator including Conditions of Contract cification. Contractor to validate based on cturer's data of approved material. updated TS-700, SCRP\_Vol 2, page 196, ng Generator including Conditions of Contract cification. Contractor to validate base on turer's data of approved material.

igned canal is the scope of the Contractor

eights shown are for the 100 year flow based on erviews and/or NOAH Flood Maps.

| Packages | Vol | Sec                                    | Page No.  | Clause No./Title                       | Reference Text<br>(if necessary) | Clarification<br>Request  | Final Response  |
|----------|-----|--|---|--|----------------------------------|---|---|
| S-05     | 2   | Vol.2<br>Book 1<br>03_CP S-05<br>VIA05 | NSRP-DWG-<br>VIA05-ST-<br>0037(REV21.<br>1)                               | GENERAL<br>ARRAGENMENT                 | STA ROSA RIVER FLOOD LVL.        | Please provide the level of "FLOOD LVL." and its return period with flowrate as well.   | Flood heights shown are for the 100 year flow based on<br>local interviews and/or NOAH Flood Maps.  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | -   | BOQ No.4-1<br>BOQ No.4-2<br>BOQ No.4-3 | -                                | Please provide criteria to calculate Structural Concrete for Pile<br>Cap/Footing, Column, Tie Beam, Slab on Fill, Reinforced<br>Concrete Wall and Elevated Slab/Concrete Stairs/Concrete<br>Gutter for Cabuyao, Banlic and Calamba Station.<br>ITEM No. 405(1)a<br>ITEM No. 405(3)a & b<br>ITEM No. 405(3)a & b<br>ITEM No. 405(6)a<br>ITEM No. 405(7)a<br>ITEM No. 405(8)a<br>ITEM No. 405(9)a | Please refer to TS Annex A - Section 405.   |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | NSRP-DWG-<br>CAB(BAN)-<br>ST-4111,<br>4302                                | BOQ No.4-1<br>BOQ No.4-2               | -                                | For Cabuyao and Banlic Station, there is a discrepancy of Pile<br>Cap Size between Pilecap Schedule(ST-4111) and Pile Cap<br>Detail(ST-4302).<br>The discrepancy may affect the quantity of Main Beam also<br>because the beam length may be confirmed based on Pile Cap<br>Size.<br>Please clarify which information about Pile Cap should be<br>followed.                                     | For Cabuyao Station, the Pile Cap sizes have already<br>been updated. Refer to sheet NSRP-DWG-CAB-ST-<br>4111 and NSRP-DWG-CAB-ST-4302 rev 21.2.<br>For Banlic Station, the Pile Cap Sizes to be updated<br>and reflected on sheets NSRP-DWG-BAN-ST-4111 and<br>NSRP-DWG-BAN-ST-4302 rev 21.3 to be issued in<br>Addendum 3 |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | NSRP-DWG-<br>BAN-ST-<br>4131, 4201  | BOQ No.4-2                             | -                                | For Banlic station, there is a discrepancy of Column Type in<br>Section A/14 between ST-4131 and ST-4201.<br>Please clarify which type of column should be adjusted in A/14.<br>(C2 or C5)  | Column C2 will be used in A/14. Sheet NSRP-DWG-<br>BAN-ST-4131 to be updated to rev 21.3 in Addendum 3  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | NSRP-DWG-<br>BAN-ST-<br>4131  | BOQ No.4-2                             | -                                |   | CG4A and CG5 dimension is 800x1000. Sheet NSRP-<br>DWG-BAN-ST-4131 to be updated to rev 21.3 in<br>Addendu 3  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | NSRP-DWG-<br>BAN-ST-<br>4141  | BOQ No.4-2                             | -                                | For Platform Floor drawing for Banlic Station, there is a text 'C2' for Column in A14 and D14, but there is no Column mark in the drawing. Please clarify whether there is a C2 Column or not.  |   |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | NSRP-DWG-<br>BAN-ST-<br>4111, 4121,<br>4131, 4136,<br>4141, 4212,<br>4213 | BOQ No.4-2                             | -                                | For Banlic Station, there is a discrepancy of column type in Grid 7, 13 and 16 between (ST-4111, 4121, 4131, 4136, 4141) and (ST-4212, 4213). Please clarify which type of column should be adjusted in Grid 7, 13 and 16.  | The drawings will be updated to be more consistent. The<br>following sheets will be updated to rev 21.3 in<br>Addendum 3<br>NSRP-DWG-BAN-ST-4111<br>NSRP-DWG-BAN-ST-4121<br>NSRP-DWG-BAN-ST-4131<br>NSRP-DWG-BAN-ST-4213  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | -   | BOQ No.3                               | Part B.2 206 (1) c               | Please clarify discrepancy between sum of Structural Cast in situ<br>Concrete, 40 MPa for Pier Head in drawings and BOQ   | BOQ and drawings are the same. Refer to drawings issued in Addendum 3 and BOQ issued in Addendum 2  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ                | -   | BOQ No.3                               | Part B.2 206 (1) d               | Please clarify discrepancy between sum of Structural Cast in Situ<br>Concrete, 50 Mpa for Cross Beam (Portal Pier) in drawings and<br>BOQ   | BOQ and drawings are the same. Refer to drawings issued in Addendum 3 and BOQ issued in Addendum 2  |

| Packages    | Vol | Sec           | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request   |                       |
|-------------|-----|---------------|----------|------------------|----------------------------------|--|-----------------------|
|             |     | Vol.1A        |          |                  |                                  | Please clarify discrepancy between sum of Prestressing Steel for   | BOQ and a             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | PART B.4 208(1) c                | Precast Segmental Box Girder in drawings and BOQ   | issued in A           |
|             |     | BOQ           |          |                  |                                  |  | 1554104 111 21        |
|             |     | Vol.1A        |          |                  |                                  | Please clarify discrepancy between sum of Structural Cast in situ  | BOQ and a             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part B.5 206(2) a                | Concrete, 50 Mpa for Cast-in-situ Balanced Cantilever Box  | issued in A           |
|             |     | BOQ           |          |                  |                                  | Girder in drawings and BOQ   |                       |
| G 0(        | 1.4 | Vol.1A        |          | DOON 2           | D (D 5 200(1))                   | Please clarify discrepancy between sum of Prestressing Steel for   | BOQ and a             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part B.5 208(1) b                | Cast-in-situ Balanced Cantilever Box Girder in drawings and BOQ  | issued in A           |
|             |     | BOQ<br>Vol.1A |          |                  |                                  |  |                       |
| S-06        | 1A  | Sec.4A        |          | BOQ No.3         | Part B.6 206(2) b                | Please clarify discrepancy between sum of Structural Concrete,<br>40 MPa for Cast-in-situ Construction on Falseworks in drawings | BOQ and a             |
| 3-00        | IA  | BOQ           | -        | BOQ NO.5         | rait B.0 200(2) 0                | and BOQ  | issued in A           |
|             |     | Vol.1A        |          |                  |                                  |  |                       |
| S-06        | 1A  | Sec.4A        | _        | BOQ No.3         | Part B.6 208(1)a                 | Please clarify discrepancy between sum of Prestressing Steel for   | BOQ and a             |
| 5-00        | 174 | BOQ           |          | DOQ NO.5         | 1 art D.0 200(1)a                | Cast-in-situ Superstructure on Falseworks in drawings and BOQ  | issued in A           |
|             |     | Vol.1A        |          |                  |                                  | Please clarify discrepancy between sum of Structure Cast in situ   |                       |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part B.8 206(5)e                 | Concrete, 40Mpa for RC Slab of Steel Tied Arch Bridge in   | BOQ and a             |
| 2 00        |     | BOQ           |          | 202100           |                                  | drawings and BOQ   | issued in A           |
|             |     | Vol.1A        |          |                  |                                  |  |                       |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part B.8 231(1)                  | Please clarify discrepancy between sum of Stay Cables (Epoxy   | BOQ and a             |
|             |     | BOQ           |          |                  |                                  | coated and filled, ECF strands) in drawings and BOQ  | issued in A           |
|             |     | Vol.1A        |          |                  |                                  |  |                       |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part B.9 206(9)b)                | Please clarify discrepancy between sum of Structural Concrete,   | BOQ and a             |
|             |     | BOQ           |          |                  |                                  | 40 MPa for Wall of At-grade Structures in drawings and BOQ   | issued in A           |
|             |     | Vol.1A        |          |                  |                                  | Please clarify discrepancy between sum of Structural Concrete,   | POO and               |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part B.9 206(10)g                | 40 MPa for Wall of At-grade Structures in drawings and BOQ   | BOQ and a issued in A |
|             |     | BOQ           |          |                  |                                  | to will a for wall of Al-grade Structures in drawings and DOQ  | issueu in A           |
|             |     | Vol.1A        |          |                  |                                  | Please clarify discrepancy between sum of Structural Concrete,   | BOQ and d             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part B.11 206(8)e                | 40 MPa for Emergency Staircases in drawings and BOQ  | issued in A           |
|             |     | BOQ           |          |                  |                                  |  | 1551101111            |
|             |     | Vol.1A        |          |                  |                                  | Please clarify discrepancy between sum of Drain PVC Pipe (200)   | BOO and a             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part C.122(1)                    | and Accessories for Elevated Section in drawings and BOQ   | issued in A           |
|             |     | BOQ           |          |                  |                                  |  |                       |
| <b>G</b> 0( | 1.4 | Vol.1A        |          |                  | D ( 122/2)                       | Please clarify discrepancy between sum of Drain PVC Pipe (350)   | BOQ and c             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part C.122(2)a                   | and Accessories for Elevated Section in drawings and BOQ   | issued in A           |
|             |     | BOQ           |          |                  |                                  |  |                       |
| G 0(        | 1.4 | Vol.1A        |          | DOON 2           | D (D 20((9))                     | Please clarify discrepancy between sum of Structural Concrete,   | BOQ and a             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part D 206(8)c                   | 40 Mpa for Protective Concrete Topping   | issued in A           |
|             |     | BOQ<br>Vol.1A |          |                  |                                  | Discourse and the activity of a solution of the strength Court in Site   |                       |
| S-06        | 1A  | Sec.4A        |          | BOQ No.3         | Part D 206(11)a                  | Please provide criteria to calculate Structural Cast in Situ<br>Concrete, 40 MPa to Cable Trough Upstands in drawings and        | BOQ and d             |
| 3-00        | IA  | BOQ           | -        | DOQ NO.3         | 1 alt D 200(11)a                 | BOQ  | issued in A           |
|             |     |               |          |                  |                                  |  |                       |
|             |     | Vol.1A        |          |                  |                                  | Please clarify discrepancy between sum of Precast Cover Precast  | BOQ and d             |
| S-06        | 1A  | Sec.4A        | -        | BOQ No.3         | Part D 206(11)c                  | Concrete Cover to Cable Trough (Type-2) – reinforcement to be  | issued in A           |
|             |     | BOQ           |          |                  |                                  | included in the unit rate in drawings and BOQ  |                       |

#### **Final Response**

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

| Packages | Vol | Sec   | Page No.   | Clause No./Title   | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
|----------|-----|---|--|--|--|---|--|
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ   | -  | BOQ No.3   | Part D 209(4)  | Please clarify discrepancy between sum of Miscellaneous<br>Steelwork – Mild Steel Handrails in drawings and BOQ   | BOQ and a issued in A  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ   | -  | BOQ No.3   | Part D 209(5)  | Please clarify discrepancy between sum of Miscellaneous<br>Steelwork - Expansion Joint Assemblies in drawings and BOQ   | BOQ and a issued in A  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ   | -  | BOQ No.3   | Part D 229(1)  | Please clarify discrepancy between sum of Pre-cast Parapet Wall (H=2.0m) in drawings and BOQ  | BOQ and a issued in A  |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ<br>Vol.2<br>Book 1<br>03_CP S-06<br>VIA06 | NSRP-DWG-<br>VIA06-ST-<br>0101<br>~<br>0106  | PIER SCHEDULE  | Bored Pile (1000mmφ), (in dry<br>conditions)<br>Bored Pile (1200mmφ), (in dry<br>conditions)<br>Bored Pile (1500mmφ), (in dry<br>conditions) | Please clarify discrepancy between sum of bored pile length in<br>drawings and BOQ.<br>ITEM No. 204(2)a<br>ITEM No. 204(2)b<br>ITEM No. 204(2)c   | BOQ and a<br>issued in A   |
| S-06     | 1A  | Vol.1A<br>Sec.4A<br>BOQ<br>Vol.2<br>Book 2<br>03_CP S-06<br>STRUC | NSRP-DWG-<br>CAB,<br>BAN,<br>CAL<br>-ST-4101<br>NSRP-DWG-<br>CAB,<br>BAN,<br>CAL<br>-ST-4301 | PILE SETOUT<br>PLAN<br>REINFORCEMEN<br>T DETAILS<br>BORED PILE   | Bored Pile (800mm diameter)<br>Bored Pile (1000mm diameter)<br>Bored Pile (1200mm diameter)<br>Bored Pile (1500mm diameter)                  | Please clarify discrepancy between sum of bored pile length in<br>drawings and BOQ.<br>ITEM No. 401(8)<br>ITEM No. 401(9)<br>ITEM No. 401(10)<br>ITEM No. 401(11)                                 | BOQ and a<br>issued in A   |
| S-06     | 1   | Vol.1<br>Sec.4A   | -  | BOQ No.2<br>BOQ No.3<br>BOQ No.4-1<br>BOQ No.4-2<br>BOQ No.4-3<br>BOQ No.5<br>BOQ No.6-1<br>BOQ No.6-2<br>BOQ No.6-3<br>BOQ No.6-4 | -  | Please provide criteria to calculate backfill/foundation fill<br>volume.<br>What is clear meaning of backfill and foundation fill?<br>ITEM No. 201(4)d<br>ITEM No. 201(4)e                        | Backfill rej<br>refill the ho<br>related wor<br>Foundatio<br>that is plac<br>the grade a<br>ground sur |
| S-06     | 1   | Vol.1<br>Sec.4A   | -  | BOQ No.2<br>BOQ No.3<br>BOQ No.6-1<br>BOQ No.6-2<br>BOQ No.6-3<br>BOQ No.6-4   | -  | Please kindly let us know how to calculate unsuitable excavation<br>volume.<br>There is no information about depth of unsuitable material in<br>drawings.<br>ITEM No. 102(1)a<br>ITEM No. 201(5)b | For Bill No<br>item to be o<br>For Bill N<br>conditions)<br>Annex A fo                                 |

#### **Final Response**

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

drawings are the same. Refer to drawings Addendum 3 and BOQ issued in Addendum 2

refers to a volume of suitable material used to hole or foundation, once excavation, and the work have been completed.

tion Fill refers to a volume of suitable material laced and compacted for the purpose of raising e above the level of the existing surrounding surface.

No. 2, Item No. 102(1)a is only an assumption, e deleted in Addendum 3

No. 3 Item 201(5)b Pile cap Excavation (in dry ns) (Unsuitable Material), refer to TS 201 for the method of measurement.

| Packages | Vol | Sec  | Page No.                                    | Clause No./Title  | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |
|----------|-----|--|---|---|---|---|--|
| S-06     | 1   | Vol.1<br>Sec.4A  | -   | BOQ No.3<br>BOQ No.4-1<br>BOQ No.4-2<br>BOQ No.4-3  | -   | Please provide criteria to estimate quantity (depth, nos.) of<br>geotechnical investigation works by contractor. How is the<br>quantity of geotechnical investigation works estimated in BOQ?<br>ITEM No. 204(1)  | For viaduc<br>section 204<br>2.7.2.  |
| S-06     | 2   | Vol.2<br>Book 1<br>03_CP S-06<br>VIA06                         | NSRP-DWG-<br>VIA06-ST-<br>0035<br>(REV21.1) | GENERAL<br>ARRAGENMENT  | SAN CRISTOBAL RIVER FLOOD<br>LEVE: 10.6   | Please clarify the "FLOOD LEVEL" indicates a employer's request for river-crossing temporary work.<br>And please provide the return-year of the flood level, cloud marked, "FLOOD LEVEL: 10.60" and the flowrate as well.   | The 100 ye<br>discharge f<br>flood level<br>the effect o   |
| S-06     | 2   | Vol.2<br>Book 1<br>03_CP S-06<br>VIA06                         | NSRP-DWG-<br>VIA06-ST-<br>0035(REV21.<br>1) | GENERAL<br>ARRAGENMENT  | SAN JUAN RIVER FLOOD LVL.   | Please provide the level of "FLOOD LVL." and its return period with flowrate as well.   | Flood heig<br>local interv   |
| S-06     | 2   | Vol.2<br>NSRP-DWG-<br>CAB-EL-5011                              |   | -   | LOW VOLTAGE POWER SINGLE<br>LINE DIAGRAM 1  | We can't find detail specification for this generator set in Book2.<br>Specification for electrical work.<br>Please inform us detail spec for this generator set.   | Refer to up<br>regarding<br>and Specifi<br>manufactu   |
| S-06     | 2   | Vol.2<br>NSRP-DWG-<br>BAN-EL-5011                              |   | -   | LOW VOLTAGE<br>POWER SINGLE<br>LINE DIAGRAM 1   | We can't find detail specification for this generator set in Book2.<br>Specification for electrical work.<br>Please inform us detail spec for this generator set.   | Refer to up<br>regarding<br>and Specifi<br>manufactu   |
| S-06     | 2   | Vol.2<br>NSRP-DWG-<br>CAL-EL-5011                              | -   | -   | LOW VOLTAGE<br>POWER SINGLE<br>LINE DIAGRAM 1   | We can't find detail specification for this generator set in Book2.<br>Specification for electrical work.<br>Please inform us detail spec for this generator set.   | Refer to up<br>regarding<br>and Specifi<br>manufactu   |
| S-07     | _   | CP S-07<br>Site data<br>10.17 Depot<br>Design Report<br>(S-07) | 406   | 8.1.2 Natural<br>Condition of Depot<br>Site<br>(1) Terrain                                    | the maximum elevation of the terrain<br>is approximately 13.4 m above the<br>sea level (hereafter refer as a.s.l) | Please clarify the relations among the survey elevation datum,<br>"a.s.l.", "Namria Control Points", "Mean Sea Level", and "<br>LLDA elevation"   | The horizo<br>CORS (Con<br>reference p<br>The coord<br>(ZONE3).<br>The stando<br>relative to t<br>The topo s<br>"a.s.l." and |
| S-07     | -   | CP S-07<br>Site data   | -   | CAD file "FINAL<br>South Topographic<br>Map 20191108.dwg"                                     | -   | Please confirm all elevations of the survey points in the topographic map, "FINAL South Topographic Map 20191108.dwg", are based on NAMRIA datum.   | Topograph<br>value of the  |
| S-07     | -   | CP S-07<br>Site Data<br>10.04<br>Hydrology<br>Report           | 17,<br>23                                   | 9.3.2 Climate Change<br>Table 9.3.2<br>9.4.3 Hydrologic<br>Analysis<br>(1) Rainfall Intensity | Table 9.3.2<br>formula 9.4.3  | Rainfall intensity value of Table 9.3.2 is different with rainfall<br>intensity formula of 9.4.3. For example, rainfall intensity for<br>10yr return period and 20min duration is 124.4mm/hr given in<br>Table 9.3.2. However, calculated value from rainfall intensity<br>formula 9.4.3 is 215.8mm/hr.<br>Please clarifiy which value is correct reference for S07 project<br>detail design and contractor's design. | The rainfa<br>generate th<br>curve fittin<br>climate cho<br>Using the<br>while the fe<br>The formu                           |

#### **Final Response**

ict and bridges refer to TS 200 Annex A 04.1.1.2 and TS 200 Specifications section 204.

year flood level with climate change peak of for San Cristobal River is 1102.20cu.m/s. The of at this location is estimated to be 10.83m with of the piers in the waterway.

ights shown are for the 100 year flow based on rviews and/or NOAH Flood Maps.

updated TS-700, SCRP\_Vol 2, page 196, g Generator including Conditions of Contract ifications. Contractor to validate based on turer's data of approved material.

updated TS-700, SCRP\_Vol 2, page 196, g Generator including Conditions of Contract ifications. Contractor to validate based on turer's data of approved material.

*updated TS-700, SCRP\_Vol 2, page 196,* g Generator including Conditions of Contract ifications. Contractor to validate based on turer's data of approved material.

contal position reference is the NAMRIA fontinuously Operating Reference Stations) point.

dinate system used was WGS84 and PRS92

dard for elevation is the NAMRIA benchmark o the average sea level in Manila Bay. o survey did not investigate the relationship nd "LLDA elevation".

ohic maps are created based on the elevation the NAMRIA benchmark.

fall intensity given in the table are used to the formula using the regression analysis and ing and already incorporate the increase due to hange:

e table, the 10yr, 20min duration is 186mm/hr. formula gives 215mm/hr. 1ula should be used.

#### CD \$04 07 Da to Clarification Do mosts (Datah Q)

|          | <u>CP S04-07 Responses to Clarification Requests (Batch 8)</u> |  |                                     |   |  |   |   |  |  |  |  |  |
|----------|--|--|-------------------------------------|---|--|---|---|--|--|--|--|--|
| Packages | Vol  | Sec  | Page No.                            | Clause No./Title  | Reference Text<br>(if necessary)           | Clarification<br>Request  | Final Response  |  |  |  |  |  |
| S-07     | -  | CP S-07<br>Site Data<br>10.04<br>Hydrology<br>Report           | 17                                  | 9.3.2 Climate Change<br>Table 9.3.2   | Table 9.3.2                                | Please check values of Table 9.3.2. For example, value of 5mins duration and 120mins duration is same.  | The formula should be used to generate the rainfall intensities for a specific duration and return period.  |  |  |  |  |  |
| S-07     | -  | CP S-07<br>Site Data<br>10.17 Depot<br>Design Report<br>(S-07) | 411                                 | 8.1.2 Natural<br>Condition of<br>Depot Site<br>(2) Flood risk<br>Figure 8.1.1.9 | -  | Please provide flood rate and flood level of San Cristobal river<br>for 2yr, 5yr, 10yr, 20yr, 50yr, 100yr return period at each station<br>from S07 Site (0+000) to Lagnua Lake.  | Available flood information is provided, No further information is available.   |  |  |  |  |  |
| S-07     | -  | CP S-07<br>Site Data<br>10.17 Depot<br>Design Report<br>(S-07) | 411                                 | 8.1.2 Natural<br>Condition of<br>Depot Site<br>(2) Flood risk<br>Figure 8.1.1.9 | -  | Please provide cross section data of San Cristobal river at each station from S07 Site (2+550) to Lagnua Lake, which are not provided with Topo CAD file. The Topo CAD file is only containing sections from 0+000 to 2+550.  | Available flood information is provided, No further information is available.   |  |  |  |  |  |
| S-07     | 2  | CP S-07<br>Vol.2<br>Book1(Civil)                               | DR-2734                             | 04_CP S-07_DPSFE  | Table "Reinforced Concrete Box<br>Culvert" | Please provide rebar detail for W500 x D500 and W800 x xD500<br>Box Culvert.  | This drawing will be amended to add these details and are to be submitted as Rev 21.3.  |  |  |  |  |  |
| S-07     | 2  | CP S-07<br>Vol.2<br>Book1(Civil)                               | DR-2734                             | 04_CP S-07_DPSFE  | Open Channel Details                       | Please provide installation spacing(center to center distance) of Lintel Beam.  | This drawing will be amended to add these details and are to be submitted as Rev 21.3.  |  |  |  |  |  |
| S-07     | 2  | Vol.2<br>Book 2<br>01_S07<br>ARCH                              | NSRP-DWG-<br>AR-3204<br>Rev.21      | Drawings  | -  | On drawing No. NSRP-DWG-AR-3204 Rev.21, preliminary planting schedule is shown however the quantity and remarks doesn't match for item 6,7 and 8. Kindly clarify and provide accurate quantity.   | Bidder to follow and price as shown in the table and BOQ Bill No 4-3.1, unless advised otherwise.   |  |  |  |  |  |
| S-07     | 2  | Vol.2<br>Book 2<br>01_S07<br>ARCH                              | NSRP-DWG-<br>DEP-AR-<br>3401 Rev.21 | Drawings  | -  | According to drawing No. NSRP-DWG-DEP-AR-3401 Rev.21,<br>there is detail for interlocking which consists of interlocking<br>block, sand, permeable concrete and crusher-run. However,<br>provided BOQ only shows Architectural interlocking concrete<br>block paver. Kindly confirm that said 4 components are parts of<br>architectural interlocking concrete clock paver. | Yes, cost of PIN D504(2) Architectural Interlocking<br>Concrete Block Paver under Bill No 4-3.2 shall include<br>the following:<br>30mm Sand, 70mm permeable concrete, and 50mm<br>crusher run.<br>In reference to drawing NSRP-DWG-DEP-AR-3401,<br>rev. 21 |  |  |  |  |  |
| S-07     | 2  | Vol.2<br>Book 2<br>01_S07<br>ARCH                              | NSRP-DWG-<br>DEP-AR-<br>3401 Rev.21 | Drawings  | -  | NSRP-DWG-DEP-AR-3401 Rev.21 show the detail of all steel components however there is still missing items like bolt size, welding type and thickness. Kindly provide full details of steel structure.  | For full details, refer to structural NSRP-DWG-DEP-<br>ST-4061 to 4062 issued as Rev21.2 in Addendum 2  |  |  |  |  |  |
| S-07     | 2  | Vol.2<br>Book 2<br>01_S07<br>ARCH                              | NSRP-DWG-<br>DEP-AR-<br>3401 Rev.21 | Drawings  | -  | The drawing No. NSRP-DWG-DEP-AR-3401 Rev.21 shows<br>typical section which include catch basin and other components.<br>Kindly provide the connection details between catch basin and<br>pedestrian shed footing. Also kindly provide rebar details for<br>footing including footing size. There is no detail in civil drawing<br>as well.                                  | Details will be added under NSRP-DWG-DEP-AR-3401<br>as Rev 21.3 in Addendum 3   |  |  |  |  |  |

|   | Packages | Vol | Sec   | Page No.   |   | Reference Text<br>(if necessary)           | Clarification<br>Request  |   |
|---|----------|-----|---|--|---|--|---|---|
| • | S-07     | -   | -   | NSRP-DWG-<br>DEP-RD-<br>1208 Rev.21                          | Drawings                                      | _  | The drawing No. NSRP-DWG-DEP-RD-1208 Rev.21 shows<br>PCCP. We understand that it is Portland cement concrete<br>pavement however there is no rebar details. Kindly provide<br>details.  | This is un-i<br>detail to be<br>at longitudi<br>please refer                                  |
| - | S-07     | -   | -   | NSRP-DWG-<br>DEP-AR-<br>3221 Rev.21                          | Drawings                                      | -  | The drawing No NSRP-DWG-DEP-AR-3221 Rev.21 shows the item '100*100*100mm cube granite stone' however provided BOQ doesn't show this item as well as quantity. Kindly provide quantity of this Item and details.   | 1. NSRP-D<br>21.3 and iss<br>2. BOQ with  |
| _ | S-07     | 1   | Vol. 1<br>1.3 CP S-07<br>Vol.1A<br>Sec.4A BOQ<br>20201001 |  | BOQ   | _  | According to BOQ, water supply items are shown however there<br>is no detail drawings. Kindly provide detail drawings for<br>irrigation.  | Pay items fa<br>Softscape a<br>issued in Ad   |
| - | S-07     | 2   | Vol.2<br>Book 2<br>01_S07<br>ARCH                         | NSRP-DWG-<br>DEP-AR-<br>3222 Rev.21                          | -   | -  | The drawing No. NSRP-DWG-DEP-AR-3222 Rev.21 shows<br>Stone-finished Flagpole Podium however there is no rebar<br>details. Kindly provide details.   | The details<br>issued Sep 2   |
| - | S-07     | -   | -   | NSRP-DWG-<br>DEP-AR-<br>3222<br>NSRP-DWG-<br>OCC-AR-<br>3206 | -   | _  | We understand from provided BOQ that item D563(9) which is<br>self-standing planting wall is shown on Drawing NSRP-DWG-<br>DEP-AR-3222 Rev.21. However, NSRP-DWG-OCC-AR-3206<br>Rev.21 shows vertical garden wall which shows on BOQ Item<br>D563(10). Kindly clarify the difference between vertical garden<br>wall and self-standing planting wall. | 1. That is so<br>DEP-AR-32<br>2. BOQ to   |
| _ | S-07     | 1A  | CP S-07<br>Vol.1A<br>Sec.4A BOQ                           | BOQ No.5   | Drainage System &<br>Irrigation Channels      | Part C Drainage Works                      | Please provide Drawings for item No. 111(3) Manhole/ Catch<br>Basin, TYPE K (for 1.2m X 1.1m~1.5m RCBC) at BOQ No.5<br>Drainage System & Irrigation Channels, Part C Drainage Works.  | Pay Item "<br>(for 1.2m X<br>issued in Ad<br>"Manhole/<br>RCPC)".<br>For TYPE                 |
| - | S-07     | 2   | CP S-07<br>Vol.2<br>Book1(Civil)                          | DR-2018,<br>2710   | 04_CP S-07_DPSFE                              | Plan(Manhole Type-J)                       | Please confirm that Manhole size of Type-J and Type-K are<br>same.<br>If not, please provide plan and section of Manhole Type-K.  | 2710.<br>Manhole si<br>difference i<br>amended to<br>21.3 in Add                              |
| - | S-07     | 2   | CP S-07 Vol.2   | 02_Book 2<br>(Architectural<br>)                             | CP S-07_01_AR-<br>OCC & CP S-<br>07_01_OCC_ST | OCC_Architectural & Structural<br>drawings | According to OCC Architectural drawings, the elevation is<br>"ELEV +0.00m=+15.31m ABOVE MEAN SEA LEVEL/TOP<br>OF GRADING SURFACE".<br>However, the elevation is "ELEV +0.00m=+15.50m ABOVE<br>MEAN SEA LEVEL/DEPOT TOP OF RAIL/FGL/FFL" at OCC<br>Structural drawings.<br>Please clarify which elevation is correct.                                  | The elevation<br>MEAN SEA<br>see NSRP-1<br>Rev21.<br>Architectur<br>Structural of<br>Addendum |

#### **Final Response**

n-reinforced PCCP, therefore there is no rebar be shown. However, for reinforcement details adinal and transverse construction joints, fer to NSRP-DWG-DEP-RD-1801.

DWG-DEP-AR-3514 will be revised under Rev issued in Addendum 3 will be updated and issued in Addendum 3

for the Water Supply/Irrigation for the at the Depot are already deleted in the BOQ Addendum 1

*ls are shown in NSRP-DWG-DEP-AR-3522 p 21,2020 as Rev21.* 

same Item, to be updated as NSRP-DWG--3222 Rev 21.3. to revised and issued in Addendum 3

"111(3)ao Manhole/ Catch Basin, TYPE K X 1.1m~1.5m RCBC) " to be revised and Addendum 3. The correct description must be e/Catch Basin, TYPE K (for 250mmØ

E K detail, refer to NSRP-DWG-DEP-DR-

sizes of Types J and K are the same. The e is in the grate length. This drawing will be to add additional details and submitted as Rev ddendum 3

ttion is "ELEV +0.00m=+15.311m ABOVE EA LEVEL/TOP OF GRADING SURFACE" P-DWG-OCC-AR-3201 issued Sep 21, 2020 as

tural Drawing has the correct elevation. I drawing will be revised and issued in m 3.

| Packages | Vol | Sec   | Page No.   | Clause No./Title   | Reference Text<br>(if necessary) | Clarification<br>Request   |   |
|----------|-----|---|--|--|----------------------------------|--|---|
| S-07     | 2   | CP S-07 Vol.2   | 02_Book 2<br>(Architectural<br>)                           | CP S-<br>07_00_AR_DEP  | Pedestrian Shed                  | According to Pedestrian Shed Typical Section 1 at NSRP-DWG-<br>AR-3401, Detailed information of Steel Column & Rafter is<br>referred to Structural drawings.<br>However, there is no structural drawings for Steel Column and<br>Rafter.<br>Please provide detailed Structural drawings of Steel Column and<br>Rafter for pedestrian Shed. | For details<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW            |
| S-07     | 2   | CP S-07 Vol.2   | 02_Book 2<br>(Architectural<br>)<br>& 02_Book 1<br>(Civil) | CP S-<br>07_00_AR_DEP<br>& 02_CP S-<br>07_Roads                    | Sidewalks                        | According to Pedestrian Shed Typical Section 1 at NSRP-DWG-<br>AR-3401, Sidewalk consist of Interlocking block, Sand,<br>Permeable Concrete and Crusher-run.<br>However, Sidewalk consist of PCCP and Sub-base course at<br>Civil Road Drawings.<br>Please clarify which Sidewalk is correct.  | Interlockin<br>Crusher-ru<br>issued as R                |
| S-07     | 2   | CP S-07 Vol.2   | BOQ No.4-<br>2.21  | Car Washing Track  | -                                | There is the quantity for Car Washing Track Building at BOQ<br>No.4-2.21.<br>However, there is no drawings for Car Washing Track Building.<br>Please provide drawings of Car Washing Track Building to<br>clarify quantities of Car Washing Track Building.  | For details<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW |
| S-07     | 2   | CP S-07 Vol.2<br>Book1  | NSRP-DWG-<br>DEP-DR-<br>2652                               | Drainage, Plumbing,<br>Sanitary, Fire Pro. &<br>Electrical Drawing | -                                | Kindly provide detailed information about the "connect to existing canal" specified in the drawing   | The earth c<br>the existing<br>deleted.                 |
| S-07     | 2   | CP S-07 Vol.2<br>Book1  | NSRP-DWG-<br>DEP-DR-<br>2651,<br>2652                      | Drainage, Plumbing,<br>Sanitary, Fire Pro. &<br>Electrical Drawing | -                                | Kindly provide detailed information on the drainage line<br>connected to "MH-3 at the end of the realignment canal 2"  | This manh   |
| S-04     | 1   | Volume 1,<br>Part IA section<br>4 Bill of<br>Quantities   | -  | BOQ No.4-1<br>Alabang Station<br>BOQ No.4-2<br>Muntinlupa Station  | 1506(24) H=500mm Stainlass Steel | There is no detailed drawing for the following items:<br>506(6)C - W=100mm, Stainless Steel Tile Border<br>506(6) - B8; W=200mm Stainless Steel Thresholds<br>506(8) - B3 ; H=150mm, Stainless Steel Baseboard<br>506(24) - H=500mm, Stainless Steel Baseboard for Elevator<br>Wall<br>Please provide details for those mentioned items.   | Details to b<br>3502 rev. 2                             |
| S-04     | 2   | Volume 2,<br>Book 2<br>(Architectural)-<br>Package CP S-<br>04: General<br>Station<br>Architectural<br>Drawings | -  | NSRP-DWG-STA-<br>AR-3522   |                                  | Aluminium Ribbed Wall Panels are shown in the drawing no.<br>NSRP-DWG-STA-AR-3522, however, there is no detail of this<br>item. Therefore, please provide the detailed drawings for this<br>item.  | Aluminum<br>Drawing to<br>AR-3522 re                    |

ils of the Pedestrian Shed, refer to sheets: DWG-DEP-ST-4061, DWG-DEP-ST-4062, and DWG-DEP-ST-4063 Rev 21.2

ing block, Sand, Permeable Concrete and run are correct, see NSRP-DWG-AR-3401 Rev21.

ils of the Pedestrian Shed, refer to sheets: *DWG-CWT-ST-3000; DWG-CWT-ST-4101; DWG-CWT-ST-4111; and DWG-CWT-ST-4112 Rev 21.2.* 

n canal were realigned and will be connected to ng canal. The manhole in this area was

thole was already deleted in Rev 21.2.

be added on sheet no. NSRP-DWG-STA-AR-21.3. Drawings to be issued in Addendum 3

m Ribbed Wall Panels to be added as detail. to be updated as Sheet no. NSRP-DWG-STArev. 21.3 in Addendum 3

| Packages | Vol | Sec   | Page No. | Clause No./Title  | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |  |
|----------|-----|---|----------|---|---|---|--|--|
| S-04     | 1   | Volume 1,<br>Part IA section<br>4 Bill of<br>Quantities   | -        | BOQ No.4-1<br>Alabang Station<br>BOQ No.4-2<br>Muntinlupa Station   | 530(3) - WF7 Wall: 12mm Heat<br>Strengthened Laminated Glass  | There is no detail for item 530(3) - WF7 Wall: 12mm Heat<br>Strengthened Laminated Glass. Therefore, please provide us<br>detailed drawing for price estimation purpose.  | Finishing s<br>to WF4, 12<br>WITH SEC<br>Addendum<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>For Tempe<br>STA-AR-35 |  |
| S-04     | 1   | Volume 1,<br>Part IA section<br>4 Bill of<br>Quantities<br>Volume 2,<br>Book 2<br>(Architectural)-<br>Package CP S-<br>04:<br>Substation<br>SS07<br>Architectural<br>Drawings<br>Substation<br>SS08<br>Architectural<br>Drawings<br>Substation<br>SS09<br>Architectural<br>Drawings | -        | BOQ no. 6-1 for<br>Substation 7<br>BOQ no. 6-2 for<br>Substation 8<br>BOQ no. 6-3 for<br>Substation 9<br>NSRP-DWG-SS7-<br>AR-3101<br>NSRP-DWG-SS8-<br>AR-3101<br>NSRP-DWG-SS9-<br>AR-3101 | 619(17) Portable Toilet<br>619(17) Portable Toilet<br>619(17) Portable Toilet<br>Substation SS07 -Architectural Floor<br>Plan and Section<br>Substation SS08 -Architectural Floor<br>Plan and Section<br>Substation SS09 -Architectural Floor<br>Plan and Section | As indicated in the BOQ no. 6-1 for Substation 7, no. 6-2 for<br>Substation 8 and no. 6-3 for Substation 9, Item No. 619(17) is<br>identified to be a portable toilet, whereas the drawing no. NSRP-<br>DWG-5507-AR-3101, NSRP-DWG-5508-AR-3101 and NSRP-<br>DWG-5509-AR-3101 show a permanent toilet. It is obvious that<br>there is a discrepancy between the BOQ and the drawings.<br>Therefore, please confirm which one is the correct one and<br>provide its details. | Toilet for a<br>Please refer<br>Reference<br>NSRP-DW<br>NSRP-DW<br>rev. 21   |  |
| S-04     | 1   | Volume 1,<br>Part IA section<br>4A Bill of<br>Quantities  | -        | BOQ no. 6-1 for<br>Substation 7<br>BOQ no. 6-2 for<br>Substation 8<br>BOQ no. 6-3 for<br>Substation 9   | S555(1) Door Sign and S555(2)<br>Building Sign  | Item No. S555(1) Door Sign and S555(2) Building Sign are<br>shown in the BOQ no. 6-1 for Substation 7, no. 6-2 for<br>Substation 8 and no. 6-3 for Substation 9. However, there is no<br>detail shown in the drawing. Therefore, please provide us<br>detailed drawing for thess items.   | New drawin<br>details. Dra   |  |

#### **Final Response**

g schedule will be revised. WF7 to be changed 12MM THK. TEMPERED GLASS PANELS ECURITY FILM. Drawings to be revised in m 3: WG-MUN-AR-3033 WG-MUN-AR-3034 WG-ALA-AR-3035 WG-ALA-AR-3035 WG-ALA-AR-3035 rev 21.3 pered glass detail, please refer to NSRP-DWG-3504 rev 21.3 in Addendum 3

all Substations shall be permanent toilet. fer to the latest BOQ issued in Addendum 2

ee drwgs: WG-PSS7/8/9-PL-6611 WG-PSS7/8/9-SN-6112

ving and sheet number to be added for signage brawings will be issued in Addendum 3

| Packages | Vol | Sec  | Page No. | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request   |  |
|----------|-----|--|----------|---|--|--|--|
| S-05     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities<br>Volume 2 -<br>Book 2<br>(Architectural)-<br>Package CP S-<br>05: Binan<br>Station<br>Architectural<br>Drawings  | -        | (September 2020)<br>NSRP-DWG-BIN-<br>AR-3202 Rev.21<br>(September 2020)   | 2400 x 1200 x 3mm thk 5mm Dia<br>Perforated Aluminum Panel with<br>Applied Polyester Powder Coating<br>Finish on Steel Stud<br>Elevation Sheet 1<br>Elevation Sheet 2<br>Schedule of Wall Finishes Sheet 1<br>Schedule of Wall Types Sheet 1<br>Typical details Wall Sheet 2 | <ol> <li>DWG No. NSRP-DWG-BIN-AR-3569 Rev.21 Date<br/>September 2020, Specify 9 (WF9)2400x1200x3 mm. THK<br/>Perforated Aluminium panel with applied polyester powder<br/>coating finish on steel stud while</li> <li>DWG No. NSRP-DWG-BIN-AR-3571 Rev.21 Date</li> <li>September 2020 WT1 Wall type-1 specify as exterior wall which<br/>is same location as DWG No.NSRP-DWG-BIN-AR-3569 Rev.21</li> <li>Date September 2020, Wall type 1 which shown on typical<br/>details wall as ACP-Aluminium Composite Panel system on<br/>Aluminium at Exterior wall (NSRP-DWG-STA-AR-3504).</li> <li>There is an discrepancy between DWG No. NSRP-DWG-BIN-<br/>AR-3569 Rev.21 Date September 2020 and DWG No. NSRP-<br/>DWG-BIN-AR-3571 Rev.21 Date September 2020 regarding<br/>material system for exterior wall. Please confirm the specification<br/>of exterior wall.</li> </ol> | For Exterio<br>ALUMINUI<br>PHOTOCA<br>(POLYVIN)<br>MINERAL<br>Drawings to<br>NSRP-DW<br>3570, rev. 2 |
| S-05     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities<br>Volume 2 -<br>Book 2<br>(Architectural)-<br>Package CP S-<br>05: Pacita<br>Station<br>Architectural<br>Drawings | -        | BOQ No.4-2 Pacita<br>Station Item<br>no.522(4)<br>NSRP-DWG-PTA-<br>AR-3201 Rev.21<br>(September 2020)<br>NSRP-DWG-PTA-<br>AR-3202 Rev.21<br>(September 2020)<br>NSRP-DWG-PTA-<br>AR-3569 Rev.21 | 2400 x 1200 x 3mm thk 5mm Dia<br>Perforated Aluminum Panel with  | <ol> <li>DWG No. NSRP-DWG-PTA-AR-3569 Rev.21 Date<br/>September 2020, Specify 9 (WF9)2400x1200x3 mm. THK<br/>Perforated Aluminium panel with applied polyester powder<br/>coating finish on steel stud while</li> <li>DWG No. NSRP-DWG-PTA-AR-3571 Rev.21 Date<br/>September 2020 WT1 Wall type-1 specify as exterior wall which<br/>is same location as DWG No.NSRP-DWG-PTA-AR-3569<br/>Rev.21 Date September 2020, Wall type 1 which shown on<br/>typical details wall as ACP-Aluminium Composite Panel system<br/>on Aluminium at Exterior wall (NSRP-DWG-STA-AR-3504).<br/>There is an discrepancy between DWG No. NSRP-DWG-PTA-<br/>AR-3569 Rev.21 Date September 2020 and DWG No. NSRP-<br/>DWG-PTA-AR-3571 Rev.21 Date September 2020 regarding<br/>material system for exterior wall. Please confirm the specification<br/>of exterior wall.</li> </ol>                | For Exterio<br>ALUMINUA<br>PHOTOCA<br>(POLYVIN)<br>MINERAL<br>Drawings to<br>NSRP-DW<br>3570, rev. 2 |

#### **Final Response**

ior walls, please use (WF9)- 4MM THK UM COMPOSITE MATERIAL (ACM) WITH ATALYST & FEVE/PVDF NYLIDENE DIFLUORIDE) COATING AND L FIBER CORE (FIRE RATED). s to be updated in Addendum 3: WG-BIN-AR-3569,NSRP-DWG-BIN-AR-21.3

ior walls, please use (WF9)- 4MM THK UM COMPOSITE MATERIAL (ACM) WITH CATALYST & FEVE/PVDF NYLIDENE DIFLUORIDE) COATING AND L FIBER CORE (FIRE RATED). s to be updated in Addendum 3: WG-PTA-AR-3569, NSRP-DWG-PTA-AR-21.3

| Packages | Vol | Sec   | Page No. | Clause No./Title   | Reference Text<br>(if necessary)   | Clarification<br>Request  |                             |
|----------|-----|---|----------|--|--|---|-----------------------------|
| S-05     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities<br>Volume 2 -<br>Book 2<br>(Architectural)-<br>Package CP S-<br>05: San Pedro<br>Station<br>Architectural<br>Drawings |          | (September 2020)<br>NSRP-DWG-SPO-<br>AR-3202 Rev.21<br>(September 2020)<br>NSRP-DWG-SPO-<br>AR-3569 Rev.21 | 2400 x 1200 x 3mm thk 5mm Dia<br>Perforated Aluminum Panel with<br>Applied Polyester Powder Coating<br>Finish on Steel Stud<br>Elevation Sheet 1<br>Elevation Sheet 2<br>Schedule of Wall Finishes Sheet 1<br>Schedule of Wall Types Sheet 1<br>Typical details Wall Sheet 2 | 1.) DWG No. NSRP-DWG-SPO-AR-3569 Rev.21 Date<br>September 2020, Specify 6 (WF6)Aluminum panels with<br>Calcium Silicate on steel stud<br>2.)DWG No. NSRP-DWG-SPO-AR-3571 Rev.21 Date<br>September 2020 WT1 Wall type-1 specify as exterior wall which<br>is same location as DWG No.NSRP-DWG-SPO-AR-3569<br>Rev.21 Date September 2020, Wall type 1 which shown on<br>typical details wall as ACP-Aluminium Composite Panel system<br>on Aluminium at Exterior wall (NSRP-DWG-STA-AR-3504).<br>There is an discrepancy between DWG and item no.522(4) in the<br>BOQ No.4-4. Please confirm the specification of exterior wall<br>finish, because WF6 item is not shown in the BOQ. If this item is<br>WF9 same as the other station, we can price it in the item<br>no.522(4) of BOQ No.4-4 | 3570, rev. 2                |
| S-05     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities   | -        | Station<br>BOQ No.4-3 Binan<br>Station.  | 506(6)C - W=100mm, Stainless Steel<br>Tile Border<br>506(6) - B8; W=200mm Stainless<br>Steel Thresholds<br>506(8) - B3 ; H=150mm, Stainless<br>Steel Baseboard<br>506(24) - H=500mm, Stainless Steel<br>Baseboard for Elevator Wall  | There is no detailed drawing for the following items:<br>506(6)C - W=100mm, Stainless Steel Tile Border<br>506(6) - B8; W=200mm Stainless Steel Thresholds<br>506(8) - B3 ; H=150mm, Stainless Steel Baseboard<br>506(24) - H=500mm, Stainless Steel Baseboard for Elevator<br>Wall<br>Please provide the details for those mentioned items.  | Details to b<br>3502 rev. 2 |
| S-05     | 2   | Volume 2 -<br>Book 2<br>(Architectural)-<br>Package CP S-<br>05: General<br>Station<br>Architectural<br>Drawings  | -        | NSRP-DWG-STA-<br>AR-3522   | General Station Typical Detail<br>Escalator  | Aluminium Ribbed Wall Panels are shown in the drawing no.<br>NSRP-DWG-STA-AR-3522, however, there is no detail of this<br>item. Therefore, please provide the detailed drawings for this<br>item.   | Details to b<br>3502 rev. 2 |

rior walls, please use (WF9)- 4MM THK NUM COMPOSITE MATERIAL (ACM) WITH CATALYST & FEVE/PVDF INYLIDENE DIFLUORIDE) COATING AND AL FIBER CORE (FIRE RATED). Is to be updated in Addendum 3 WG-SPO-AR-3569, NSRP-DWG-SPO-AR-21.3

be added to sheet no. NSRP-DWG-STA-AR-21.3. Drawings to be issued in Addendum 3

be added to sheet no. NSRP-DWG-STA-AR-21.3. Drawings to be issued in Addendum 3


| Packages | Vol | Sec   | Page No. | Clause No./Title   | Reference Text<br>(if necessary)                             | Clarification<br>Request  |  |
|----------|-----|---|----------|--|--|---|--|
| S-05     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities | -        | BOQ No.4-1 San<br>Pedro Station<br>BOQ No.4-2 Pacita<br>Station<br>BOQ No.4-3 Binan<br>Station.<br>BOQ No.4-4 Rosa<br>Station  | 530(3) - WF7 Wall: 12mm Heat<br>Strengthened Laminated Glass | There is no detail for item 530(3) - WF7 Wall: 12mm Heat<br>Strengthened Laminated Glass. Therefore, please provide the<br>detailed drawings for this item.   | Finishing s<br>to WF4, 12.<br>WITH SEC<br>Addendum<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>NSRP-DW<br>For Tempe<br>STA-AR-35 |
| S-05     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities | -        | BOQ no. 6-1 for<br>Substation 10<br>BOQ no. 6-2 for<br>Substation 11<br>BOQ no. 6-3 for<br>Substation 12<br>BOQ no. 6-3 for<br>Substation 13<br>BOQ no. 6-3 for<br>Substation 14<br>NSRP-DWG-SS10<br>AR-3101<br>NSRP-DWG-SS12<br>AR-3101<br>NSRP-DWG-SS13<br>AR-3101<br>NSRP-DWG-SS14<br>AR-3101 | Substation SS14 -Architectural Floor<br>Plan and Section     | As indicated in the BOQ no. 6-1 for Substation 7, no. 6-2 for<br>Substation 8 and no. 6-3 for Substation 9, Item No. 619(17) is<br>identified to be a portable toilet, whereas the drawing no. NSRP-<br>DWG-SS10-AR-3101, NSRP-DWG-SS11-AR-3101, NSRP-<br>DWG-SS12-AR-3101, NSRP-DWG-SS13-AR-3101, and<br>NSRP-DWG-SS14-AR-3101 show a permanent toilet. It is<br>obvious that there is a discrepancy between the BOQ and the<br>drawings. Therefore, please confirm which one is the correct one<br>and provide its details. | Toilet for a<br>Please refe  |

#### **Final Response**

g schedule will be revised. WF7 to be changed 12MM THK. TEMPERED GLASS PANELS ECURITY FILM. Drawings to be revised in m 3: WG-SPO-AR-3033 WG-SPO-AR-3034 WG-PTA-AR-3035 WG-PTA-AR-3034 WG-PTA-AR-3035 WG-BIN-AR-3033 WG-BIN-AR-3034 WG-BIN-AR-3035 rev 21.3 pered glass detail, please refer to NSRP-DWG-3504 rev 21.3 in Addendum 3

all Substations shall be permanent toilet. fer to the latest BOQ issued in Addendum 2

| Packages | Vol | Sec  | Page No. | Clause No./Title   | Reference Text<br>(if necessary)  | Clarification<br>Request   |                                      |
|----------|-----|--|----------|--|---|--|--------------------------------------|
| S-05     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities  | -        | BOQ no. 6-1 for<br>Substation 10<br>BOQ no. 6-2 for<br>Substation 11<br>BOQ no. 6-3 for<br>Substation 12<br>BOQ no. 6-3 for<br>Substation 13<br>BOQ no. 6-3 for<br>Substation 14 | S555(1) Door Sign and S555(2)<br>Building Sign  | Item No. S555(1) Door Sign and S555(2) Building Sign are<br>shown in the BOQ no. 6-1 for Substation 10, no. 6-2 for<br>Substation 11, no. 6-2 for Substation 12, no. 6-2 for Substation<br>13 and no. 6-3 for Substation 14. However, there is no detail<br>shown in the drawing. Therefore, please provide us detailed<br>drawing for price estimation purpose. | Drawing w                            |
| S-06     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities  | -        | BOQ No.4-1<br>Cabuyao Station<br>BOQ No.4-2<br>Banlic Station<br>BOQ No.4-3<br>Calamba Station.  | 506(6)C - W=100mm, Stainless Steel<br>Tile Border<br>506(6) - B8; W=200mm Stainless<br>Steel Thresholds<br>506(8) - B3 ; H=150mm, Stainless<br>Steel Baseboard<br>506(24) - H=500mm, Stainless Steel<br>Baseboard for Elevator Wall | There is no detailed drawing for the following items:<br>506(6)C - W=100mm, Stainless Steel Tile Border<br>506(6) - B8; W=200mm Stainless Steel Thresholds<br>506(8) - B3 ; H=150mm, Stainless Steel Baseboard<br>506(24) - H=500mm, Stainless Steel Baseboard for Elevator<br>Wall<br>Please provide detail for those mentioned items.                          | Details to b<br>3502 rev. 2          |
| S-06     | 2   | Volume 2 -<br>Book 2<br>(Architectural)-<br>Package CP S-<br>06: General<br>Station<br>Architectural<br>Drawings | -        | AR-3522  | General Station Typical Detail<br>Escalator   | Aluminium Ribbed Wall Panels are shown in the drawing no.<br>NSRP-DWG-STA-AR-3522, however, there is no detail of this<br>item. Therefore, please provide the detailed drawing for this item.  | Aluminum<br>Drawing to<br>AR-3522 re |
| S-06     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities  | -        | BOQ No.4-1<br>Cabuyao Station<br>BOQ No.4-2<br>Banlic Station<br>BOQ No.4-3<br>Calamba Station.  | 530(3) - WF7 Wall: 12mm Heat<br>Strengthened Laminated Glass  | There is no detail for item 530(3) - WF7 Wall: 12mm Heat<br>Strengthened Laminated Glass. Therefore, please provide the<br>detailed drawing for this item.   | For WF7 i<br>added. For<br>DWG-STA   |



7 it will be changed to WF4, with detail to be For Tempered glass, detail please refer to NSRP-TA-AR-3504 rev 21.3 issued in Addendum 3

| Packages | Vol | Sec   | Page No.               | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request  |   |
|----------|-----|---|------------------------|---|--|---|---|
| S-06     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities | -                      | AR-3101<br>NSRP-DWG-SS17-<br>AR-3101  | Plan and Section<br>Substation SS16 -Architectural Floor<br>Plan and Section<br>Substation SS17 -Architectural Floor<br>Plan and Section<br>Substation SS18 -Architectural Floor<br>Plan and Section | As indicated in the BOQ no. 6-1 for Substation 7, no. 6-2 for<br>Substation 8 and no. 6-3 for Substation 9, Item No. 619(17) is<br>identified to be a portable toilet, whereas the drawing no. NSRP-<br>DWG-SS10-AR-3101, NSRP-DWG-SS11-AR-3101, NSRP-<br>DWG-SS12-AR-3101, NSRP-DWG-SS13-AR-3101, and<br>NSRP-DWG-SS14-AR-3101 show a permanent toilet. It is<br>obvious that there is a discrepancy between the BOQ and the<br>drawings. Therefore, please confirm which one is the correct one<br>and provide its details. | Toilet for a<br>Please refe<br>Reference<br>NSRP-DW<br>NSRP-DW<br>rev. 21 dat |
| S-06     | 1   | Volume 1 Part<br>IA section 4A<br>Bill of<br>Quantities | -                      | NSRP-DWG-SS18-<br>AR-3101<br>BOQ no. 6-1 for<br>Substation 15<br>BOQ no. 6-2 for<br>Substation 16<br>BOQ no. 6-3 for<br>Substation 17<br>BOQ no. 6-3 for<br>Substation 18 | S555(1) Door Sign and S555(2)<br>Building Sign   | Item No. S555(1) Door Sign and S555(2) Building Sign are<br>shown in the BOQ no. 6-1 for Substation 10, no. 6-2 for<br>Substation 11, no. 6-2 for Substation 12, no. 6-2 for Substation<br>13 and no. 6-3 for Substation 14. However, there is no detail<br>shown in the drawing. Therefore, please provide the detailed<br>drawing for this item.  | New drawin<br>provided. L   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                | CAB-ST-4151            | -   | -  | Please provide sectional drawing for CS30 indicating<br>reinforcement details in order for us to evaluate the rebars<br>accordingly.  | CS30 detail<br>ST-4151 Rd   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                | BAN-ST-<br>4431 & 4448 | -   | -  | Slab rebar schedule of CS30 (DWG-BAN-ST-4431) differ in the detail drawing (DWG-BAN-ST-4448). Please advise which one to follow.  | Details on I<br>Details on I<br>as rev 21.3                                   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                | SS00-AR-<br>3021       | -   | Cement Mortar topping wire mesh  | As per the drawings, the Slope to drain cement mortar topping<br>wire mesh is applied on the roof. However the same is not<br>measured in the BOQ.<br>$\rightarrow$ Kindly provide the item and quantity with specification.  | BOQ will b  |
| S-06     | 1A  | Volume 1A &<br>Section 4A                               | Bill No 6              | Item 412  | CHB Wall, Non-Load Bearing, (incl.<br>Reinforcing Steel); t=150mm  | As per the drawing, all CHB wall thickness are 200mm.<br>However, the BOQ shows 150mm THK CHB wall.<br>→Please kindly provide us the location and proper drawings   | The 200 m<br>plastering o<br>thk CHB w  |

#### **Final Response**

all Substations shall be permanent toilet. fer to the BOQ dated in Addendum 2

e dwgs: WG-PSS15/16/17/18-PL-6611; WG-PSS15/16/17/18-SN-6112; and ated September 2020.

ving and new sheet no. for signage to be Drawings will be issued in Addendum 3

ails to be provided on sheet NSRP-DWG-CAB-Rev 21.3 to be issued in Addendum 3

n NSRP-DWG-BAN-ST-4448 will be used. n NSRP-DWG-BAN-ST-4431 will be updated 3 and issued in Addendum 3

be revised and issued in Addendum 3

mm thickness of the wall considers the g on both sides of the wall, thus, the 150 mm wall will be used.

| Packages | Vol | Sec  | Page No.                      | Clause No./Title         | Reference Text<br>(if necessary) | Clarification<br>Request   |  |
|----------|-----|--|-------------------------------|--------------------------|----------------------------------|--|--|
| S-06     | 1A  | Volume 1A &<br>Section 4A  | Bill No 6                     | Item 526(1,2,3,4)        | Doors                            | As per the revised BOQ, There are 4 nos of Doors (D1, D2, D3, D4), However, the drawings shows D2 door only.<br>→Please kindly provide us the location and revised drawings  | NSRP-DW<br>D3 & D4 w   |
| S-06     | -   | CP S04-07<br>Responses to<br>Clarificatioan<br>Requests<br>(Batch 3) | 3 of 12                       | BOQ No 6-1, 6-2<br>& 6-4 | -                                | As per the reponses, the substation 15, 16 & 18 are the same dimensions and quantities. However, the revised BOQ of Addendum no1 is different quantities. $\rightarrow$ Kindly clarify it.                                     | Yes, the tot<br>different fr<br>developmen<br>works of eq<br>refer to late |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                             | SS00-AR-<br>3021              | -                        | 300mm<br>High Zocallo            | As per the drawings, the 300mm high Zocallo is installed under<br>the CHB wall.<br>$\rightarrow$ Kindly confirm that the same item with quantity is included in<br>BOQ.  | Zocalo und<br>quantity an  |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                             | CAB-ST-4503<br>(Version 21.1) | -                        | -                                | The detail C is the reference for ST-4161 but the same detail is not show in ST-4161.<br>$\rightarrow$ Kindly advise it.   | The target s<br>NSRP-DW<br>in Addendu                                      |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                             | BAN-AR-<br>3202               | -                        | NORTHWEST ELEVATION              | $\rightarrow$ Kindly clarify whether the fixed glass louver is required since the same is not shown other drawings and BOQ.  | No fixed gl<br>3202 will b   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                             | BAN-AR-<br>3202               | -                        | SOUTHEAST ELEVATION              | There is no relevant drawings for Loading Dock.<br>→ Kindly provide the drawings / specification / BOQ.  | 1.) For rub<br>STA-AR-35<br>Addendum<br>2.) BOQ w<br>in Addendu            |
| S-06     | 1A  | Volume 1A &<br>Section 4A  | Bill No 4                     | -                        | Item No 564(6)a: PWD Curb Ramp   | This item (PWD Curb Ramp) is provided the unit as ea.<br>→ Does the bidder should consider the same as per Drawing for<br>PWD RAMP ENTRANCE?<br>→ Kindly provide the details drawings and breakdown for work<br>consideration. | For PWD (<br>to the follow<br>Cabuyao S<br>Banlic Sta<br>Calamba S         |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                             | BAN-AR-<br>3515 to 3517       | -                        | GROUND LEVEL<br>DETAILED PLAN    | There is shown seating area under covered walkway.<br>→ Kindly clarify whether the same is under bidder's scope. If<br>yes, please provide the BOQ and details.  | 1.) This is a<br>Works, 564<br>0.40mH).<br>2.) NSRP-J<br>AR-3623 w         |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                             | STA-AR-<br>3582               | -                        | WOMENS HELP<br>DESK PLAN         | <ul> <li>Ref. drawing shows the wall (partition) but it is not specified the wall type.</li> <li>→ Kindly provide the wall type and details</li> <li>→ If the BOQ is not provided, please provide it.</li> </ul>               | Details on S<br>will be issue  |

#### **Final Response**

WG-SS00-AR-3005 will be revised to add D1, with rev 21.3 in Addendum 3

otal quantities for the said 3 substations are from each other since these have different site ent plans. These differ as to the structural equipment pads, perimeter fence, etc. Please atest submitted BOQ issued in Addendum 2

nder the CHB wall is already included in the and cost of CHB Walls.

et sheet of Detail C is CAB-ST-4166. Sheet WG-CAB-ST-4503 to be updated as Rev. 21.3 dum 3

glass louver (delete). NSRP-DWG-BAN-ARbe revised and issued in Addendum 3

*ubber buffer at loading dock, NSRP-DWG-*3556 to be revised as Rev. 21.3 and issued in m 3 will be updated as per the drawings and issued

will be updated as per the drawings and issued lum 3

Curb Ramp Details of CP S-06 Stations, refer lowing drawing sheets: Sta: NSRP-DWG-CAB-CW-1802 Rev 21; ta: NSRP-DWG-BAN-CW- 1802 Rev 21; and Sta: NSRP-DWG-CW-1802 Rev 21.

s already included in BOQ Bill 4 External 54(25) - Concrete Bench ( 3.0mL x 1.05mW x

P-DWG-BAN-AR-3621 and NSRP-DWG-BANwill be revised as rev. 21.3 in Addendum 3

n Sheet NSRP-DWG-STA-AR-3582 rev 21.3 wued in Addendum 3

|          | <u>CP S04-07 Responses to Clarification Requests (Batch 8)</u> |  |  |                  |   |   |   |  |  |  |  |
|----------|--|--|--|------------------|---|---|---|--|--|--|--|
| Packages | Vol  | Sec                                      | Page No.   | Clause No./Title | Reference Text<br>(if necessary)  | Clarification<br>Request  | Final Response  |  |  |  |  |
| S-06     | 1A   | Volume 1A &<br>Section 4A                | Bill No 6  | Item 128(4)      | Fencing (CHB t=150mm x 2500mm<br>high)                                      | There is Fencing (CHB t=150mm x 2500mm high) in the BOQ.<br>However, there is no CHB 150mm THK wall in the drawings.<br>$\rightarrow$ Kindly provide the Fencing location and details   | 1.) BOQ will be revised and issued in Addendum 3<br>2.) Please refer to NSRP-DWG-SS00-AR-3103<br>(Perimeter Fence Detail).  |  |  |  |  |
| S-06     | 2  | Volume 2 &<br>Section 6<br>(II Drawings) | SS15-ST-<br>4201<br>SS16-ST-<br>4201<br>SS17-ST-<br>4201 | -                | Slab girder   | As per the substation toilet structure drawing, there are girders on the end of slab.<br>$\rightarrow$ Please provide the detail drawings.  | There are no girders at ground level. Plan shows the thickened ends of the slab on fill.  |  |  |  |  |
| S-06     | 1A   | Volume 1A &<br>Section 4A                | Bill No 6  | Item 505(4)      | Floor Finishes - Self-Levelling Epoxy<br>Paint with Hardener                | As per schedule and plans there are two types of floor finishes.<br>Epoxy Coating for Meeting Room and Anti-Static Vinyl Sheet<br>for Equipment Room.<br>→ Kindly clarify or provide updated Architectural drawings for<br>Substation.  | Only epoxy coating finish on both Meeting &<br>Equipment rooms. Refer to Substation schedule of<br>Finishes NSRP-DWG-SS00-AR-3005. Drawings will be<br>revised and issued as rev 21.3 in Addendum 3.  |  |  |  |  |
| S-06     | 1A   | Volume 1A &<br>Section 4A                | Bill No 6  | Item S547(8)     | Wall Finishes - High-Performance<br>Urethane Coatings (Masonry<br>Painting) | As per schedule there are different types of wall finishes that is already in Item S548(1), S548(2) and S548(12). $\rightarrow$ Kindly clarify it.  | The finishes for PINS S548(1), S548(2), & S548(12) are<br>indicated in NSRP-DWG-SS00-AR-3005 21 Sept. 2020<br>rev. 21.<br>S548(1) - 12mm thk. Gypsum Board on Light Metal<br>Frame; Painted Finish for Meeting Rooms.<br>S548(2) - Solvent-based type Paint Finish for<br>Equipment Rooms.<br>S548(12) - Water-based Elastomeric Paint (Coating for<br>Exterior Wall) for Exterior Walls. |  |  |  |  |
| S-06     | 1A   | Volume 1A &<br>Section 4A                | Bill No 6  | Item S555(1-2)   | Other Finishing Works - Door & Bldg<br>Sign                                 | Not shown in the drawings. $\rightarrow$ Kindly verify it.  | New drawing and sheet number to be added for signage details. Drawings will be issued in Addendum 3   |  |  |  |  |
| S-06     | 2  | Volume 2 &<br>Section 6<br>(II Drawings) | CAB-ST-<br>4161, 4502 &<br>4503                          | -                | Reference attachment Page 1 & 2   | Reference drawings to CABUYAO Station (same question<br>applies to all other stations)<br>Frame 7A height 1m. Frame height of Frame 1, h=1m.<br>Rectangular frame.<br>Top view of Frame 7A shows a different arrangement.<br>Seems to have the geometry of half the frame 7<br>→ Kindly clarify the geometry and frame heigh of frame 7A. | <i>Roof details to be reviewed and updated as needed and issued as rev 21.3 in Addendum 3</i>   |  |  |  |  |
| S-06     | 2  | Volume 2 &<br>Section 6<br>(II Drawings) | CAB-ST-<br>4501, 4502 &<br>4503                          | -                | Reference attachment Page 3 & 4   | Reference drawings to CABUYAO Station (same question<br>applies to all other stations)<br>Frame 7 height 1.803m. Frame height of Frame 2, h=1m.<br>→ Kindly clarify the frame heigh of frame 7.   | <b>Roof details to be reviewed and updated as needed and issued as rev 21.3 in Addendum 3</b>   |  |  |  |  |
| S-06     | 2  | Volume 2 &<br>Section 6<br>(II Drawings) | CAB-ST-<br>4501, 4502 &<br>4503                          | -                | <u>Reference attachment Page 5 &amp; 6</u>                                  | Reference drawings to CABUYAO Station (same question<br>applies to all other stations)<br>Frame 8 height 1.803m. Frame height of Frame 3, h=1m.<br>→ Kindly clarify the frame heigh of frame 8.   | <i>Roof details to be reviewed and updated as needed and issued as rev 21.3 in Addendum 3</i>   |  |  |  |  |

| Packages | Vol | Sec  | Page No.                           | Clause No./Title | Reference Text<br>(if necessary)               | Clarification<br>Request  |   |
|----------|-----|--|------------------------------------|------------------|--|---|---|
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | CAB-ST-4501<br>& 4503              | -                | Reference attachment Page 7                    | Reference drawings to CABUYAO Station (same question applies to all other stations)         Dashed line indicates triangular part of frame 3 (H=1m). Frame has a height of H=1.803M         → Kindly clarify the frame heigh of frame 8.  | Roof details to<br>issued as rev 2              |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | CAB-ST-4501<br>& 4211              | -                | Reference attachment Page 8 & 9                | Reference drawings to CABUYAO Station (same question  |   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | CAB-AR-<br>3564 Rev21.1            | -                | Cabuyao Station Windows Type<br>W18, W19 & W20 | Windows Type W18, W19 & W20 are indicated detail drawing<br>and layout plan (CAB-AR-3611 & 3564 Rev.21) but not noted<br>schedule of windows drawing CAB AP 3563 Rev.21 and BOO   |   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | CAB-AR-<br>3568                    | -                | Cabuyao Station Louver Type L20,<br>21         | Louver type L20 & 21 are indicated in Schedule of Louvers<br>Sheet 2, but not measured the BOQ.<br>$\rightarrow$ Kindly provide the BOQ.  | BOQ will be r                                   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | CAB-AR-<br>3568                    | -                | Cabuyao Station Louver Type L21                | → Please confirm that the Louver for Janitors room is Louver type 21.<br>→ If yes, please modify the same drawing.  | Louver Tag in<br>and issued in .                |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | BAN-AR-<br>3563. Rev21.1           | -                | Banlic Station Window Type W17                 | There is a discrepancy (Window Size) between BOQ and drawing.<br>→ Kindly advise it.  | W17 was alred<br>drawing (NSR<br>refer to BOQ i |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | BAN-AR-<br>3561 & 3562.<br>Rev21.1 | -                | Banlic Station SHUTTER SH4                     | Between Schedule of doors sheet 1 & sheet2, the size for SH4 is the difference.<br>$\rightarrow$ Kindly advise it.  | These are the<br>3000 mm (H).                   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(II Drawings)                   | BAN-AR-<br>3561 & 3562.<br>Rev21.1 | -                | Banlic Station SHUTTER SH6                     | Shutter type SH6 is deleted in the drawing (BAN-AR-3562), but<br>it is provided in BOQ and BAN-AR-3561.<br>$\rightarrow$ Kindly advise it.  | SH6 was alrea<br>Addendum 2                     |
| S-06     | 1A  | Volume 1A &<br>Section 4A                                  | Bill no 4                          | -                | Item 554(20): Water Dispenser                  | As per Revised BOQ (Rev_T.A. 2b), the water dispenser is<br>measured as new item.<br>$\rightarrow$ Kindly provide the setting location, drawings and<br>specification.  |   |
| S-06     | 2   | Volume 2 &<br>Section 6<br>(IC-Technical<br>Specification) | -                                  | -                | Extra Material / Spare Material                | As per Technical Specification (TS 500), some items (i.e<br>Acoustic Ceiling, Tile, Resilient Flooring, etc.) are requiring<br>Extra Material or Spare Material. While the same has been<br>specified that spare materials should be in accordance with<br>requirements of the Contract or Contract Document.<br>$\rightarrow$ Kindly provide section article/paragraph in conditions of<br>contract showing all the information for the spare materials. |   |

| Final Response  |     |
|---|-----|
| iils to be reviewed and updated as needed and<br>rev 21.3 in Addendum 3 | d   |
| ils to be reviewed and updated as needed an<br>rev 21.3 in Addendum 3   | d   |
| OQ is updated as per latest drawing NSRP-                               |     |
| B-AR-3563 rev. 21.2. Please refer to latest                             |     |
| Addendum 2  |     |
| W19 and W20 were marked as deleted on Dv                                | vg. |
| P-DWG-CAB-AR-3564 rev 21.2 and not show                                 | vn  |
| ws layout dwg. no. NSRP-DWG-CAB-AR-                                     |     |
| 21.2.   |     |

Cag in NSRP-DWG-CAB-AR-3568 to be reviseded in Addendum 3

already updated as per latest submitted (NSRP-DWG-BAN-AR-3564 rev. 21.1). Please BOQ issued in Addendum 2

e the same: SH4 dimension is 3600 mm (W) x (H).

already deleted. Please refer to BOQ issued in m 2

drawings, and specifications will be revised d in Addendum 3

extra materials shall be 5% of the original indicated in the BOQ. This percentage exclude is during installation. Section 538 of TS-500 vised and issued in Addendum 3

| Packages | Vol | Sec  | Page No.                       | Clause No./Title  | Reference Text<br>(if necessary) | Clarification<br>Request   |   |
|----------|-----|--|--------------------------------|---|----------------------------------|--|---|
| S-06     | 1A  | Volume 1A.<br>Part I Section<br>4A   | BOQ No.5<br>PART C             | -   | -                                | Refer to the BOQ No.5, Part C, 111(80)a~111(82)b,<br>Maintenance Access Cover, the unit is "set". Please clarify the<br>location and details of Maintenance Access Cover.                                  | For the deta<br>VIA00-130   |
| S-06     | 2   | Volume 2.<br>Part II Section<br>6. II Drawings                                   | NSRP-DWG-<br>VIA00-DR-<br>1405 | -   | -                                | Please clarify headwall, endwall and retaining wall in Outfall<br>should be considered in BOQ No.5 Part B, 206(8)d or in BOQ<br>No.2,Part C, 206(9)d.  | No, it shou<br>Outfall Typ  |
| S-06     | 2   | Volume 2,<br>Book1(Civil),<br>14_CP S-<br>06_Maintenac<br>e<br>Road,Drawing<br>s | -                              | NSRP-DWG-<br>VIA06-RD-2014                                | -                                | Refer to the dwg No.NSRP-DWG-VIA06-RD-2014, We can't<br>find the strength of concrete of retaining wall type-1 and type-2.<br>We wonder if the strength of concrete is 28Mpa or 40Mpa.<br>Please, clarify. | Update reta<br>issued as R<br>RD-2014 R<br>and refer to<br>requiremen |
| S-06     | 2   | _ `  |                                | NSRP-DWG-<br>VIA00-ST-1001                                | -                                | Refer to the dwg No.NSRP-DWG-VIA00-ST-1001, we should<br>refer to dwg No.NSRP-DWG-ST-1003 to check the segment<br>reinforcement. But we can't find that drawing(No.NSRP-DWG-<br>ST-1003). Please, clarify. | Additional<br>VIA00-ST-   |
| S-04     | 3   | Volume 3-<br>Section 8   | PCC7                           | KD 03-1 Receiving<br>Substations (S10<br>S11 S12 S13 S14) | -                                | Please confirm the minimum requirement to achieve this key<br>date. Does it include the building beside substation (i.e.<br>Rectifier)?  | Yes, ready j  |

#### **Final Response**

letail and location, please refer to NSRP-DWG-305 rev 21


ould be included in the cost of Drainage Sype 4, Part C Bill No. 5.

etaining wall layout, profile and details were Rev 21.2 Refer to sheet NSRP-DWG-VIA06-Rev 21.2 for updated retaining wall details to notes for compressive strength ents.

al sheet referring to Section 5 in NSRP-DWG-T-1003 shall be added.

y for receiving permanent electricity supply.

|          | <u>er sor or Responses to Charmenton Requests (Daten o)</u> |  |                                |   |                                  |   |  |  |
|----------|---|--|--------------------------------|---|----------------------------------|---|--|--|
| Packages | Vol   | Sec  | Page No.                       | Clause No./Title  | Reference Text<br>(if necessary) | Clarification<br>Request  |  |  |
| S-04     | 3   | Volume 3-<br>Section 8                             | PCC7                           | KD 02-1 Complete<br>a minimum and<br>continuous length<br>of 3,000<br>metres on the<br>viaduct where it<br>passes through at<br>least<br>one of the stations<br>KD 02-2 Complete<br>a minimum and<br>continuous length<br>of 6,000<br>metres within any<br>viaduct section<br>KD 02-3<br>Completion of the<br>remaining viaduct<br>sections<br>(approximately<br>2.51 km) | -                                | Please confirm the minimum requirement to achieve this Key<br>Dates. Is it including the Cast-in-Situ Upstand, Parapet or cable<br>trough with cover and protective concrete?   | Yes, the n<br>Dates is i<br>cable troi   |  |
| S-04     | 2   | Volume 2-2.1<br>Book1 (Civil)-<br>CPS-<br>04_VIA00 | NSCR-DWG-<br>VIA00-ST-<br>0321 | Pile details  |                                  | It is stated in drawings NSCR-DWG-VIA00-ST-0321 to ST-0325 that the lenton coupler is marked in the 3m zone are below soffit of pile cap. Please confirm that the location of lenton coupler could be moved to suit our construction/ rebar fixing purposes   | Yes.   |  |
| S-04     | 2   | Volume 2   | -                              | -   | NSCR-DWG-ALA-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Air Ducts<br>PLENUM 2400 x 1600 mm<br>PLENUM 1600 x 1100 mm<br>PLENUM 1200 x 450 mm<br>PLENUM 900 x 600 mm<br>PLENUM 900 x 450 mm<br>PLENUM 900 x 400 mm<br>PLENUM 900 x 300 mm<br>PLENUM 750 x 250 mm<br>PLENUM 750 x 600 mm<br>EAD 850 x 700 mm<br>EAD 300 x 300 mm | Plenum b<br>be includ<br>Please re<br>605.1.1, 1<br>shall incl<br>(b) Duct<br>EAD 850<br>in Adden<br>5608 rev<br>EAD 300<br>plan. Plea |  |



| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request  | Final Response   |
|----------|-----|----------|----------|------------------|----------------------------------|---|--|
| S-04     | 2   | Volume 2 | _        | -                | NSCR-DWG-ALA-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Pressurization Duct System<br>SPAD 800 x 500 mm<br>PLENUM 2000 x 1500 mm  | Plenum boxes are considered as duct fittings and to be<br>included in the rate of the ductworks.<br>Please refer to SCRP-TS 600_Annex A, Sub-Clause<br>605.1.1, Item 1(b), which states that rate of ductworks<br>shall include (among others):<br>(b) Duct fittings and stiffener/s;<br>SPAD 800 x 500 are already included in the BOQ<br>issued in Addendum 2. |
| S-04     | 2   | Volume 2 | _        | -                | NSCR-DWG-ALA-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>AC Grilles & Diffuser<br>2100 x600 EAG<br>1900X600 EAG<br>1650X600 EAG<br>1950X1950 SAG<br>450x450 SAG<br>400X400 SAG<br>350X350 SAG<br>300X300 SAG<br>200X200 SAG<br>150X150 SAG | AC Grilles & Diffusers<br>2100 x600 EAG<br>1900X600 EAG<br>1650X600 EAG<br>1950X1950 SAG<br>450x450 SAG<br>400X400 SAG<br>350X350 SAG<br>300X300 SAG<br>200X200 SAG &<br>150X150 SAG are already included in the BOQ issued<br>in Addendum 2   |
| S-04     | 2   | Volume 2 | -        | -                |                                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Motorized Damper<br>1500X500 MD<br>Fire Dampers<br>3000X2150 FD<br>3000X1350 FD<br>3000X1250 FD<br>1300X1300 FD<br>900X400 FD<br>800X60 FD  | Fire Damper<br>3000x2150 FD<br>3000x1350 FD<br>3000x1250 FD &<br>900x400 FD are already included in the BOQ issued in<br>Addendum 2<br>1500x500 MD,<br>1300x1300 FD &<br>800x60 FD are not shown in plan. Please provide the<br>drawings/location of the items.  |
| S-04     | 2   | Volume 2 | -        | -                | NSCR-DWG-ALA-ME                  |   | <b>SEF-01 &amp; PF-01</b> were already included in the <b>BOQ</b> issued in Addendum 2   |

|          | <u>CP S04-07 Responses to Clarification Requests (Batch 8)</u> |          |          |                  |                                  |   |  |  |  |  |
|----------|--|----------|----------|------------------|----------------------------------|---|--|--|--|--|
| Packages | Vol  | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request  | Final Response   |  |  |  |
| S-04     | 2  | Volume 2 | -        | -                | TS-600 Sec 611.1.4 and 635.1.2   | Please confirm what will govern on Warranty Period Standard 1<br>year Defects and Liability Period (DLP) or Tech Specifications<br>per Sec 611.1.4 Air Cooled Split Type Air Conditioning Unit<br>Warranty Period is 5 years while on Sec 635.1.2 Fan Coil Unit<br>Warranty Period is 10 years. | Technical Specifications (TS) will govern.   |  |  |  |
| S-04     | 2  | Volume 2 | -        | -                | NSCR-DWG-MUN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Air Ducts<br>PLENUM 3100 x 1500<br>PLENUM 2600 x 1500<br>PLENUM 1500 x 1300<br>Smoke Exhaust Duct<br>1350x450 SED<br>950x400 SED<br>700x350 SED<br>600x350 SED<br>600x250 SED     | <ul> <li>Plenum boxes are considered as duct fittings and are to be included in the rate of the ductworks.</li> <li>Please refer to SCRP-TS 600_Annex A, Sub-Clause 605.1.1, Item 1(b), which states that rate of ductworks shall include (among others):</li> <li>(b) Duct fittings and stiffener/s;</li> <li>1350x450 SED, 950x400 SED, 700x350 SED &amp; 600x250 SED were already included in the BOQ issued in Addendum 2</li> <li>600x350 SED is not shown in plan. Please provide the drawings/location of the items.</li> </ul> |  |  |  |
| S-04     | 2  | Volume 2 | -        | -                | NSCR-DWG-MUN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Pressurization Duct System<br>SPAD 950 x 800<br>PLENUM 2500 x 2200 mm   | <ul> <li>Plenum boxes are considered as duct fittings and are to be included in the rate of the ductworks.</li> <li>Please refer to SCRP-TS 600_Annex A, Sub-Clause 605.1.1, Item 1(b), which states that rate of ductworks shall include (among others):</li> <li>(b) Duct fittings and stiffener/s;</li> <li>SPAD 950 x 800 are already included in the BOQ issued in Addendum 2</li> </ul>  |  |  |  |
| S-04     | 2  | Volume 2 | -        | -                | NSCR-DWG-MUN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ.<br>Motorized Damper<br>900x400 MD<br>1500x500 MD<br>Fire Dampers<br>3000X2150 FD<br>3000X1350 FD<br>3000X1250 FD<br>1300X1300 FD<br>900X300 FD<br>250x250 FD<br>150Ø FD  | 1500x500 MD<br>900x300 FD<br>250x250 FD<br>were already included in the BOQ issued in Addendum<br>2<br>900x400 MD<br>3000x2150 FD<br>3000x1350 FD<br>3000x1250 FD<br>1300x1300 FD<br>1500 FD are not shown in plan. Please provide the<br>drawings/location of the items.  |  |  |  |

| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary)               | Clarification<br>Request  |  |
|----------|-----|----------|----------|------------------|--|---|--|
| S-04     | 2   | Volume 2 | -        | -                | NSCR-DWG-MUN-ME                                | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Air Grilles<br>1200x600<br>2000x2000  | Air Grilles<br>1200x600<br>2000x200<br>were alrea<br>2   |
| S-04     | 2   | Volume 2 | -        | -                | NSCR-DWG-MUN-ME                                | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Fans & AC Equipment<br>SEF-01: Axial Inline Type Smoke Exhaust Fan for Unventilated<br>Area at Concourse Level, Airflow: 6335 L/S and Static Pressure<br>of 250PA - (5 UNITS)<br>PF-01 : Stair Pressurization - (4 UNITS) | SEF-01 &<br>issued in A  |
| S-04     | 2   | Volume 2 | -        | -                | NSCR-DWG-ALA-FS-6612, NSCR-<br>DWG-MUN-FS-6612 | Water Tank Piping is 100 mm according Pump Room Layout but<br>there is no 100 mm Pipe in the BOQ. May we add these as Line<br>Items under Sundries?   | Pipe Syster<br>the rate of<br>Please ref<br>617.1.1, Ita<br>shall inclu<br>(c) Pipes,  |
| S-04     | 2   | Volume 2 | -        | -                | NSCR-DWG-ALA-FS-6612, NSCR-<br>DWG-MUN-FS-6612 | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Control Valve<br>Pressure Gauge<br>Gate Valve OS&Y<br>Check Valve<br>Test Valves<br>May we add these items under Sundries?  | Valves and<br>are to be in<br>Please ref<br>632.1.1, Ita<br>Tanks & P<br>1(c) Pipes<br>2(b) Pipe j<br>valves; and<br>2(d) Pipin<br>with tempe<br>discharge j |
| S-04     | 2   | Volume 2 | -        | -                | NSCR-DWG-ALA-FS-6618, NSCR-<br>DWG-MUN-FS-6608 | The Fire Department Connection and Test Header Connection<br>are not included in the BOQ. May we add these are additional<br>line items under Sundries?   | Fire Depar<br>Connection<br>Hose Syste   |
| S-04     | 2   | Volume 2 | -        | -                | NSCR-DWG-ALA-PL<br>NSCR-DWG-MUN-PL             | According to Drawings and Equipment Schedule, there are 12<br>Water Heaters in ALA and 1 in MUN. BOQ only reflects 6 in<br>ALA and 0 in MUN.  | Quantity of<br>already co  |

### **Final Response**

es 00 000

eady included in the BOQ issued in Addendum

& PF-01 were already included in the BOQ Addendum 2

tem for the Water Tanks are to be included in of the **Pumps**.

efer to SCRP-TS 600\_Annex A, Sub-Clause Items 1(c), which states that rate of Pumps lude (among others):

s, including fittings and accessories.

nd Accessories for the Water Tanks and pumps included in the rate of the Tanks & Pumps.

efer to SCRP-TS 600\_Annex A, Sub-Clause Items 1(c), 2(b) & 2(d) which states that rate of Pumps shall include (among others):

es, including fittings and accessories; e fittings and accessories, including gate and

ing from fire water tank unto Isolation Valve per switch and from Test Valve Manifold valve re pipe joint of fire pump assembly.

partment Connection and Test Header ion is the same as item 630(8) Stand Pipe and stem.

of Water Heaters in ALA and MUN were corrected in the BOQ issued in Addendum 2

| Packages | Vol | Sec      | Page No.  | Clause No./Title             | Reference Text<br>(if necessary)  | Clarification<br>Request   |  |
|----------|-----|----------|---|------------------------------|---|--|--|
| S-04     | 2   | Volume 2 | -   | -                            | NSCR-DWG-ALA-PL<br>NSCR-DWG-MUN-PL  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Sanitary Works<br>Floor Drain, 50mm<br>Canopy Drain, 100mm<br>Floor Cleanout, 100mm<br>Floor Cleanout, 80mm<br>Floor Cleanout, 80mm<br>Ground Cleanout, 50mm<br>Ground Cleanout, 250mm<br>Ceiling Cleanout, 100mm<br>Ceiling Cleanout, 100mm<br>Ceiling Cleanout, 40mm<br>Ceiling Cleanout, 32mm<br>Ceiling Cleanout, 25mm | 50mm Floo<br>issued in A<br>100mm Ca<br>provide the<br>Cleanouts<br>included in<br>Please refe<br>607.1.1, wh<br>include Pip<br>pipe, includ<br>and installa |
| S-04     | 2   | Volume 2 | -   | -                            | NSCR-DWG-ALA-PL<br>NSCR-DWG-MUN-PL  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Waste Water Pipe 75 mm<br>Vent Pipe 75 mm<br>Stainless Rain Water Pipe 250 mm  | 75 mm dian<br>75 mm dia<br>250 mm di<br>already inc  |
| S-04     | 2   | Volume 2 | -   | -                            | NSCR-DWG-ALA-PL<br>NSCR-DWG-MUN-PL  | Please clarify the type of Waste Water Treatment Plant to be<br>used, if a specific type is required   | No specific<br>requiremen  |
| S-04     | 2   | Volume 2 | NSCR-DWG-<br>ALA-EL-<br>5201 / 02<br>NSCR-DWG-<br>MUN-EL-<br>5201 /02 | -                            | Alabang Station Cable Containment<br>Layout Ground Flr and Concourse<br>Level<br>Muntinlupa Station Cable<br>Containment Layout Ground Flr &<br>Concourse Level | Please confirm the size of Cable tray, in DWG it is 900mm2 but<br>in BOQ it is 600mm2.   | Cable Tray<br>600mm for<br>drawings.<br>Please refe<br>includes pa<br>PIN 707(1)<br>100mm(H).  |
| S-04     | 2   | Volume 2 | -   | Electrical<br>Specifications | Spare Part List   | Please provide Spare part list and no item in BOQ.   | Please refe<br>700_Annex<br>parts and/o<br>Cost of spa<br>in the cost<br>extra stocks  |
| S-04     | 2   | Volume 2 | -   | Static Load Test             | Static Load Test  | Please clarify if the static load test will be done on test piles/sacrificial piles  | Yes, as per<br>piles and S<br>Cross Hole   |

#### **Final Response**

oor Drain are already included on the BOQ Addendum 2

Canopy Drain not shown in plan. Please the drawings/location of the items.

ts are considered as pipe fittings and to be in the rate of the Piping works.

efer to SCRP-TS 600\_Annex A, Sub-Clause which states that rate of Tanks & Pumps shall Pipes, fittings and accessories for each type of uding approved allowance for wastage; supply llation.

ameter Waste Water Pipe liameter Vent Pipe diameter Stainless Rain Water Pipe were ncluded on the BOQ issued in Addendum 2

ic type is required as long as it meets the ents of the specifications.

ay is 900mm for Bill Nos. 4-1, 4-2, & 4-3; and for Bill No. 4-4 in accordance to mentioned

efer to **BOQ** issued in Addendum 2, which pay item as follows:

(1)a --- Cable Tray w/ Cover, 900mm(W) x I).

fer to provisions in the TS 700 and SCRP\_TS ex A for pay items to be provided with spare Vor extra stocks.

pare parts and/or extra stock shall be included at of the pay items requiring spare parts and/or acks as specified in the TS and TS Annex A.

er TS 204.2.6, "..Initial Load Tests for the test Static Load Tests, Integrity Tests as well as le Sonic Logging Tests for all working piles."

| Packages | Vol | Sec   | Page No.   | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request   |  |
|----------|-----|---|--|---|--|--|--|
| S-04     | 2   | Volume 2  | -  | Cross Hole Sonic<br>Logging Test  | Cross Hole Sonic Logging Test  | Please clarify if all bored piles will includes BI Pipes and the<br>owner has the prerogative to which piles to test for cross hole<br>sonic log.  | As per TS 2<br>tube for CS<br>noted, to pe   |
| S-04     | 2   | Volume 2 and<br>the BOQ Bill<br>3 Part B.4        | NSRP-DWG-<br>VIA04-ST-<br>0038 & 0038            | -   | Precast Segmental box Girder with<br>width 11.5m   | There is missing "Fabrication and Erection of Structural Concrete<br>Class 50 MPa for Precast Segmental Box Girder (W=11.5m,<br>H=2.4m)". Please clarify   | BOQ will b   |
| S-04     | 2   | Volume 2 & BOQ Bill 3                             | NSRP-DWG-<br>VIA00-ST-<br>0511                   | -   | Missing item in BOQ for the<br>Removable steel linear grate cover &<br>PTFE bonded to top of restrainer<br>Block | There are missing item in the BOQ in the bill 3 for the removable<br>steel linear grate cover & PTFE Bonded to top of restrainer<br>Block. Please add the item in the BOQ.   | BOQ will b   |
| S-04     | 2   | Volume 2 &<br>BOQ Bill 3<br>Part D item<br>209(5) | NSRP-DWG-<br>VIA00-ST-<br>1321                   | -   | Expansion Joint Assemblies   | With reference to the item 209 (5) part D in bill no 3, there is<br>"expansion Joint assemblies", but No such details could be found<br>in the drawing. However, there are similar details which is<br>Galvanised steel plate & associated anchor bolts in the drawing<br>NSCRP-DWG-VIA00-ST-0511. Please confirm the measurement<br>of the said galvanized steel plate with associated anchor are<br>under the item 219(5). | For item 20<br>DWG-VIA   |
| S-04     | 2   | Volume 2  | NSRP-DWG-<br>VIA00-ST-<br>0402                   | Maximum Concrete<br>placement<br>Temperature                              | Maximum Concrete Placement<br>Temperature should be kept at 24 deg<br>for 40MPa                                  | Please review and confirm the 24 deg concrete is requirement or<br>suggest any other alternative. The concrete delivery to achieve<br>may not be practical due to unforeseen traffic condition and<br>serious traffic jam in most of the time.   | The maxim<br>placing sho<br>should be a<br>mixing plan<br>Contractor<br>TS200 Clan<br>TS200 206.<br>the cooling<br>concreting<br>concrete ex |
| S-04     | 2   | Volume 2  | VIA00-ST-<br>342, NSRP-<br>DWG-VIA00-<br>DR-1301 | Drainage on pile<br>cap   | Drainage cover rebar detail &<br>drainage horizontal bars  | No rebar detail for drainage cover shown in VIA00-ST-342. Can the horizontal bars attached to the column post fix?   | Drainage c<br>referred to  |
| S-04     | 2   | Volume 2  | NSRP-DWG-<br>VIA04-ST-<br>0029                   | Public road access<br>way   | Public road access way   | Road access way intersection - Are we allowed to lessen the<br>public road access way and add mid support for the cast in situ<br>viaduct or as long as LGU approves it and have sufficient width<br>to not hamper traffic flow?   | Yes, your u<br>required to   |
| S-04     | 2   | Volume 2  | NSRP-DWG-<br>VIA00-ST-<br>0402                   | Crack control<br>recommendations<br>for pier column and<br>headstock only | -  | Is crack control recommendation for curing concrete of pier<br>column and headstock by using sealed plastic wrapping and<br>wrapping of thermal blanket are required or we will just follow<br>the water curing stated on 206.13.1 (Technical specification) for<br>Class A and Class P concrete?  | Please follo<br>can propos<br>being subje  |

### **Final Response**

S 204.4.12, the contractor shall install access CSL testing in all bored piles, except otherwise permit access for the CSL test probes.

be revised and issued in Addendum 3

be revised and issued in Addendum 3

209(5), please refer to drawing number NSRP-IA00-ST-1321. 9(5) is not used.

imum temperature of fresh concrete at time of hould be between 26 to 30 degrees C and e achieved through normal precautions at the lant, for working in hot-humid climates. The or shall comply with the recommendations of lause 206.7.8.4 with regard to pre-cooling and 06.7.8.5 and TS200 Clause 206.7.8.5 regarding ng of the concrete. At no stage during the og process should the temperature of the fresh exceed 35 degrees C.

cover drawings as stated in DR-1301, is to in DR-1305.

understanding is correct. The bidder shall be to liaise with concerned authorities.

llow the recommendation unless the contractor ose other equivalent or better control measure ject to Engineer's approval

| Packages | Vol | Sec                    | Page No.                              | Clause No./Title  | Reference Text<br>(if necessary)                   | Clarification<br>Request   |  |
|----------|-----|------------------------|---------------------------------------|---|--|--|--|
| S-04     | 2   | Volume 2               | NSRP-DWG-<br>VIA04-ST-<br>0101 to 105 | Bearing Type 2  | -  | With reference to the Pier Schedule, there is a bearing type 2, but<br>No details were found in the drawings. Please advice.             | No details f<br>2 bearings<br>as per Note<br>0781 Rev 2<br>All Bearing<br>the required<br>submitted to<br>fabrication. |
| S-04     | 2   | Volume 2               | NSRP-DWG-<br>VIA00-ST-<br>0781        | Bearing Type 1  | -  | A type 3 elastomer bearing in table 7 of drawing NSRP-DWG-<br>VIA00-ST-0781 is found. Please confirm where should adopt<br>this details. | Type 3 in th<br>Type 2.<br>In the pier<br>11.5m wide<br>Type 2 app<br>segmental i<br>NSRP-DW<br>Addendum               |
| S-04     | 2   | Volume 2               | NSRP-DWG-<br>CIS70-ST-<br>0103        | Starter bars for<br>track bed at<br>Abutment top slab     | Starter bars for track bed at Abutment<br>top slab | No starter bars for track bed shown on top slab of abutment  | NSRP-DW<br>addendum<br>reinforcem<br>NSRP-DW<br>addendum<br>abutment.  |
| S-05     | 3   | Volume 3-<br>Section 8 | PCC7                                  | KD 03-1 Receiving<br>Substations (S10<br>S11 S12 S13 S14) | -  | Please confirm the minimum requirement to achieve this key<br>date. Does it include the building beside substation (i.e.<br>Rectifier)?  | The require<br>preparation   |

### **Final Response**

s have been provided in the drawings for Type as since the contractor will design the bearings on the #3 indicated in NSRP-DWG-VIA00-ST-21.

ings shall be designed by the contractor as per rements of AASHTO LRFD 2016 and shall be I to the Engineer for approval prior to on.

the drawing shall be revised to Type 1 and


er schedule, Type 1 applies to 10.3m and de precast segmental box girder. pplies to 6.3m and 5.1m wide precast l box girder. WG-VIA00-ST-0781 will be revised in m 3

WG-CIS70-ST-0103 will be revised in m 3 to reflect the starter bars for track slab ment detail on abutment.

WG-CIS70-ST-0101 will be revised in n 3 to reflect the track slab concrete detail on

*irements to achieve Key Date is ready for on works for receiving electricity.* 

| Packages | Vol | Sec                    | Page No. | Clause No./Title  | Reference Text<br>(if necessary) | Clarification<br>Request   |  |
|----------|-----|------------------------|----------|---|----------------------------------|--|--|
| S-05     | 3   | Volume 3-<br>Section 8 | PCC7     | KD 02-1 Complete<br>a minimum and<br>continuous length<br>of 3,000<br>metres on the<br>viaduct where it<br>passes through at<br>least<br>one of the stations<br>KD 02-2 Complete<br>a minimum and<br>continuous length<br>of 6,000<br>metres within any<br>viaduct section<br>KD 02-3<br>Completion of the<br>remaining viaduct<br>sections<br>(approximately<br>2.51 km) | -                                | Please confirm the minimum requirement to achieve this Key<br>Dates. Is it the Cast-in-Situ Upstand, Parapet or the Viaduct<br>Segment Installation? | All works<br>protective                |
| S-05     | 2   | Volume 2               | -        | Cross Hole Sonic<br>Logging Test  | Cross Hole Sonic Logging Test    | Please clarify if all bored piles will includes BI Pipes and the<br>owner has the prerogative to which piles to test for cross hole<br>sonic log.    | As per TS<br>tube for C<br>noted, to j |



| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request  |  |
|----------|-----|----------|----------|------------------|----------------------------------|---|--|
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Air Ducts<br>PLENUM 2800 x 1300 mm<br>PLENUM 1500 x 1000 mm<br>PLENUM 1700 x 700 mm<br>PLENUM 1000 x 700 mm<br>PLENUM 900 x 600 mm<br>PLENUM 900 x 400 mm<br>PLENUM 900 x 300 mm<br>PLENUM 600 x 400 mm<br>PLENUM 750 x 600 mm<br>Smoke Exhaust Ducts<br>PLENUM 4750 x 1500<br>PLENUM 1500 x 1350<br>2200 x 500 SED<br>1000 x 400 SED<br>1200 x 500 SED<br>1700 x 500 SED | Plenum boxes are<br>be included in the<br>Please refer to S0<br>605.1.1, Item 1(b)<br>shall include (am<br>(b) Duct fittings of<br>2200x500 SED, 1<br>1700x500 SED we<br>issued in Addendo |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Pressurization Duct System<br>SPAD 800 x 500 mm<br>PLENUM 2000 x 1500 mm  | "Plenum boxes a<br>to be included in<br>Please refer to S<br>605.1.1, Item 1(b)<br>shall include (am<br>(b) Duct fittings<br>800x500 SPAD is<br>drawings/location                          |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>AC Grilles & Diffuser<br>1850 x 600 EAG<br>600 x 500 EAG<br>400 x 350 EAG<br>2000 x 2000 SAG<br>500 x 500 SAG<br>400 x 350 SAG<br>350 x 350 SAG<br>150 x150 SAG<br>200 X 200 SAG  | 1850x600 EAG<br>2000x2000 SAG<br>500x500 SAG<br>350x350 SAG<br>150x150 SAG &<br>200x200 SAG ard<br>in Addendum 2<br>600x500 EAG<br>400x350 EAG<br>400x350 SAG ard<br>the drawings/loca     |

| Final Response  |
|---|
|   |
|   |
|   |
| oxes are considered as duct fittings and are t<br>d in the rate of the ductworks.                             |
| fer to SCRP-TS 600_Annex A, Sub-Clause<br>em 1(b), which states that rate of ductworks<br>ade (among others): |
| fittings and stiffener/s;   |
| SED, 1000x400 SED, 1200x500 SED & SED were already included in the BOQ  |
| Addendum 2  |
|   |

and are to

boxes are considered as duct fittings and are uded in the rate of the ductworks.

efer to SCRP-TS 600 Annex A, Sub-Clause tem 1(b), which states that rate of ductworks ude (among others):

fittings and stiffener/s;

SPAD is not shown in plan. Please provide the *location of the items.* 

EAG 00 SAG **SAG SAG** SAG & SAG are already included in the BOQ issued *dum 2* **EAG EAG** SAG are not shown in plan. Please provide ngs/location of the items.

| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request   |   |
|----------|-----|----------|----------|------------------|----------------------------------|--|---|
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Motorized Damper<br>2200 x 500<br>1000 x 400<br>Fire Dampers<br>4750 x 1500 FD<br>1500 x 1350 FD<br>3000 x 1500 FD<br>1000 x 700 FD<br>1300 x 1300 FD<br>300 x 250 FD  | 2200x500 1<br>1000x400<br>4750x1500<br>1500x1350<br>are alread<br>3000x1500<br>1000x700<br>1300x1300<br>300x250 F<br>drawings/lo                      |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>FANS   | SEF-01 &<br>issued in A   |
| S-05     | 2   | Volume 2 | _        | -                | NSCR-DWG-PTA-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Air Ducts<br>PLENUM 2400 x 1600 mm<br>PLENUM 1650 x 550 mm<br>PLENUM 1200 x 400 mm<br>PLENUM 1150 x 400 mm<br>PLENUM 1150 x 350 mm<br>PLENUM 900 x 350 mm<br>PLENUM 900 x 300 mm<br>PLENUM 900 x 500 mm<br>Smoke Exhaust Ducts<br>PLENUM 3950 x 1500<br>PLENUM 3950 x 1500<br>PLENUM 2850 x 1500<br>PLENUM 1500 x 1200<br>1000 x 450 SED<br>900 x 450 SED<br>900 x 450 SED<br>900 x 450 SED<br>700 x 350 SED<br>700 x 350 SED<br>700 x 350 SED | Plenum bo<br>be included<br>Please ref<br>605.1.1, Ita<br>shall inclu<br>(b) Duct fi<br>1000x450<br>SED & 600<br>BOQ issue<br>700x200 S<br>drawings/l |

0 MD 00 MD 500 FD & 50 FD ady included in the BOQ issued in Addendum 2

500 FD 00 FD 300 FD & 0 FD are not shown in plan. Please provide the s/location of the items.

& *PF-01* were already included in the BOQ Addendum 2

boxes are considered as duct fittings and are to led in the rate of the ductworks.

efer to SCRP-TS 600\_Annex A, Sub-Clause Item 1(b), which states that rate of ductworks Jude (among others):


*fittings and stiffener/s;* 

0 SED, 900x450 SED, 700x450 SED, 700x350 00x350 SED were already included in the 1ed in Addendum 2

SED is not shown in plan. Please provide the *Acception of the items.* 

| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request  | Final Response  |
|----------|-----|----------|----------|------------------|----------------------------------|---|---|
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-BIN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Pressurization Duct System<br>SPAD 950 x 800 mm<br>PLENUM 2500 x 2200 mm        | <ul> <li>"Plenum boxes are considered as duct fittings and are to be included in the rate of the ductworks.</li> <li>Please refer to SCRP-TS 600_Annex A, Sub-Clause 605.1.1, Item 1(b), which states that rate of ductworks shall include (among others):</li> <li>(b) Duct fittings and stiffener/s;</li> <li>950x800 SPAD is already included in the BOQ issued in Addendum 2</li> </ul> |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-PTA-ME                  | 400 x 350 EAG<br>2000 x 2000 SAG<br>500 x 500 SAG<br>400 x 350 SAG<br>350 x 350 SAG<br>150 x150 SAG   | 600x500 EAG,<br>2000x2000 EAG,<br>350x350 SAG,<br>150x150 SAG &<br>200x200 SAG were already included in the BOQ issued<br>in Addendum 2<br>1850x600 EAG<br>400x350 EAG<br>500x500 EAG &<br>400x350 SAG are not shown in plan. Please provide<br>the drawings/location of the items.   |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-PTA-ME                  | Motorized Damper<br>1850 x 500 MD<br>1600 x 500 MD<br>1600 x 450 MD<br>900 x 400 MD<br>Fire Dampers<br>3950 x 1500 FD<br>3000 x 1500 FD<br>2850 x 1500 FD<br>2600 x 1000 FD<br>2400 x 1600 FD | 1850x500 MD,<br>900x400 MD,<br>3950x500 FD,<br>2850x1500 FD<br>2600x1000 FD &<br>1500x1200 FD are already included in the BOQ issued<br>in Addendum 2<br>1600x500 MD<br>1600x450 MD<br>3000x1500 FD<br>2400x1600 FD &<br>1300x1300 FD are not shown in plan. Please provide<br>the drawings/location of the items.  |

| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request   |  |
|----------|-----|----------|----------|------------------|----------------------------------|--|--|
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-PTA-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>FANS<br>SEF-01: Axial Inline Type Smoke Exhaust Fan for Unventilated<br>Area at Concourse Level, Airflow: 4232 L/S and Static Pressure<br>of 250PA - (6 UNITS)<br>PF-01 : Stair Pressurization - (4 UNITS)   | SEF-01 & PF-01<br>issued in Addendu  |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-BIN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Air Ducts<br>PLENUM 2400 x 1600 mm<br>PLENUM 1800 x 1600 mm<br>PLENUM 1000 x 400 mm<br>PLENUM 1050 x 350 mm<br>Smoke Exhaust Ducts<br>PLENUM 4750 x 1500<br>PLENUM 3300 x 1500<br>PLENUM 2650 x 1300<br>PLENUM 1500 x 1200<br>2200 x 500 SED<br>1700 x 500 SED<br>1250 x 500 SED<br>1200 x 500 SED<br>1200 x 500 SED | Plenum boxes are<br>be included in the<br>Please refer to SC<br>605.1.1, Item 1(b),<br>shall include (amo<br>(b) Duct fittings a<br>2200x500 SED, 1<br>1250x500 SED, 1<br>already included i |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-BIN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Pressurization Duct System<br>SPAD 950 x 800 mm<br>PLENUM 2500 x 2200 mm   | "Plenum boxes an<br>to be included in t<br>Please refer to SC<br>605.1.1, Item 1(b)<br>shall include (amo<br>(b) Duct fittings a<br>950x800 SPAD is<br>Addendum 2                            |



| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary) | Clarification<br>Request   |  |
|----------|-----|----------|----------|------------------|----------------------------------|--|--|
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-BIN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>AC Grilles & Diffuser<br>1850 x 600 EAG<br>600 x 500 EAG<br>400 x 350 EAG<br>2000 x 2000 SAG<br>500 x 500 SAG<br>400 x 350 SAG<br>350 x 350 SAG<br>150 x150 SAG<br>200 X 200 SAG                             | 1850x600<br>2000x2000<br>350x350 S<br>200x200 S<br>in Addendu<br>600x500 E<br>400x350 E<br>500x500 S<br>400x350 S<br>150x150 S<br>the drawin           |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-BIN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Motorized Damper<br>2200 x 500 MD<br>1600 x 500 MD<br>750 x 450 MD<br>Fire Dampers<br>4750 x 1500 FD<br>3300 x 1500 FD<br>2650 x 1300 FD<br>1500 x 1200 FD<br>1300 x 1300 FD<br>800 x 800 FD<br>750 x 250 FD | 2200x500<br>1600x500<br>750x450 N<br>4750x1500<br>3300x1500<br>2650x1300<br>1500x1200<br>Addendum<br>800x800 I<br>750x250 I<br>1300x1300<br>the drawin |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-BIN-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>FANS<br>SEF-01: Axial Inline Type Smoke Exhaust Fan for Unventilated<br>Area at Concourse Level, Airflow: 5546 L/S and Static Pressure<br>of 250PA - (6 UNITS)<br>PF-01 : Stair Pressurization - (4 UNITS)   | SEF-01 &<br>issued in A  |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SRO-ME                  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Air Ducts<br>PLENUM 2400 x 1600 mm<br>PLENUM 1800 x 1600 mm<br>PLENUM 1050 x 450 mm<br>PLENUM 1050 x 350 mm  | Plenum bo<br>be included<br>Please ref<br>605.1.1, Ita<br>shall inclu<br>(b) Duct f  |

| Final Response   |
|--|
| ) EAG,<br>00 SAG,<br>SAG &   |
| SAG are already included in the BOQ issued<br>dum 2  |
| EAG<br>EAG<br>SAG<br>SAG &   |
| SAG are not shown in plan. Please provide<br>ngs/location of the items.  |
| 9 MD,<br>9 MD,<br>MD<br>90 FD,   |
| 00 FD<br>00 FD &<br>00 FD are already included in the BOQ in<br>m 2  |
| FD<br>FD &<br>00 FD are not shown in plan. Please provide<br>ngs/location of the items.                        |
| & <b>PF-01</b> were already included in the <b>BOQ</b><br>Addendum 2   |
| oxes are considered as duct fittings and are to<br>ed in the rate of the ductworks.                            |
| fer to SCRP-TS 600_Annex A, Sub-Clause<br>tem 1(b), which states that rate of ductworks<br>ude (among others): |
| fittings and stiffener/s.  |

| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary)   | Clarification<br>Request   |   |
|----------|-----|----------|----------|------------------|--|--|---|
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SRO-ME  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Fire Dampers<br>1300 x 1300 FD   | 1300x1300<br>the drawin <sub>t</sub>  |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-FS-6612, NSCR-<br>DWG-SRO-FS-6612, NSCR-DWG-<br>BIN-FS-6612, NSCR-DWG-PTA-FS-<br>6612 | Water Tank Piping is consistently 100 mm according Pump<br>Room Layout but there is no 100 mm Pipe in the BOQ. May we<br>add these as Line Items under Sundries  | Pipe System<br>the rate of a<br>Please refe<br>617.1.1, Ite<br>shall includ<br>(c) Pipes, i   |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-FS-6612, NSCR-<br>DWG-SRO-FS-6612, NSCR-DWG-<br>BIN-FS-6612, NSCR-DWG-PTA-FS-<br>6612 | The Following Items not present in the BOQ:<br>Control Valve<br>Pressure Gauge<br>Gate Valve OS&Y<br>Check Valve<br>Test Valves<br>May we add these items under Sundries?  | Valves and<br>are to be in<br>Please refe<br>632.1.1, Ite<br>Tanks & P<br>1(c) Pipes,<br>2(b) Pipe f<br>valves; and<br>2(d) Piping<br>with tempe<br>discharge p |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-FS-6618, NSCR-<br>DWG-SRO-FS-6608, NSCR-DWG-<br>BIN-FS-6618, NSCR-DWG-PTA-FS-<br>6608 | The Fire Department Connection and Test Header Connection<br>are not included in the BOQ. May we add these are additional<br>line items under Sundries?  | Fire Depar<br>Connection<br>Hose Syste  |
| S-05     | 2   | Volume 2 | -        | -                | NSCR-DWG-SPO-PL NSCR-DWG-<br>SRO-PL, NSCR-DWG-BIN-PL,<br>NSCR-DWG-PTA-PL                           | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Water Distribution System<br>Water Distribution Pipe GI 50 mm<br>Water Distribution Pipe GI 75 mm<br>Water Distribution Pipe 20 mm<br>Gate Valve 20 mm<br>Gate Valve 75 mm | 75 mm, 50<br>water supp<br>already inc<br>Technical<br>shall be PF<br>Clause 607  |

### **Final Response**

00 FD are not shown in plan. Please provide ings/location of the items.

em for the Water Tanks are to be included in f the Pumps.

*efer to SCRP-TS 600\_Annex A, Sub-Clause (tems 1(c), which states that rate of Pumps (ude (among others):* 

, including fittings and accessories.

nd Accessories for the Water Tanks and pumps included in the rate of the Tanks & Pumps.

efer to SCRP-TS 600\_Annex A, Sub-Clause (tems 1(c), 2(b) & 2(d) which states that rate of Pumps shall include (among others):

rs, including fittings and accessories; e fittings and accessories, including gate nd

ing from fire water tank unto Isolation Valve oer switch and from Test Valve Manifold valve pipe joint of fire pump assembly.

artment Connection and Test Header on is the same as item 630(8) Stand Pipe and tem.

Omm & 20mm diameter pipes for domestic pply and 75mm & 20mm gate valves were included on the BOQ issued in Addendum 2

al Specification for domestic water supply line PPR PN-20. Please refer to SCRP-TS 600 Sub-07.2.3.

| Packages | Vol | Sec      | Page No.   | Clause No./Title             | Reference Text<br>(if necessary)  | Clarification<br>Request  |  |
|----------|-----|----------|--|------------------------------|---|---|--|
| S-05     | 2   | Volume 2 | -  | -                            | NSCR-DWG-SPO-PL NSCR-DWG-<br>SRO-PL, NSCR-DWG-BIN-PL,<br>NSCR-DWG-PTA-PL  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Sanitary Works<br>Floor Drain, 50mm<br>Canopy Drain, 100mm<br>Floor Cleanout, 100mm<br>Floor Cleanout, 80mm<br>Floor Cleanout, 80mm<br>Ground Cleanout, 50mm<br>Ground Cleanout, 250mm<br>Ceiling Cleanout, 100mm<br>Ceiling Cleanout, 40mm<br>Ceiling Cleanout, 32mm<br>Ceiling Cleanout, 25mm | 50mm Floo<br>issued in A<br>100mm Ca<br>provide the<br>Cleanouts<br>included in<br>Please refe<br>607.1.1, wh<br>include Pip<br>pipe, includ<br>and installa |
| S-05     | 2   | Volume 2 | -  | -                            | NSCR-DWG-SPO-PL NSCR-DWG-<br>SRO-PL, NSCR-DWG-BIN-PL,<br>NSCR-DWG-PTA-PL  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Waste Water Pipe 75 mm<br>Vent Pipe 75 mm<br>Stainless Rain Water Pipe 250 mm   | 75 mm dian<br>75 mm dia<br>250 mm di<br>already inc  |
| S-05     | 2   | Volume 2 | -  | -                            | NSCR-DWG-SPO-PL NSCR-DWG-<br>SRO-PL, NSCR-DWG-BIN-PL,<br>NSCR-DWG-PTA-PL  | Please clarify the type of Waste Water Treatment Plant to be<br>used, if a specific type is required  | No specific<br>requiremen  |
| S-05     | 2   | Volume 2 | NSCR-DWG-<br>SPO-EL-5201<br>/ 02<br>NSCR-DWG-<br>PTA-EL-5201<br>/ 02<br>NSCR-DWG-<br>BIN-EL-5201<br>/ 02<br>NSCR-DWG-<br>SRO-EL-5201<br>/ 02 | -                            | San Pedro Station Cable Containment<br>Layout Ground Flr and Concourse<br>Level<br>Pacita Station Cable Containment<br>Layout Ground Flr & Concourse<br>Level<br>Binan Station Cable Containment<br>Layout Ground Flr & Concourse<br>Level<br>Starosa Station Cable Containment<br>Layout Ground Flr & Concourse<br>Level | Please confirm the size of Cable tray, in DWG it is 900mm2 but<br>in BOQ it is 600mm2.  | Cable Tray<br>600mm for<br>mentioned<br>Please refe<br>pay item as<br>PIN 707(1)<br>100mm(H).  |
| S-05     | 2   | Volume 2 | -  | Electrical<br>Specifications | Spare Part List   | Please provide Spare part list and no item in BOQ.  | Please refer<br>700_Annex<br>parts and/o<br>Cost of spa<br>in the cost<br>extra stocks   |

#### **Final Response**

oor Drain are already included on the BOQ Addendum 2

Canopy Drain not shown in plan. Please he drawings/location of the items.

ts are considered as pipe fittings and to be in the rate of the Piping works.

efer to SCRP-TS 600\_Annex A, Sub-Clause which states that rate of Tanks & Pumps shall Pipes, fittings and accessories for each type of uding approved allowance for wastage; supply llation.

ameter Waste Water Pipe liameter Vent Pipe diameter Stainless Rain Water Pipe were ncluded on the BOQ issued in Addendum 2

ic type is required as long as it meets the ents of the specifications.

ay is 900mm for Bill Nos. 4-1, 4-2, & 4-3; and for Bill No. 4-4 in accordance with the d drawings.

efer to **BOQ**o in Addendum 2, which includes as follows:

(1)a --- Cable Tray w/ Cover, 900mm(W) x I).

fer to provisions in the TS 700 and SCRP\_TS ex A for pay items to be provided with spare Vor extra stocks.

| Packages | Vol | Sec  | Page No.                              | Clause No./Title                               | Reference Text<br>(if necessary) | Clarification<br>Request  |  |
|----------|-----|--|---------------------------------------|--|----------------------------------|---|--|
| S-05     | 1   | Volume 1-<br>Section 2, Bid<br>Data Sheet,<br>Part C ITB<br>13.4 | -                                     | Alternative<br>technical solution              |                                  | Please confirm if this clause includes any proposal to change<br>from precast to cast-in-situ driven mainly by improving<br>constructability. An example of which is precast deck slab<br>instead of cast-in-situ on steel bridges. | No alterna<br>during Bid<br>clauses for<br>implement   |
| S-05     | 2   | Volume 2   | NSRP-DWG-<br>VIA05-ST-<br>0101 to 106 | Bearing Type 2                                 | -                                | With reference to the Pier Schedule, there is a bearing type 2, but<br>No details were found in the drawings. Please advice.  | No details<br>2 bearings<br>as per Note<br>0781 Rev 2<br>All Bearin<br>the require<br>submitted t<br>fabrication |
| S-05     | 2   | Volume 2   | NSRP-DWG-<br>VIA00-ST-<br>0781        | Bearing Type 1                                 | -                                | A type 3 elastomer bearing in table 7 of drawing NSRP-DWG-<br>VIA00-ST-0781 is found. Please confirm where should adopt<br>this details.  | Type 3 in t<br>Type 2.<br>In the pier<br>11.5m wide<br>Type 2 app<br>segmental<br>NSRP-DW<br>Addendum            |
| S-06     | 3   | Volume 3-<br>Section 8   | PCC7                                  | KD 03-1 Receiving<br>Substations (S7 S8<br>S9) | -                                | Please confirm the minimum requirement to achieve this key date. Does it include the building beside substation (i.e. Rectifier)?   | The requir<br>preparation  |

### **Final Response**

native technical solution shall be permitted Bid. The Contractor may follow relevant FIDIC For value engineering during contract ntation.

Is have been provided in the drawings for Type gs since the contractor will design the bearings fote #3 indicated in NSRP-DWG-VIA00-STv 21.


ings shall be designed by the contractor as per rements of AASHTO LRFD 2016 and shall be l to the Engineer for approval prior to on.

the drawing shall be revised to Type 1 and

ier schedule, Type 1 applies to 10.3m and ide precast segmental box girder. applies to 6.3m and 5.1m wide precast al box girder. DWG-VIA00-ST-0781 shall be revised in am 3

irements to achieve Key Date is ready for ion works for receiving electricity

|          |     |                        |          |   |  | fullification requests (Butten of   |  |
|----------|-----|------------------------|----------|---|--|---|--|
| Packages | Vol | Sec                    | Page No. | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
| S-06     | 3   | Volume 3-<br>Section 8 | PCC7     | KD 02-1 Complete<br>a minimum and<br>continuous length<br>of 3,000<br>metres on the<br>viaduct where it<br>passes through at<br>least<br>one of the stations<br>KD 02-2 Complete<br>a minimum and<br>continuous length<br>of 6,000<br>metres within any<br>viaduct section<br>KD 02-3<br>Completion of the<br>remaining viaduct<br>sections<br>(approximately<br>2.51 km) |  | Please confirm the minimum requirement to achieve this Key<br>Dates. Is it the Cast-in-Situ Upstand, Parapet or the Viaduct<br>Segment Instalaltion?            | All works<br>protective  |
| S-06     | 2   | Volume 2               | -        | Cross Hole Sonic<br>Logging Test  | Cross Hole Sonic Logging Test  | Please clarify if all bored piles will includes BI Pipes and the<br>owner has the prerogative to which piles to test for cross hole<br>sonic log.               | As per TS<br>tube for C<br>noted, to j   |
| S-06     | 2   | Volume 2               | -        | -   | NSCR-DWG-BAN-FS-6612, NSCR-<br>DWG-CAB-FS-6612, NSCR-DWG-<br>CAL-FS-6612 | Water Tank Piping is consistently 100 mm according Pump<br>Room Layout but there is no 100 mm Pipe in the BOQ. May we<br>add these as Line Items under Sundries | Pipe Syste<br>the rate of<br>Please re<br>617.1.1, It<br>shall inclu<br>(c) Pipes, |



(c) Pipes, including fittings and accessories.

| Packages | Vol | Sec      | Page No. | Clause No./Title | Reference Text<br>(if necessary)   | Clarification<br>Request   |  |
|----------|-----|----------|----------|------------------|--|--|--|
| S-06     | 2   | Volume 2 | -        | -                | NSCR-DWG-BAN-FS-6612, NSCR-<br>DWG-CAB-FS-6612, NSCR-DWG-<br>CAL-FS-6612   | The Following Items not present in the BOQ:<br>Control Valve<br>Pressure Gauge<br>Gate Valve OS&Y<br>Check Valve<br>Test Valves<br>May we add these items under Sundries?  | Valves and<br>are to be in<br>Please refe<br>632.1.1, Ite<br>Tanks & Pu<br>1(c) Pipes,<br>2(b) Pipe fu<br>valves; and<br>2(d) Piping<br>with temper<br>discharge p |
| S-06     | 2   | Volume 2 | -        | -                | NSCR-DWG-BAN-FS-6618, NSCR-<br>DWG-CAB-FS-6608, , NSCR-DWG-<br>CAL-FS-6608 | The Fire Department Connection and Test Header Connection<br>are not included in the BOQ. May we add these are additional<br>line items under Sundries?  | Fire Depart<br>Connection<br>Hose Syster   |
| S-06     | 2   | Volume 2 | -        | -                | NSCR-DWG-BAN-PL, NSCR-DWG-<br>CAB-PL, , NSCR-DWG-CAL-PL                    | According to Drawings and Equipment Schedule, there are 12<br>Water Heaters in ALA and 1 in MUN. BOQ only reflects 6 in<br>ALA and 0 in MUN.   | Quantity of<br>already cor   |
| S-06     | 2   | Volume 2 | -        | -                | NSCR-DWG-BAN-PL, NSCR-DWG-<br>CAB-PL, NSCR-DWG-CAL-PL                      | The following items were found in the Drawings but not included<br>in the BOQ . May we add the following Items which are in the<br>Layout Plans & Equipment Schedule but not reflected in the<br>BOQ? .<br>Water Distribution System<br>Water Distribution Pipe GI 50 mm<br>Water Distribution Pipe GI 75 mm<br>Water Distribution Pipe 20 mm<br>Gate Valve 20 mm<br>Gate Valve 75 mm                          | 75 mm, 50n<br>water suppl<br>already incl<br>Technical<br>shall be PP<br>Clause 607.   |
| S-06     | 2   | Volume 2 | -        | -                | NSCR-DWG-BAN-PL, NSCR-DWG-<br>CAB-PL, NSCR-DWG-CAL-PL                      | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Sanitary Works<br>Floor Drain, 50mm<br>Canopy Drain, 100mm<br>Floor Cleanout, 100mm<br>Floor Cleanout, 80mm<br>Floor Cleanout, 80mm<br>Ground Cleanout, 50mm<br>Ground Cleanout, 250mm<br>Ceiling Cleanout, 150mm<br>Ceiling Cleanout, 100mm<br>Ceiling Cleanout, 40mm<br>Ceiling Cleanout, 32mm | 50mm Floo<br>issued in Ad<br>100mm Ca<br>provide the<br>Cleanouts<br>included in<br>Please refe<br>607.1.1, wh<br>include Pip<br>pipe, incluad<br>and installa     |

### **Final Response**

d Accessories for the Water Tanks and pumps included in the rate of the Tanks & Pumps.

fer to SCRP-TS 600\_Annex A, Sub-Clause tems 1(c), 2(b) & 2(d) which states that rate of Pumps shall include (among others):

s, including fittings and accessories; fittings and accessories, including gate ad

ng from fire water tank unto Isolation Valve per switch and from Test Valve Manifold valve pipe joint of fire pump assembly.

artment Connection and Test Header on is the same as item 630(8) Stand Pipe and tem.

of Water Heaters in ALA and MUN were orrected in the BOQ issued in Addendum 2

0mm & 20mm diameter pipes for domestic ply and 75mm & 20mm gate valves were acluded on the BOQ issued in Addendum 2

Il Specification for domestic water supply line PR PN-20. Please refer to SCRP-TS 600 Sub-07.2.3.

oor Drain are already included on the BOQ Addendum 2

Canopy Drain not shown in plan. Please the drawings/location of the items.

ts are considered as pipe fittings and to be in the rate of the Piping works.

fer to SCRP-TS 600\_Annex A, Sub-Clause which states that rate of Tanks & Pumps shall ipes, fittings and accessories for each type of uding approved allowance for wastage; supply llation.

| Packages | Vol | Sec   | Page No.   | Clause No./Title  | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
|----------|-----|---|--|---|--|---|--|
| S-06     | 2   | Volume 2  | -  | -   | NSCR-DWG-BAN-PL, NSCR-DWG-<br>CAB-PL, NSCR-DWG-CAL-PL  | The following items were found in the Drawings but not included<br>in the BOQ . Please confirm and advise.<br>Waste Water Pipe 75 mm<br>Vent Pipe 75 mm<br>Stainless Rain Water Pipe 250 mm   | 75 mm dian<br>75 mm dia<br>250 mm di<br>already inc  |
| S-06     | 2   | Volume 2  | -  | -   |  | Please clarify the type of Waste Water Treatment Plant to be<br>used, if a specific type is required  | No specific<br>requiremen  |
| S-06     | 2   | Volume 2  | NSCR-DWG-<br>CAB-EL-<br>5201 / 02<br>NSCR-DWG-<br>BAN-EL-<br>5201 / 02<br>NSCR-DWG-<br>CAL-EL-5201<br>/ 02 | -   | Cabuyao Station Cable Containment<br>Layout Ground Flr and Concourse<br>Level<br>Banlic Station Cable Containment<br>Layout Ground Flr & Concourse<br>Level<br>Calamba Station Cable Containment<br>Layout Ground Flr & Concourse<br>Level | Please confirm the size of Cable tray, in DWG it is 900mm2 but<br>in BOQ it is 600mm2.  | Cable Tray<br>600mm for<br>drawings.<br>Please refe<br>includes pa<br>PIN 707(1<br>100mm(H)                      |
| S-06     | 2   | Volume 2  | -  | Electrical<br>Specifications  | Spare Part List  | Please provide Spare part list and no item in BOQ.  | Please refe<br>700_Annex<br>parts and/o<br>Cost of spo<br>in the cost<br>extra stock                             |
| S-06     | 1   | Volume 1-<br>Section 2, Bid<br>Data Sheet,<br>Part C ITB<br>13.4                | -  | Alternative<br>technical solution   | -  | Please confirm if this clause includes any proposal to change<br>from precast to cast-in-situ driven mainly by improving<br>constructability. An example of which is precast deck slab<br>instead of cast-in-situ on steel bridges. | No alterna<br>during Bid<br>clauses for<br>implementa  |
| S-06     | 1   | Volume 1<br>Section 4a bill<br>3 Part B.8<br>Item no<br>209(17) and<br>Volume 2 | -  | Steelworks – Steel<br>Tied Arch Bridge –<br>San Cristobal River<br>Crossing |  | There is weight of steel in Steel tied Arch Bridge discrepancy<br>between the BOQ and the drawings. The difference is more than<br>25%. Please review and amend the BQ accordingly.   | BOQ will b   |
| S-06     | 2   | Volume 2  | NSRP-DWG-<br>VIA06-ST-<br>0101 to 106  | Bearing Type 2  | _  | With reference to the Pier Schedule, there is a bearing type 2, but<br>No details were found in the drawings. Please advice.  | No details<br>2 bearings<br>as per Note<br>0781 Rev 2<br>All Bearin<br>the require<br>submitted t<br>fabrication |

#### **Final Response**

ameter Waste Water Pipe liameter Vent Pipe diameter Stainless Rain Water Pipe were ncluded on the BOQ issued in Addendum 2

ic type is required as long as it meets the ents of the specifications.

ay is 900mm for Bill Nos. 4-1, 4-2, & 4-3; and for Bill No. 4-4 in accordance to mentioned

efer to BOQ issued in Addendum 2, which pay item as follows:

(1)a --- Cable Tray w/ Cover, 900mm(W) x H).

fer to provisions in the TS 700 and SCRP\_TS ex A for pay items to be provided with spare l/or extra stocks.

pare parts and/or extra stock shall be included st of the pay items requiring spare parts and/or cks as specified in the TS and TS Annex A.

ative technical solution shall be permitted id. The Contractor may follow relevant FIDIC or value engineering during contract atation.

be revised and issued in Addendum 3

s have been provided in the drawings for Type as since the contractor will design the bearings ate #3 indicated in NSRP-DWG-VIA00-ST-21.

ings shall be designed by the contractor as per rements of AASHTO LRFD 2016 and shall be I to the Engineer for approval prior to on.

| Packages | Vol | Sec                    | Page No.                       | Clause No./Title                            | Reference Text<br>(if necessary) | Clarification<br>Request  |  |
|----------|-----|------------------------|--------------------------------|---|----------------------------------|---|--|
| S-06     | 2   | Volume 2               | NSRP-DWG-<br>VIA00-ST-<br>0781 | Bearing Type 1                              | -                                | A type 3 elastomer bearing in table 7 of drawing NSRP-DWG-<br>VIA00-ST-0781 is found. Please confirm where should adopt<br>this details.  | Type 3 in th<br>Type 2.<br>In the pier<br>11.5m wide<br>Type 2 app<br>segmental to<br>NSRP-DW                            |
| S-04     | 2   | -                      | -                              | Drawings /<br>Structural                    | Structural Drawings              | Please confirm the following:<br>The tag for the slab at Platform Floor Level along Grid A and<br>Grid F is S20, at Drawing Sheet NSRP-DWG-ALA-ST-<br>4141.Refer to <u>"ANNEX B"</u>  | The highlig  |
| S-04     | 2   | -                      | -                              | Drawings /<br>Architectural                 | Architectural Drawings           | Please provide of the following:<br>a.Blow up section of PWD Toilet @ Ground Level, at Drawing<br>Sheet<br>NCRP-DWG-ALA-ST-4523. Refer to <u>"ANNEX C"</u><br>b.Blow up section of Male ,Female Shower Room & Male,<br>Female Driver's Toilet<br>at Concourse. Level. at Drawing Sheet NCRP-DWG-ALA-ST-<br>3518.<br>Refer to <u>"ANNEX D"</u> | For annex<br>NSRP-DW<br>3537 rev. 2<br>For annex<br>NSRP-DW<br>3539 rev. 2   |
| S-04     | 2   | -                      | -                              | Drawings /<br>Architectural                 | Architectural Drawings           | Please confirm the following:<br>Material to be used for the base of the countertop, if concrete<br>substrate or angular bar. Refer to <u>"ANNEX E"</u>   | Granite sla<br>wall for ma<br>hung type l<br>purpose toi<br>3101 and N<br>lavatories b                                   |
| S-04     | 1   | Volume 1 Sec.<br>1-3,5 | EQC 16<br>&<br>Page 53/63      | 1.4 Step 4 –<br>Ranking of Bidders<br>1.4.3 | -                                | The bidder understands that the evaluation of multiple contract<br>for CP S-04, S-05, S-06, S-07 and CP S-01, C-S02 will be<br>independent from each other. Please confirm our understanding.   | Bids will be<br>package.<br>However, E<br>following a<br>3 EQC 1.4.<br>* Average<br>* Financia<br>* Equipme<br>* Personn |


# **Final Response** the drawing shall be revised to Type 1 and er schedule, Type 1 applies to 10.3m and de precast segmental box girder. pplies to 6.3m and 5.1m wide precast l box girder. WG-VIA00-ST-0781 shall be revised. lighted slabs on Annex B are S20. x C, please refer to detail of toilet sheet no. WG-ALA-AR-3536 and NSRP-DWG-ALA-AR-21 ex D, details are to be provide on sheet no. WG-ALA-AR-3538 and NSRP-DWG-ALA-AR-21.3 to be issued in Addendum 3 lab countertop with angular bar fixation on nale & female toilets and shower rooms; walle lavatory for PWD, and both for Multioilets; Please refer to NSRP-DWG-ALA-AR-NSRP-DWG-MUN-AR-3101 for type of s being used. rev. 21.2 be evaluated independently for each contract Bidder is reminded to pay attention to the aggregated requirements as stated in Section 4.2 and EQC 1.4.3 e annual construction turnover cial resources nent to be allocated, and

nel to be fielded

| Packages | Vol | Sec                    | Page No.                    | Clause No./Title        | Reference Text<br>(if necessary)  | Clarification<br>Request   |   |
|----------|-----|------------------------|-----------------------------|-------------------------|---|--|---|
| S-04     | 1   | Volume 1 Sec.<br>1-3,5 | ITB 5 & 6<br>&<br>Page 8/63 | 4. Eligible Bidders     | (e) a Bidder participates in more than<br>one bid in this bidding process, either<br>individually or as a partner in a Joint<br>Venture, except for alternative offers<br>permitted under ITB 13 of the<br>Bidding Document. This will result in<br>the<br>discualification of all Bids in which it | The bidder understands that this clause is specifically mentioned<br>for every single one package only and will not consider for all the<br>other packages which can be submitted as a combined package,<br>i.e.;<br>- Company A and B will be participating to the Package 5 as a JV<br>- Company A and C will be participating to the Package 1 as a JV<br>We understand that there will be no conflict of interest between  | The conflic<br>bidding pro<br>The quoted<br>conflict of |
| S-04     | 1   | Volume 1 Sec.<br>1-3,5 | ITB 8<br>&<br>Page 11/63    | 10 . Language of<br>Bid | are part<br>of the Bid may be in another language<br>provided they are accompanied by an<br>accurate translation of the relevant<br>passages in the language specified in   | The bidder understands that the all the documents which will<br>comprise the bidder's submission, shall be in English and where<br>the supporting documents are not in English originally, the<br>accurate translation of these shall be attached. However there is<br>no validation condition for these foreign language documents<br>such as key personnel supplemental documents: diploma,<br>certificates, etc. We understood that only the accurate translation<br>of these supplement documents will be valid & accpeted by your<br>management without any apostille approval. Please confirm. | Bidder's un<br>comprising<br>ITB 20.2                   |


| Final Response  |
|---|
| lict of interest as stated in ITB 4.3 refers to the<br>rocess a single package.<br>ed scenario of bidding is not classified as<br>f interest under ITB 4.3. |
| understanding is correct. All documents<br>1g the Bid shall be signed in accorance with   |

| Packages | Vol | Sec   | Page No.  | Clause No./Title            | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
|----------|-----|---|-----------|-----------------------------|--|---|--|
| S-04     | 1   | Volume 1,<br>Section 4  | 33 of 130 | BoQ T/S No. 507             | W=200mm Expansion joint and joint cover assemblies   | Please provide detail drawings for types of expansion joints.   | For Expans<br>STA-AR-35  |
| S-04     | 2   | Volume 2,<br>Section 6  | 15 of 116 | GS 103                      | Possession of Site and Contractor's<br>Mobilization  | Please provide the exemption for heavy equipment mobilization during daylight.  | Please refe  |
| S-04     | 2   | -   | -         | Drawings /<br>Architectural | Architectural Drawings   | Please confirm which detail will be govern of the following:<br>a. If wall hung lavatory or with granite countertop. Location is @<br>Concourse Level Male & Female Staff Toilet - Muntinlupa<br>Station. Refer to <u>"ANNEX F"</u> .<br>NSRP-DWG-MUN-AR-3403 to 3404<br>b . If wall hung lavatory or with granite countertop. Location is<br>@ Ground Level PWD Toilet - Muntinlupa Station. Refer to<br><u>"ANNEX G"</u><br>NSRP-DWG-MUN-AR-3533<br>c. If wall hung lavatory or with granite countertop. Location is @<br>Concourse Level Multi Purpose Toilet - Muntinlupa Station.<br>Refer to <u>"ANNEX H"</u><br>NSRP-DWG-MUN-AR-3537 | a. Wall-hur<br>be revised a<br>b. Wall-hu<br>will be revis<br>c.Wall-hur<br>be revised a   |
| S-04     | 2   | -   | -         | Drawings /<br>Architectural | Architectural Drawings   | <ul> <li>Please provide the Location of the following:</li> <li>a. 95mm x 905mm x 100mm Loading Dock Rubber Buffer @</li> <li>Parking Area - Muntinlupa Station.</li> <li>b. Door Sign and Building sign @ Substations.</li> <li>c. BRR @ Alabang and Muntinlupa Stations.</li> <li>d. Location of Plant Pot Glass Fiber Reinforced Concrete Ø 2m,</li> <li>H 3m. Refer to <u>"ANNEX I"</u></li> <li>NSRP-DWG-MUN-AR-3022.</li> </ul>   | a. Please se<br>3556 Rev. 2<br>b. Signage<br>drawings au<br>c. BFR is l<br>ALA (NSRI<br>Grids A-B f<br>rev. 21.2<br>d. Plant Po<br>required. |
| S-04     | 2   | Volume 2 &<br>Section 6 IB<br>General<br>Specification  | GS 38     | 114.2.6                     | In cases where it is necessary or<br>required by the Engineer, the<br>Contractor shall construct and<br>maintain temporary traffic ramps, and<br>furnish all the labour and materials<br>required. | Which BOQ item includes this payment? Please explain how the specified work will be paid.   | The tempor<br>which is pa  |
| S-04     | -   | Site Data - 19.<br>SCRP Site<br>Data Proposed<br>Site(s) for<br>Contractor -<br>SCRP Item<br>10.19 Sites for<br>Contractor -<br>Revised | -         | -                           | -  | We tried to contact the property owners for potential site areas<br>shared by the client, but some areas have changed ownership.<br>Please suggest new alternative site areas.  | The propos<br>required to  |



osed site is for reference only and the bidder is to allocate proposed site.

| Packages | Vol | Sec  | Page No.  | Clause No./Title   | Reference Text<br>(if necessary)  | Clarification<br>Request  |   |
|----------|-----|--|-----------|--|---|---|---|
| S-04     | 1   | Volume 1<br>Section 4<br>Bill of<br>Quantities                 | 19 of 130 | GS 118(12)   | Demolish Buildings/Structures,<br>dispose of arisings off-site unless<br>agreed otherwise with the Engineer   | Please confirm that the Employer shall provide the land<br>acquisition for alignment and inside of Right of Way as per<br>tender drawings.  | The employ  |
| S-04     | 1   | Volume 1<br>Section 4<br>Bill of<br>Quantities                 | 19 of 130 | GS 118(12)   | Demolish Buildings/Structures,<br>dispose of arisings off-site unless<br>agreed otherwise with the Engineer   | Please confirm that the Employer shall provide all relocation of<br>existing residences for alignment and inside of Right of Way as<br>per tender drawings.   | please refer<br>Clearing of   |
| S-04     | 1   | Volume 1<br>Section 4<br>Bill of<br>Quantities                 | 19 of 130 | GS 118(12)   | Demolish Buildings/Structures,<br>dispose of arisings off-site unless<br>agreed otherwise with the Engineer   | Please confirm that the contractor has the responsibility of all<br>demolish Buildings/Structures inside the Right of Way as per<br>tender drawings except land acquisition, relocation of residences,<br>and protection, or relocation of utilities.<br>If the Employer confirms this, the Employer shall provide the<br>detailed survey report of existing buildings/structures to estimate<br>the cost because the cost as a unit of a lump sum cannot be<br>calculated due to insufficient knowledge.<br>We would like to remind you that the detailed survey report of<br>existing buildings/structures shall consist of the amount, number,<br>conditions, floors and heights, construction materials, foundation<br>type, condition of materials and items inside the<br>buildings/structures, etc. Without the detailed survey report, price<br>analysis of this payment item is impossible.<br>Therefore, please provide the detailed survey report of existing<br>buildings/structures. | Please refe<br>has already<br>each respec   |
| S-04     | 1   | Volume 1<br>Section 4<br>Bidding Forms                         | BF 58     | Form EXP-1:<br>Contracts of<br>Similar Size and<br>Nature      | The exchange rate to be used to<br>calculate the value of the contract for<br>conversion to a specific currency<br>shall be the selling rate of the<br>Borrower's national bank on the date<br>of the contract. | The tenderer can use the exchange selling rates of Central Bank<br>in the country of the contract in case the exchange rates do not<br>exist in Borrower's national bank.<br>Please kindly confirm.   | Bidder sha<br>they used to<br>in the Borr   |
| S-04     | 1   | Volume 1<br>Section 4<br>Bidding Forms                         | BF 59     | Form EXP-2:<br>Construction<br>Experience in Key<br>Activities | Note: \$ equivalent based on the foreign exchange rate as of the same date and currency of the contract.  | The tenderer can use the exchange selling rates of Central Bank<br>in the country of the contract in case the exchange rates do not<br>exist in Borrower's national bank.<br>Please kindly confirm.   | Bidder sha<br>they used to<br>in the Borr   |
| S-04     | 1   | Volume 1 /<br>1.3b CP S-01<br>Vol.1A<br>Sec.4A BOQ<br>20200930 | Bill no.1 | GS104(4)   | Mobilisation of Contractor's<br>Accommodation   | We understand that after the contractor delivers the segment<br>moulds, machinery and equipment to the precast yard, payment<br>will be done under item GS104 (5) in Bill no.1. Please confirm.   | Please refe<br>GS104(5)<br>GS104(19)<br>Payment s<br>1. Lumpsu<br>for mobiliz,<br>2. Lump su<br>the contrac |



| Packages | Vol | Sec                        | Page No.   | Clause No./Title   | Reference Text<br>(if necessary)   | Clarification<br>Request  |  |
|----------|-----|----------------------------|--|--|--|---|--|
| S-06     | 2   | Vol 2<br>Book 1<br>(Civil) | NSRP-DWG-<br>BR215-ST-<br>0193-4                               | San Cristobal Arch<br>Bridge Arch Tie<br>Details Sheet 2-3 | 2 Sectional elevation – at – cable<br>anchorage on cable CL in NSRP-<br>DWG-BR215-ST-0193 /<br>1-7 in NSRP-DWG-BR215-ST-0194 | It is understood that the requirement of Structural Steel GRADE 345(50) shall be applied for both formwork tube, and hatch cover with applicable components. Please clarify.  | Yes, Struct<br>for both for              |
| S-06     | 1A  | Vol 1A<br>Sec.4A           | Bill no.3<br>PART B.8  | Steel Tied Arch<br>Bridge                                  | -  | Please clarify where to include coating qt'y as it is not included<br>in given BOQ.   | Please incl<br>item 209(1                |
| S-06     | 1A  | Vol 1A<br>Sec. 4A          | Bill no.5<br>PART<br>D   | River Bank<br>Protection<br>Works                          | NSRP-DWG-VIA00-ST-0701 /<br>NSRP-DWG-VIA06-ST-0035   | There is no item for sheet pile with concrete capping in given<br>BOQ. However, it is necessary to install sheet pile with concrete<br>capping where height of river bank protection is more than 5m<br>according to provided drawing.  | Installation<br>Cristobal R<br>ST-0701 w |
| S-06     | -   | 02_CP S-<br>06_VIA00       | NSRP-DWG-<br>VIA00-ST-<br>402                                  | CASTING CON.   | All exposed con'c surface:class 2<br>suface finish(anti-graffiti coating)  | "ALL EXPOSED CONCRETE SURFACES SHALL HAVE<br>CLASS 2 SURFACE FINISH TO THE PROJECT<br>SPECIFICATION AND ARE TO BE TREATED WITH AN<br>APPROVED ANTI-GRAFFITI COATING" is stated in the Note<br>5 of the drawing 'ST-402'.<br>Please confirm that this clause is applied for the pier column and<br>headstock only. | All exposed<br>column and                |
| S-06     | -   | 03_CP S-<br>06_VIA06       | NSRP-DWG-<br>VIA06-ST-<br>051<br>NSRP-DWG-<br>VIA06-ST-<br>106 | PIER TYPE  | -  | There is discripancy in design drawing.<br>- in NSRP-DWG-VIA06-ST-051 : Piers Type of DAT21 &<br>DAT22 seems Type P9<br>- in NSRP-DWG-VIA06-ST-106 : Piers Type of DAT21 &<br>DAT22 is written Type P1<br>Please kindly clarify which the bidder shall follow.  | Pier Sched<br>Type P9 in                 |

### **Final Response**

ctural Steel GRADE 345(50) shall be applied formwork tube, and hatch cover.

*iclude the cost of coating to the unit rate of pay* (17).

on of sheet pile with concrete capping for San River is not necessary. NSRP-DWG-VIA00will be revised and issued in Addendum 3

ed concrete surface is not limited to pier and head stock.

edule shall be revised showing the pier type as in Addendum 3